

Scope of Work for viewing project at Heislerville WMA:

This project requires the following services:

Replacing telephone poles (telephone poles are onsite but were dislocated during Sandy) around the border, re-grading the parking area and adding a 2” layer of crushed shell (2,200 sq ft)
Pushing debris from trails, filling geoblocks and fixing eroded edges along 300 linear ft of trail
regrading/repairing 138 sq ft of geoblock tread on trails by adding fill and grading trail edges
Replacing/repairing broken and sunken pavers on a 117 sq ft viewing platform

This project requires the following materials:

Clam shells for parking area and trails – enough to spread a 2” deep layer on existing parking area and 1 “ on trails
New pavers - 9
Sand for sunken pavers
Glue for pavers
Crushed stone for paver base – approximately 2 tons
Crushed concrete for trail repair – approximately 2 tons

Contact Person:

Laurie Pettigrew

NJ Division of Fish and Wildlife

8747 Ferry Rd

Millville, NJ 08332

Office: 856-785-0592

Fax: 856-785-0670