ADVERTISEMENT FOR BIDS

Project No: P1121-12 – Demolition of Dwellings

Location: 576 and 640 Bamford Ave.; 88 Claire Ave.; 122 Harriot St.; 661, 675 and 679 Lewis St.;

82 and 88 Port Reading Ave. and 7 Wedgewood Ave., Woodbridge, NJ - Middlesex

County

A NON-MANDATORY PRE-BID MEETING IS SCHEDULED FOR 10:00 A.M., OCTOBER 14, 2019. LOCATION: 88 CLAIRE AVENUE, WODBRIDGE, NJ. CONTACT PERSON: WILLIAM BYSTER (609) 984-4705

IT IS HIGHLY RECOMMENDED CONTRACTORS ATTEND THIS NON-MANDATORY PRE-BID MEETING.

Sealed proposals must be received and time-stamped in the Plan Room, Division of Property Management & Construction, 33 West State Street, 9th Floor, (PO Box 034) Trenton, NJ 08625 until 2:00 p.m. on October 29, 2019 for:

Single Bid (lump sum all trades)
General Construction (C008) or
General Construction/Alterations & Additions (C009) or
Demolition (C021)
\$338,848.

IN ACCORDANCE WITH N.J.S.A. 52:32-2, THIS PROJECT SHALL BE BID AS A SINGLE BID (LUMP SUM ALL TRADES). BIDDER MUST BE CLASSIFIED THEMSELVES OR NAME THEIR CLASSIFIED SUBCONTRACTOR(S) FOR THE FOLLOWING TRADE(S):

Demolition (C021) Plumbing (C030) Asbestos Removal / Treatment (C092)

FAILURE TO LIST CLASSIFIED SUBCONTRACTORS WILL DEEM THE BID NON-RESPONSIVE.

CLASSIFIED DPMC CONTRACTORS/SUBCONTRACTORS MAY BE FOUND AT DPMC'S WEBSITE LISTED BELOW:

http://www.state.nj.us/treasury/dpmc/contract_search.shtml

Bid Documents may be examined at the above address or obtained for a document fee based on the individual trade estimate shown above, as follows: Trade Estimate up to \$100,000 – No Fee, in excess of \$100,000 - \$65.00. An additional \$25.00 fee is required for mailing of bid documents. All fees are non-refundable and must be received by the Division before documents will be released. A company check payable to the "Treasurer, State of New Jersey" is required. Contact **Shawn Taylor at (609) 292-5229** for further information. Mailing address is as follows: Regular Mail (DPMC, P.O. Box 034, Trenton, NJ 08625) or Overnight Mail (DPMC, 33 West State St, 9th Fl, Trenton, NJ 08608).

Bidders must be classified by the Division under N.J.S.A. 52:35-1 et seq. and must submit bid security as provided in Instructions to Bidders and General Conditions revised December 2015. No bidder may withdraw his bid for 60 calendar days after the opening. The State may reject any and all bids.

Bidders are required to comply with the requirements of N.J.S.A. 10:5-31 et seq. and N.J.A.C. 17:27.

http://nj.gov/comptroller/sandytransparency/contracts/sandy/.

The contract resulting from this RFQ/RFP is subject to the requirements of Executive Order No. 125. Accordingly, the OSC will post a copy of the contract, including the RFQ/RFP, the winning bidder's proposal and other related contract documents for the above contract on the Sandy Transparency website.

In submitting its proposal, a bidder may designate specific information as not subject to disclosure. However, such bidder must have a good faith legal and/ or factual basis to assert that such designated portions of its proposal (i) are proprietary and confidential financial or commercial information or trade secrets or (ii) must not be disclosed to protect the personal privacy of an identified individual. The location in the proposal of any such designation should be clearly stated in a cover letter, and a redacted copy of the proposal should be provided.

The State reserves the right to make the determination as to what is proprietary or confidential, and will advise the winning bidder accordingly. The State will not honor any attempt by a winning bidder to designate its entire proposal as proprietary, confidential and/or to claim copyright protection for its entire proposal. In the event of any challenge to the winning bidder's assertion of confidentiality with which the State does not concur, the bidder shall be solely responsible for defending its designation.

This project is funded in whole or in part by Community Development Block Grant- Disaster Recovery (CDBG-DR) funds received from the U.S. Department of Housing and Urban Development (HUD). Bidder agrees to comply with all applicable Federal CDBG-DR laws, guidelines and standards in a manner satisfactory to the State of New Jersey and HUD, including but not limited to the requirements of Section 3 of the HUD Act of 1968.

Notice of Requirement for DUNS Number Registration

In accordance with 2CFR Part 200.213 "Suspension and Debarment", all vendors, contractors and subcontractors submitting proposals on federal FEMA and HUD funded projects will be required to register for a Data Universal Numbering System (DUNS) number in order to be eligible for a contract award. These regulations restrict awards, sub-awards and contracts with certain parties that are debarred, suspended, or otherwise excluded from or ineligible for participating in federal assistance programs or activities. In order to comply with this requirement, each consultant, prime contractor and sub-contractor must register in the System of Award Management (SAM) at http://www.sam.gov and register for a DUNS number at http://www.dnb.com/duns-number.html.

Be advised that firms doing work for the government or bidding on government contracts or proposals will need to get a D-U-N-S Number for each physical location of their business. Firms can get a D-U-N-S Number expedited for free if they are required to register with the federal government for a government funded contract and the firm may have the D-U-N-S number expedited at no cost.

Successful bidders will be required to submit to the Division of Property Management and Construction (DPMC) their DUNS number immediately after the bid due date and prior to contract award.

RICHARD M. FERRARA, ASSISTANT DEPUTY DIRECTOR CONTRACTS & PROCUREMENT DIVISION OF PROPERTY MANAGEMENT & CONSTRUCTION STATE OF NEW JERSEY DEPARTMENT OF THE TREASURY P. O. BOX 034 TRENTON, NJ 08625-0034

NON-MANDATORY PRE-BID CONFERENCE

PROJECT # P1121-12

LOCATION: Multiple Properties,

Woodbridge, NJ

DATE: October 14, 2019

TIME: 10:00 AM

CONTACT PERSON: William Byster

PHONE: 609-984-4705

MEETING LOCATION: 88 Claire Avenue

Woodbridge, NJ

NOTE: IT IS HIGHLY RECOMMENDED CONTRACTORS ATTEND

THIS NON-MANDATORY PRE-BID MEETING.

SPECIFICATION DEMOLITION OF DWELLINGS

640 Bamford Avenue 675 Lewis Street
576 Bamford Avenue 679 Lewis Street
88 Claire Avenue 82 Port Reading Avenue
122 Harriot Street 88 Port Reading Avenue
661 Lewis Street 7 Wedgewood Avenue

Woodbridge Township, Middlesex County, New Jersey

PROJECT NUMBER P1121-12 STATE OF NEW JERSEY

Honorable Philip D. Murphy, Governor Honorable Sheila Y. Oliver, Lieutenant Governor



DEPARTMENT OF THE TREASURY

Elizabeth Maher Muoio, State Treasurer

DIVISION OF PROPERTY MANAGEMENT AND CONSTRUCTION

Christopher Chianese, Director Richard Flodmand, Deputy Director

URS ARCHITECTS/ENGINEERS INC.

1255 Broad Street, Ste 201 Clifton, New Jersey 07013 Tel: 973.883.8500 Fax: 973.883.8501



State of New Jersey

PHILIP D. MURPHY
Governor

DEPARTMENT OF TREASURY
DIVISION OF PROPERTY MANAGEMENT & CONSTRUCTION
P O Box 034
TRENTON NJ 08625-0034

ELIZABETH MAHER MUOIO State Treasurer

CHRISTOPHER CHIANESE
Director

SHEILA Y. OLIVER
Lt. Governor

October 21, 2019

SUBJECT:

Bulletin "B" Dated October 21, 2019

PROJECT #:

P1121-12

DESCRIPTION:

Demolition of Dwellings

Various Properties

Woodbridge Township, Middlesex County, NJ

Gentlemen:

WE ARE FORWARDING A COPY OF THE ABOVE REFERENCED BULLETIN. PLEASE ACKNOWLEDGE RECEIPT BY RETURNING THIS FORM TO:

Division of Property Management and Construction

Attention: R. Ferrara Contracts & Procurement

PO Box 034

Trenton NJ 08625-0034 Fax #: 609-777-1970

Very truly yours,

Richard M. Ferrara
Assistant Deputy Director
Contracts and Procurement

Date Received

Firm Name

Address

Signature

Title

STATE OF NEW JERSEY DEPARTMENT OF TREASURY DIVISION OF PROPERTY MANAGEMENT AND CONSTRUCTION PO BOX 034, TRENTON, NJ 08625-0034

PROJECT #: **DPMC Blue Acres P1121-12**

Demolition of Dwellings

Various Properties

Woodbridge Township, Middlesex County, NJ

576 Bamford Ave.

675 Lewis St.

640 Bamford Ave.

679 Lewis St.

88 Claire Ave.

82 Port Reading Ave.

122 Harriot St.

88 Port Reading Ave.

661 Lewis St.

7 Wedgewood Ave.

A/E: URS / AECOM

DATE: October 21, 2019

BULLETIN "B"

Bidder must acknowledge receipt of this Bulletin on bid form in the space provided therefore.

This Bulletin is issued for the purpose of amending certain requirements of the original Contract Documents, as noted hereinafter, and is hereby made part of and incorporated in full force as part of the Contract Documents. Unless specifically noted or specified hereinafter, all work shall comply with the applicable provisions of the Contract Documents.

A) ATTACHMENTS

- 1. See attached Revised Bid Proposal Form for Contractor Use.
- 2. See attached Non-Mandatory Pre-Bid meeting minutes dated October 15, 2019.
- 3. See attached Non-Mandatory Pre-Bid meeting sign-in sheet dated October 15, 2019.

B) CONTRACTOR QUESTIONS

NO CONTRACTOR QUESTIONS RECEIVED

END OF BULLETIN B

REVISED BULLETIN B BID PROPOSAL FORM

STATE OF NEW JERSEY
DEPARTMENT OF TREASURY
DIVISION OF PROPERTY MANAGEMENT & CONSTRUCTION
P O BOX 034
TRENTON NEW JERSEY 08625-0034

The bid proposal is to be returned in the pre-addressed envelope and will be accepted no later than 2:00 p.m.,

October 29, 2019	after which time the bid proposals will be publicly opened and read.
FIRM NAME: (Please Type or Print) (Business Street Address ONLY – No P O Box)	
PROJECT NO	P1121-12
PROJECT:	Demolition of Residential Dwellings
LOCATION:	675 Lewis St., 679 Lewis St., 82 Port Reading Ave., 88 Port Reading Ave., 7 Wedgewood Ave., Woodbridge, NJ
COUNTY:	Middlesex
The undersigned Single Prime specifications.	Contractor proposes to be responsible for all work shown in the contract plans and
Single Bid	\$
lump sum all trades	(Numerical Figures Only)
Management and Construction	:35-1 et seq., the Contractor will be classified with the Division of Property (DPMC) in one of the following trades: General Construction (C008) or General d Additions (C009) or Demolition (C021)
The proposal is based upon the	bid documents listed below.
1. Instructions to Bidder	s and General Conditions Revised, December 2015
2. Specifications dated:	September 2019
3. Drawing(s)#: Inclu	ided in the Specifications Dated: September 2019
This project will be fully comp	leted and ready for occupancy within65 Calendar days.
Liquidated damages will be ass	sessed at 1/20 of one percent (.05%) of the value of this contract (minimum of \$250.00).
The above price is good through	th sixty (60) days after the bid opening date.
Submit only one bid proposal	and bid bond form.
A bid bond in the amount of fithis proposal form.	fty percent (50%) of the TOTAL bid, including alternates if applicable, must accompany

DPMC-3 Single Prime (rev. 10/13) INDEX 500

BULLETIN NUMBER

The Contractor must include prices for the base bid and all alternates and unit prices when requested, otherwise the bid may be considered non-responsive.

Having examined the bid documents and the site of the proposed work and being familiar with all of the conditions surrounding the construction of the proposed project including the availability of materials and labor, the Contractor hereby proposes to furnish all labor, materials and supplies, and to construct the project as submitted, within the time set forth therein, and at the price stated. This price is to cover all expenses incurred in performing the work required, of which this proposal is a part.

The Contractor acknowledges and affirms that it has personal knowledge of or has obtained and reviewed a copy of the valid prevailing wage rates for all trades involved in the project for the geographical location of the project as issued by the Commissioner of the Department of Labor, P O Box 389, Trenton, New Jersey, 08625 (609) 292-2259.

DATE OF BULLETIN

The Contractor acknowledges receipt of the following Bulletins:

A	September 26, 2019
В	October 21, 2019
with DPMC in accordance with N.J.S.A. 52:35-1 et intends to perform the work described under any of Prime Contractor must be classified in that trade an	cluded in this Single Bid proposal are listed below and are classified t seq. at the time of the bid due date. If the Single Prime contractor if the listed trades sections of this bid proposal form, that Single ad listed in the appropriate Subcontractor section of this bid proposal. satisfied Subcontractors as part of Single Bid proposals shall constitute ection of the bid.
DEMOLITION (C021)	
NAME:	
ADDRESS:	
PLUMBING (C030)	
NAME:	
ADDRESS:	
ASBESTOS REMOVAL/TREATMENT (C092)	
NAME:	
1000	
ADDRESS:	

ALLOWANCES

There are NO allowances in this bid.

EXECUTION OF CONTRACT

Upon receipt of written notice of the acceptance of this bid, the Contractor shall execute the formal contract within 10 calendar days and deliver a Performance and Payment Bond as well as other information as required in the bid solicitation.

COMMENCEMENT OF WORK

Contractor acknowledges that the work is to commence upon receipt of the Notice to Proceed with the exception of permit activities.

BID SECURITY

Bid Bond is fifty percent (50%) of the TOTAL bid, including alternates if applicable, and is to become the property of the State in the event the contract and bond are not executed within the time set forth as liquidated damages for the delay and additional expense incurred by the Owner.

CERTIFICATION

I certify that the below	v named firm is cl	assified by the Divi	sion of Property I	Management and	l Construction	in the
approved amount of	\$	= fo	r (trade)	¥		until
10	(expir	ation date).		37		
I further certify that the consideration of uncomajor trade subcontra	mpleted construct	ion work (please ref	fer to N.J.A.C. 17	:19-2.13, which	describes how	v certain
			Respectfully su	bmitted,		
(Seal-if Bid proposal	is by a corporation	n)	in the			
		D.,.				
		By:		(Name of	Firm)	
				(Signatu	ıre)	
			*			
				(Title	•)	
			(Business	Street Address (ONLY – No P	O Box)
			(City	State	County	Zip)
			Phone No.			3
			Fax No.			
Federal Identification	1 No		<u> </u>			
Any change in owner	ship information s	since filing your Re	quest for Classific	cation (Form DP	MC 27)	
☐ Yes						
☐ No						
If yes, attach explana	tion.	A.				

PROJECT NO.: <u>P1121-12</u>

PROJECT: Demolition of Residential Dwellings

STATE OF NEW JERSEY DEPARTMENT OF TREASURY DIVISION OF PROPERTY MANAGEMENT & CONSTRUCTION

NON-COLLUSION AFFIDAVIT

576 Bamford Ave 679 Lewis St., 82 Middlesex Count	Port Reading	d Ave., 88 (Ave., 88 Por	Claire Ave., 122 Hat Reading Ave., 7 V	arriot St., 661 Lewis St Wedgewood Ave., Wo	., 675 Lewis St., odbridge,
			Bid Due Date	October 29, 2019	2:00 PM
STATE OF NEW JERSEY	[
	SS.				
COUNTY OF	[
I,		of	the City of		
in the County of			and the State of		
of full age, being duly sworn ac	cording to law	on my oath	depose and say tha	t:	
I am					
of the firm of					
the Contractor making the Bid I authority so to do; that said Corcollusion, or otherwise taken ar project; and that all statements full knowledge that the State of the statements contained in this	ntractor has not my action in rest contained in sa 'New Jersey re	, directly or raint of free id bid propos lies upon the	indirectly, entered, competitive biddi sal and in this affide truth of the staten	into any agreement, pa ng in connection with lavit are true and corre- nents contained in said	articipated in any the above named ct, and made with
			SIC	GNATURE OF PRIN	CIPAL
Subscribed and sworn to before	e me this	day			
of 20 ,					
Notary Public	e				
My Commission expires		,			

Public Law 2005, Chapter 92

Formerly: Executive Order 129

In accordance with Public Law 2005, Chapter 92 (N.J.S.A. 52:34-13.2 et seq., superseding Executive Order 129 (2004)) all bidders submitting a proposal shall be required to submit a Source Disclosure Certification that all services will be performed in the United States. The bidder shall disclose the location by country where services under the contract will be performed and any subcontracting of services under the contract and the location by country where any subcontracted services will be performed.

SOURCE DISCLOSURE CERTIFICATION FORM

Bidder:
I hereby certify and say:
I have personal knowledge of the facts set forth herein and am authorized to make this Certification on behalf of the Bidder.
The Bidder submits this Certification as part of a bid proposal in response to the referenced solicitation issued by the State of New Jersey, Department of Treasury, Division of Property Management and Construction (DPMC), in accordance with the requirements of Public Law 2005, Chapter 92, (N.J.S.A. 52:34-13.2 et seq., superseding Executive Order 129 (2004)).
The following is a list of every location where services will be performed by the bidder and all subcontractors.
Bidder or Subcontractor Description of Services Performance Location(s) by Country
Any changes to the information set forth in this Certification during the term of any contract awarded under the referenced Project Number will be immediately reported by the Bidder to the Contract Compliance Unit in the DPMC, Department of Treasury, State of New Jersey, PO Box 034, Trenton, NJ 08625.
I understand that, after award of a contract to the Bidder, it is determined that the Bidder has shifted services declared above to be provided within the United States to sources outside the United States, prior to a written determination by the Director, Division of Property Management and Construction, that extraordinary circumstances require the shift of services or that the failure to shift the services would result in economic hardship to the State of New Jersey, the Bidder shall be deemed in breach of contract, which contract will be subject to termination for cause under its contract with DPMC.
I further understand that this Certification is submitted on behalf of the Bidder in order to induce DPMC to accept a bid proposal, with knowledge that the State of New Jersey and DPMC are relying upon the truth of the statements contained herein.
I certify that, to the best of my knowledge and belief, the foregoing statements by me are true. I am aware that if any of the statements are willfully false, I am subject to punishment.
Bidder: [Name of Organization or Entity]
By: Title:
Print Name: Date:

STATE OF NEW JERSEY DIVISION OF PROPERTY MANAGEMENT AND CONSTRUCTION DISCLOSURE OF INVESTMENT ACTIVITIES IN IRAN

BIDDER
Pursuant to Public Law 2012, c. 25, any person or entity that submits a bid or proposal or otherwise proposes to enter into or renew a contract must complete the certification below to attest, under penalty of perjury, that neither the person or entity, nor any of its parents, subsidiaries, or affiliates, is identified on the Department of Treasury's Chapter 25 list as a person or entity engaging in investment activities in Iran. The Chapter 25 list is found on the Division of Purchase and Property's website at http://www.state.nj.us/treasury/purchase/pdf/Chapter25List.pdf . Bidders must review this list prior to completing the below certification. Failure to complete the certification may render a bidder's proposal non-responsive. If the Director finds a person or entity to be in violation of law, s/he shall take action as may be appropriate and provided by law, rule or contract, including but not limited to, imposing sanctions, seeking compliance, recovering damages, declaring the party in default and seeking debarment or suspension of the party.
PLEASE CHECK THE APPROPRIATE BOX:
I certify, pursuant to Public Law 2012, c. 25, that neither the bidder listed above nor any of the bidder's parents, subsidiaries, or affiliates is listed on the N.J. Department of the Treasury's list of entities determined to be engaged in prohibited activities in Iran pursuant to P.L. 2012, C. 25 ("Chapter 25 List"). I further certify that I am the person listed above, or I am an officer or representative of the entity listed above and am authorized to make this certification on its behalf. I will skip Part 2 and sign and complete the Certification below.
OR
I am unable to certify as above because the bidder and/or one or more of its parents, subsidiaries, or affiliates is listed on the Department's Chapter 25 list. I will provide a detailed, accurate and precise description of the activities in Part 2 below and sign and complete the Certification below. Failure to provide such will result in the proposal being rendered as non-responsive and appropriate penalties, fines and/or sanctions will be assessed as provided by law.
Part 2: PLEASE PROVIDE FURTHER INFORMATION RELATED TO INVESTMENT ACTIVITIES IN IRAN You must provide a detailed, accurate and precise description of the activities of the bidding person/entity, or one of its parents, subsidiaries or affiliates, engaging in the investment activities in Iran outlined above by completing the box(es) below.
Name Relationship to Bidder/Offeror
Description of Activities
Duration of Engagement Anticipated Cessation Date
Bidder/Offeror Contract Name Contact Phone Number

List Additional Activities on Separate Sheet

P.L. 2012 c. 25

CERTIFICATION: I, being duly sworn upon my oath, hereby represent and state that the foregoing information and any attachments thereto to the best of my knowledge are true and complete. I attest that I am authorized to execute this certification on behalf of the above-referenced person or entity. I acknowledge that the State of New Jersey is relying on the information contained herein and thereby acknowledge that I am under a continuing obligation from the date of this certification through the completion of any contracts with the State to notify the State in writing of any changes to the answers of information contained herein. I acknowledge that I am aware that it is a criminal offense to make a false statement or misrepresentation in this certification, and if I do so, I recognize that I am subject to criminal prosecution under the law and that it will also constitute a material breach of my agreement(s) with the State of New Jersey and that the State at its option may declare any contract(s) resulting from this certification void and unenforceable.

Full Name (Print):	Signature:
Title:	Date:

NON- MANDATORY PRE-BID MEETING MINUTES

PROJECT #P1121-12 BLUE ACRES DEMO PROGRAM / WOODBRIDGE TOWNSHIP

Date: 10/15/2019

PROJECT # P1121-12:

576 Bamford Ave. 675 Lewis St. 679 Lewis St. 679 Lewis St.

88 Claire Ave.
122 Harriot St.
661 Lewis St.
82 Port Reading Ave.
88 Port Reading Ave.
7 Wedgewood Ave.

1. Introductions:

- a. State Project Team Members
 - 1) Bill Byster
 - 2) Regina Bruno
- b. Project Design Consultant & Staff
- 2. AECOM- Humberto Morales

3. Administrative Items

- a. All Bidders please Sign In
- b. Nothing said here or during the site visit(s) is a part of the contract unless specifically issued in writing by Bulletin.
- c. Minutes of this meeting & sign-in sheet will be distributed as part of a subsequent Bulletin along with other info that may be required including answers to any Bidders' questions.

4. All bidders must be "Classified with DPMC" in one of the following trades:

- a. General Construction (C008) or General Construction/ Alterations & Additions (C009) or Demolition (C021)
- b. All Bidders also must have DPMC Classified Sub-Contractors in the following trades: Demolition (C021), Asbestos Removal (C092) and Plumbing (C030)
- c. Bid is Single Prime / Lump Sum
- d. There are NO Allowances.
- e. This is a HUD CDBG project:
 - 1. The Prime Contractor is to familiarize themselves with Bulletin A and Appendix F in specifications.

5. Plans, Specifications and Bid Proposals can be obtained by contacting:

a. Anthony Mangine at 609 292-7201 or at the 9th floor plan room at 33 West State Street, Trenton.

6. Questions regarding the Bid Proposal form. Bidding procedures. Bonding. etc., contact:

- a. Shawn Taylor of the DPMC Contracts Procurement Group at 609 292-5229.
- b. Do NOT leave any blanks on the bid proposal form!
- 7. Bids Due: 10/29/2019 by 2:00 pm at 33 West State Street, Trenton unless modified by Bulletin:
 - a. If bid is mailed through the US Postal Service the address is:

Division of Property Management and Construction PO Box 034 Trenton, NJ 08625-0034

b. If bid is delivered by delivery service (UPS, FedEx, etc.) the physical address is:

Division of Property Management and Construction 33 West State Street, 9th Floor Trenton, NJ **08608**

8. Contract Terms:

- a. Contract Performance Period is 65 calendar days from issuance of NTP by the State for Project #P1121-12.
- b. Liquidated Damages 1/20th of 1% of contract value with a minimum of \$250.
- c. Bid Bond is 50% of bid amount.

9. NOTICE OF REQUIREMENT FOR A DUNS NUMBER REGISTRATION

- a. In accordance with 2CFR Part 200.213 "Suspension and Debarment", all vendors, contractors and subcontractors submitting proposals on federal FEMA and HUD funded projects will be required to register for a Data Universal Numbering System (DUNS) number in order to be eligible for a contract award. These regulations restrict awards, sub-awards and contracts with certain parties that are debarred, suspended, or otherwise excluded from or ineligible for participation in federal assistance programs or activities. In order to comply with this requirement, each consultant, prime contractor and sub-contractor must register in the System of Award Management (SAM) at http://www.sam.gov and register for a DUNS number at http://www.dnb.com/duns-number.html.
- b. Be advised that firms doing work for the government or bidding on government contracts or proposals will need to get a D-U-N-S Number for each physical location of their business. Firms can get a <u>D-U-N-S Number expedited for free</u> if they are required to register with the federal government for a government funded contract and the firm may have the D-U-N-S number expedited for no cost.
- c. Successful bidders will be required to submit to the Division of Property Management and Construction (DPMC) their DUNS number immediately after the bid due date and prior to contract award

10. Mandatory Post Bid Review with Apparent Low bidder:

- a. Apparent Low Bidder should be prepared for a meeting with the Project Engineer and State Project Team on 10/31/2019 at 10am for P1121-12 to review your bid.
 - 1) Location: Woodbridge Municipal Building, 1 Main Street, Woodbridge, NJ07095
- b. Apparent Low Bidder must bring their estimator along with Demo Sub-Contractor and ACM Sub-Contractor to the meeting.

11. Additional Ouestions after today's meeting:

- a. E-mail to: William.Byster@treas.ni.gov
- b. No later than: 10/17/2019 by 12 Noon
- c. All questions/RFI's in WORD format, not PDF
- d. No verbal questions or phone calls to DPMC, client or engineer
- e. Responses will be made to all via a subsequent Bulletin.

12. Project Description:

- a. Single Prime / Bid is Lump Sum / there are NO Allowances for this Bid.
- b. Review Scope of Work, Plan & Spec at the end of the agenda by Consultant.
- c. Special Features/Requirements Bullet Points:
 - 1. Very fast paced demo project.
 - 2. Everything Man Made, within the scope parameters of this project, must be removed from these sites.
 - 3. A Plumbing Permit is not required on these DPMC Demo Projects related to the water and sewer cut and caps.
 - 4. Caution with adjoining properties.
 - 5. Protection of sidewalks and aprons.
 - 6. Before photos for General Contractor's benefit must be time & date stamped.
 - 7. Temporary fencing to be installed on ALL properties before any work takes place on any property.
 - 8. Contractor to adhere to all soil erosion and sediment control measures as required by the Specifications and the local Soil Conservation District.
 - 9. No containers left in the street overnight and no dumpsters left without a cover on site.
 - Do not block roads.
 - 11. No interaction with the public, all questions go to town BA.
 - 12. Once a building is demolished it must be taken away, no stock piling or moving to another demo site.
 - 13. No backfill is permitted on site until the DPMC PM signs off that all debris has been removed from the site. This will be done on a site by site basis.

- 14. Client is DEP Periodic soil samples will be taken by DEP.
- 15. Backfill requires 3rd party testing agency for compaction for each lift prior to placement of topsoil.
- 16. Topsoil (6") Seeding/Stabilization Refer to Spec Section 329200, 3.2.C.
- 17. Substantial Completion must occur within the Contract Time Frame and this demo project will only be considered substantially complete when all required deliverables have been delivered to and accepted by the A/E and the State. This is also to include State / AE receipt of all Contractor manifests and "C" of "A's" issued by DCA.
- 18. Working Hours: 8am to 4:30pm Monday through Friday.
- 19. Safety Personal Protection/Safety Plan.
- 20. Provide detailed Demolition Plan and Abatement Plan.
- 21. Must show sequencing of homes to be abated and sequencing of homes to be demolished.
- 22. 48 hours' notice must be given to DPMC prior to the start of any home demolition. Example: If Demo Permit is rec'd by 3:30pm on Monday, the earliest that building can be demo'd is Weds at 8am. One full business day in between notice and demo.
- 23. Water Usage Fee / Deposit for Water Meters (see attachment)
- 24. 25% of Hazardous Mat Abatement Cost and 25% of Demo Cost will be held until all manifests are submitted to AE and State.
- 25. The Prime Contractor will submit the HUD forms contained in Bulletin A and Appendix F during the course of the work to demonstrate their actual conformance with the guidelines.

13. Submittals:

- a. Submittals up to and including item #21 are required within 4 calendar days of NTP. Submittals must include the DPMC 12/13 form cover sheet or will not be considered.
- b. Demo Permits will not be released until the first 21 Submittals are approved by AE & State.
- c. A third (3rd) review of submittals will require a back charge in the form of a credit change order by the contractor.

14. Review of Contractor Invoicing:

- a. DMPC will provide the contractor with the SOV's broken out by funding source after Submittal #17 is approved by AE.
- b. Submit first invoice ASAP to ensure the Contractor information is updated properly in the system due to multiple funding sources.

15. Review Schedule of Values / Submittal Log:

- a. SOV ACM, Demo & Site
- b. Updated Submittal Log is attached. HUD Submittals are incorporated. These submittals must be reviewed by AE prior to submitting the first invoice.

16. Highlight General Conditions Clauses:

- a. Paragraph IB1.5 FULL KNOWLEDGE OF SITE
- b. Bidders are required to visit site prior to submitting proposals; thorough examination of conditions of site: Reasonably observable conditions.
- c. Paragraph IB8.3 THOROUGH REVIEW OF CONTRACT DOCUMENTS
- d. Prior to submission of bid. No claims unless written request in compliance with IB8.2 and the matter has not been addressed by issuance of bulletin(s).
- e. Paragraph IB10.2 NO SALES TAX FOR MATERIAL. SUPPLIES. OR SERVICES
- f. Paragraph IB10.4 PURCHASES OR RENTALS OF EQUIPMENT ARE NOT EXEMPT FROM ANY TAX UNDER STATE SALES TAX ACT
- g. 4.6.2 The Contractor shall employ a FULL-TIME COMPETENT SUPERINTENDENT and necessary foremen and assistants, who shall be in attendance on the Project Site during the progress of the Work. The superintendent shall represent the Contractor, and all communications given to the superintendent shall be binding upon the Contractor. The State reserves the right to require a change in superintendent if the superintendent's performance, as judged by the DPMC, is deemed to be inadequate. Upon application in writing, and if deemed appropriate and expressly approved by the DPMC, the requirement for a full-time superintendent may be waived. If such a waiver is permitted, the Contractor shall employ a full-time competent foreman who shall be in attendance on the site during the progress of work and shall represent the Contractor, and all communications given to the foreman Pages 25 and 26 of 83 shall be binding upon the Contractor. The Contractor shall not employ persons unfit or unskilled in the assigned area of work.
- 17. <u>Project progress:</u> Meetings will only be held if needed. The A/E will attend, chair and issue record minutes of the meeting.

18. Site Walk-Thru:

- a. Tour work area
- b. Homes to be open until 2 pm
- c. No questions will be answered during walk-thru
- 19. <u>Consultant- Review Scope of Work. Plan. & Spec.</u> Consultant will record all company names, questions and answers in meeting minutes. Answers to any questions which are unanswered will be included in meeting minutes and addressed by a subsequent Bulletin.

POST-BID SCHEDULE OF VALUES

DPMC BUREAU OF DESIGN CONSTRUCTION MONTHLY ESTIMATEFOR PAYMENT TO CONTRACTOR

ROTOR	TBD			CONTRACT TOTALS			ill in Ind		Fill In 1st	PROJECT	
EM #	ITEM DESCR:PTION	TEM DESCRIPTION QUANTITY UNIT UNIT PRICE AMOUNT		COMPLETED THIS PERIOD		PREVIOUSLY COMPLETED			N PLACE COMPLETE		
1	576 Ramined Ave.	Gordina	UIII	ONN PRICE	AMOUNT	QUANTITY	AMOUNT	QUANTITIY	- AMOUNT	QUANTITY	AMOUNT
2	HAZARDOUS MAT COST	1	ea	\$0.00	\$0.00	0.00%	\$0.00	0.00%	\$0.00	0.007	
, 1	DEMO COST	1		\$0.00	\$0.00	0.00%	\$0.00			0.00%	-
- 1	SITE COST	1		\$0.00	\$0.00	0.00%	\$0.00	0.00%	\$0.00	0.00%	
5	SPARE	1	_	\$0,00	\$0,00			0.00%	\$0.00	0.00%	
-		 	- "	30,00	30,00	0.009	\$0.00	0.00%	\$0.00	0.00%	
a a	610 Bambra Ave		-			 		_		-	
7	HAZARDOUS MAT COST	1	ea	\$0.00	*0.00	0.000	44.44				
	DEMO COST	- 			\$0.00	0.00%	\$0.00	0.00%	\$0.00	0.00%	
	SITE COST	'	ea	\$0.00	\$0.00	0.00%	\$0.00	0.00%	\$0.00	. 0.00%	_
	SPARE	_	Pa	\$0.00	\$0,00	0.00%	\$0,00	0.00%	\$0.00	0.00%	
		- 1	ea	\$0.00	\$0.00	0.00%	\$0,00	0.00%	\$0.00	0.00%	
11.	A Claire Ave		\vdash								
	HAZARDOUS MAT COST	_									
	DEMO COST	1	ea	\$0.00	\$0.00	0.009	\$0.00	0.009	\$0.00	0.00%	
		1	es.	\$0.00	\$0,00	0.00%	\$0,00	0.00%	\$0.00	0.00%	
	SITE COST	- 1	ea	\$0.00	\$0.00	0.00%	\$0.00	0.00%	\$0.00	0.00%	
5 .	SPARE	- 1	ea	\$0.00	\$0.00	0.009	\$0.00	0.00%	\$0.00	0.00%	
										-	_
	122 Harr - 1							i		 	
	HAZARDOUS MAT COST	- 1	ea	\$0.00	\$0.00	0.00%	\$0.00	0.00%	\$0.00	0.00%	
a I	DEMO COST	1	ea	\$0.00	\$0.00	0.00%	\$0.00	0.00%	\$0.00	0.00%	
9]:	SITE COST	- 1	ea	\$0,00	\$0.00	0.00%	. \$0.00	0.00%	\$0.00	0.00%	
0 [SPARE	- 1	ea	\$0.00	\$0.00	0.009	\$0.00				
					\$11,100	0100 F	30,00	0.00%	\$0.00	0.00%	
1	int Lewis S		- -					 		\vdash	
2	HAZARDOUS MAT COST	1	PB	\$0.00	£0.00	0.000	***	0.000			-
\rightarrow	DEMO COST	1	ea ea	\$0.00	\$0.00	0.00%	\$0.00	0.00%	\$0.00	0.00%	
-	SITE COST				\$0.00	0.00%	\$0.00	0.00%	\$0.00	0.00%	
	SPARE	1	ea	\$0,00	\$0.00	0.00%	\$0,00	0.00%	\$0,00	0.00%	
•	57 7AC.	- '	ea	\$0.00	\$0,00	0.00%	\$0,00	0.00%	\$0,00	0.00%	
6	CILI was ke										
	675 Lewis St.										
	HAZARDOUS MAT COST	- 1	ea	\$0.00	\$0.00	0.00%	\$0.00	0.00%	\$0.00	0.00%	
	DEMO COST	- 1	ea	\$0.00	\$0.00	0.00%	\$0.00	0.00%	\$0,00	0.00%	
	SITE COST		ea	\$0.00	\$0.00	0.00%	\$0,00	0.00%	\$0,00	0.00%	
5	SPARE	I	ea	\$0.00	\$0.00	0.00%	\$0.00	0.00%	\$0.00	0.00%	
								-	B11100	U. U.D. K	
	Lewis II					-					
: F	HAZARDOUS MAT ÇOST	- 1	ea	\$0.00	\$0.00	0.00%	\$0,00	0.00%	\$0.00	0.00%	
) [1	DEMO COST	I	ea	\$0.00	\$0.00	0.00%	\$0.00	0.00%	\$0.00	0.00%	
· S	SITE COST	1	ea	\$0.00	\$0.00	0.00%	\$0.00				
5 5	SPARE	- 1	ea	\$0.00	\$0.00	0.00%		0.00%	\$0.00	0.00%	
\neg		_	- (1)	80.00	317,1777	O.DU W	\$0.00	0.00%	\$0.00	0.00%	
8	Q Part Remines Ave.		_	_							
, ,	HAZARDOUS MAT COST	- 1	ea	\$0.00	40.00	0.000					
_	DEMO COST	- 1			\$0,00	0.00%	\$0.00	0.00%	\$0,00	0.00%	
	SITE COST	1	ea	\$0.00	\$0.00	0.00%	\$0.00	0.00%	\$0.00	0.00%	
	SPARE		ea	\$0,00	\$0.00	0.00%	\$0.00	0.00%	\$0,00	0.00%	
- 13	74 / 1154	- 1	ea	50.00	\$0,00	0.00%	\$0,00	0.00%	\$0.00	0.00%	
- 1	9 Dunt Barring										
	8 Port Rending Ave		_								
_	HAZARDOUS MAT COST	- 1	ra	\$12.00	\$0.00	0.00%	\$0.00	0.00%	\$0.00	0.00%	
	DEMO COST	- 1	co	\$0,00	\$0.00	0.00%	\$0.00	0.00%	\$0,00	0.00%	
	SITE COST	I	ea	\$0.00	\$0,00	0.00%	\$0,00	0.00%	\$0,00	0.00%	
S	PARE	- 1	ea	\$0.00	\$0.00	0.00%	\$0.00	0.00%	\$0,00	0.00%	
									\$11,00		
	Redrewand Ave.							_			
	IAZARDOUS MAT COST	- 1	10	\$0,00	\$0.00	0.009	\$0.00	0.00%	\$0,00	0.00%	
	DEMO COST	- 1	ea	\$0.00	\$0.00	0.00%	\$0.00	0.00%	\$0.00	0.00%	
	ITE COST		ea	\$0.00	\$0.00	0.00%	\$0.00	0.00%	\$0.00	0.00%	
S	PARE	7	ea	\$0.00	\$0.00	0.00%	\$0.00	0.000	4.1		
					*******	3,000	317,1717	0.00%	\$0.00	0.00%	
A	ddress					-					
	IAZARDOUS MAT COST	1	ea	\$0.00	\$0,00	0.00%	£0.00	0.000		0.005	
	DEMO COST	1 - 1	ea	\$0.00	\$0.00		\$0.00	0.00%	\$0,00	0.00%	
	ITE COST	1		\$0.00		0.00%	\$0.00	0.00%	\$0,00	0.00%	
	PARE	+ 1	ea		\$0.00	0.00%	\$0.00	0.00%	\$0.00	0.00%	
.,,		+ '	ea	\$0.00	\$0.00	0.00%	\$0.00	0.00%	\$0,00	0.00%	•
	ddress	_				,					
	AZARDOUS MAT COST	- 1	ea	\$0.00	\$0.00	0.00%	\$0.00	0.00%	\$0.00	0.00%	
	DEMO COST	- 1	ea	\$0.00	\$0.00	0.00%	\$0.00	0.00%	\$0.00	0.00%	
	ITE COST	- 1	ea	\$0.00	\$0,00	0.00%	\$0.00	0.00%	\$0.00	0.00%	
SI	PARE	/	ea	\$0.00	\$0.00	0.00%	\$0.00	0.009	\$0.00	0.00%	
							70.00		\$0,00	0.00 A	
$\Box \Gamma$								\rightarrow			
$_{\perp}$ T			_								
			_		-						
(40)	pare I		ea	\$0.00	\$0.00	0.00%	60.00	0.000			
122		 	111		ar7.00	J.00 A	\$0.00	0.00%	\$0,00	0.00%	
-39	pare 2	,	#41	\$0.00	\$0.00	n ong	40.00	D. GOOT			
			ea 📙	347,040	\$0,00	0.00%	\$0,00	0.00%	\$0.00	0,00%	3
	201 1							_		B, B17 /L	
Si				50.00							
Si	sate 3	1	ea E	\$0,00	\$0.00	0.00%	\$0,00	0.00%	\$0,00	0.00%	

KEY: FUNDING SOURCE

TRACKING	SECTION			-		in .	P1121-12
#	#	DESCRIPTION	ADDRESS	DATE REC'D	REVIEW CODE	DATE	NOTES
1	020700	Health & Safety Plan	 	1		APPROVED	
2	GC	Subcontractor (Compaction Testing)		+			
3	GC	Subcontractor (ACM_Sampling)					
4	GC	Subcontractor (ACM Testing)					
5	GÇ	Subcontractor (DOL/OSHA Air Sampling)		 			
6	GC	Other Subcontractors					
7	220000	Sewer Cap		 			
. 8	220000	Water Cap					
9	015626	Temporary Fence		 			
10		Silt Fence		 			
11	312500	Inlet Filter		 	<u> </u>		
12	312500	Tracking Pad Material		 	_		
13	020590	Asbestos Abatement Plan		 			
14		Demolition Plan		 			
14.01		AST Removal		 			<u> </u>
15	020700	Materials Salvage & Recycling Management Plan		 			
16	GC	Construction Sequence	-	 	_		<u></u>
17	GC	Schedule of Values		 			<u> </u>
18	020700	Rodent and Insect Pesticides SDS (MSDS)		+			<u> </u>
19	312300	Clean Fill Material Proctor and Gradation Analysis and Certification Letter		 			
20	329200	Imported Topsoil Material Certification Letter		 	————		
21	329200	Hydroseed Mix (Seed Type, etc.)					
22.01		UCC Tech Sheets, Certificate of Pesticide Application, Water & Sewer Disconnect					
22.01	020700	Letters and ACM All Clear Letter	576 Bamford Avenue				
22.02		UCC Tech Sheets, Certificate of Pesticide Application, Water & Sewer Disconnect					
22.02	020700	Letters and ACM All Clear Letter	640 Barnford Avenue				
22.03		UCC Tech Sheets, Certificate of Pesticide Application, Water & Sewer Disconnect				-	-
	020700	Letters and ACM All Clear Letter	88 Claire Avenue		22		
22.04	ĺ	UCC Tech Sheets, Certificate of Pesticide Application, Water & Sewer Disconnect				_	<u> </u>
	020700	Letters and ACM All Clear Letter	122 Harriot Street	1		1	
22.05		UCC Tech Sheets, Certificate of Pesticide Application, Water & Sewer Disconnect	2011 : 0:				
-	020700	Letters and ACM All Clear Letter	661 Lewis Street				
22.06		UCC Tech Sheets, Certificate of Pesticide Application, Water & Sewer Disconnect	675 Lauda Chuan				·
<u> </u>	020700	Letters and ACM All Clear Letter	675 Lewis Street] [i	
22.07	000700	UCC Tech Sheets, Certificate of Pesticide Application, Water & Sewer Disconnect	679 Lewis Street				
100 BC	020700	Letters and ACM All Clear Letter	079 Lewis Street	l			
22.08	000700	UCC Tech Sheets, Certificate of Pesticide Application, Water & Sewer Disconnect	82 Port Reading Avenue		-		
	020700	Letters and ACM All Clear Letter				[0)
22.09	020700	UCC Tech Sheets, Certificate of Pesticide Application, Water & Sewer Disconnect	88 Port Reading Avenue				
		Letters and ACM All Clear Letter	CO / OIL HORding Avenue	W			
22.10	020700	UCC Tech Sheets, Certificate of Pesticide Application, Water & Sewer Disconnect Letters and ACM All Clear Letter	7 Wedgewood Avenue				24 14
23.01		ACM Waste Manifests, ACM Removal Letter (RACM)					= :0
23.02		ACM Waste Manifests, ACM Removal Letter (RACM) ACM Waste Manifests, ACM Removal Letter (RACM)	576 Bamford Avenue				
23.03		ACM Waste Manifests, ACM Removal Letter (RACM)	640 Barnford Avenue	<u> </u>			
23.04	020590	ACM Waste Manifests, ACM-Removal Letter (RACM) ACM Waste Manifests, ACM-Removal Letter (RACM)	88 Claire Avenue	<u> </u>	ll l		
23.05	020590	ACM Waste Manifests, ACM Removal Letter (RACM) ACM Waste Manifests, ACM Removal Letter (RACM)	122 Harriot Street				
23.06	020500	ACM Waste Manifests, ACM Removal Letter (MACM)	661 Lewis Street				
23.07	020590	ACM Waste Manifests, ACM Removal Lotter (RACM) ACM Waste Manifests, ACM Removal Lotter (RACM)	675 Lewis Street				
23.08	020590	ACM Waste Manifests, ACM Personal Letter (HACM)	679 Lewis Street				
23.09	020590	ACM Waste Manifests, ACM Removal Letter (RACM)	82 Port Reading Avenue				<u> </u>
23.10	020590	ACM Waste Manifests, ACM Removal Letter (RACM)	88 Port Reading Avenue			3.54	
24.01	020390	ACM Waste Manifests, ACM Removal Letter (RACM)	7 Wedgewood Avenue				
24.02		Landfill Receipts For General Demolition	576 Bamford Avenue				
24.02	020700	Landfill Receipts For General Demolition	640 Barnford Avenue			10	
24.03	020700	Landfill Receipts For General Demolition	88 Claire Avenue				<u> </u>
24.05	020700 1	Landfill Receipts For General Demolition	122 Harriot Street				
24.00	020700	Landfill Receipts For General Demolition	661 Lewis Street				

TRACKING	SECTION				_	0.477	
#	#	DESCRIPTION	ADDRESS	DATE REC'D	REVIEW CODE	APPROVED	NOTES
24.06	020700	Landfill Receipts For General Demolition	675 Lewis Street	 		APPROVED	
24.07	020700	Landfill Receipts For General Demolition	679 Lewis Street	 	_		
24.08	020700	Landfill Receipts For General Demolition	82 Port Reading Avenue	†	.	 	
24.09	020700	Landfill Receipts For General Demolition	88 Port Reading Avenue	 		 	
24.10	020700	Landfill Receipts For General Demolition	7 Wedgewood Avenue	┼──┤		 	
25.01	020700	Salvage & Recycling Receipts	576 Barnford Avenue	 			
25.02	020700	Salvage & Recycling Receipts	640 Bamford Avenue	 			-
25.03	020700	Salvage & Recycling Receipts	88 Claire Avenue	 		 -	
25.04	020700	Salvage & Recycling Receipts	122 Harriot Street	 		├	
25.05	020700	Salvage & Recycling Receipts	661 Lewis Street	+		 	·
25.06	020700	Salvage & Recycling Receipts & AST	675 Lewis Street	 			
25.07	020700	Salvage & Recycling Receipts	679 Lewis Street	 		 	
25.08	020700	Salvage & Recycling Receipts & AST	82 Port Reading Avenue	 		├──-	
25.09	020700	Salvage & Recycling Receipts	88 Port Reading Avenue	 - 			
25.10	020700	Salvage & Recycling Receipts	7 Wedgewood Avenue	 			
26.01	020700	DOL/OSHA Sampling Recults	576 Bamford Avenue	NA I	NA	NIA I	
26.02	020700	DOL/OSHA Sampling Results	640 Barnford Avenue	NA NA	NA NA	NA NA	
26.03	020700	DOL/OSHA Sampling Results	88 Claire Avenue	NA NA	NA NA	NA NA	
26.04	020700	DOL/OSHA Sampling Results	122 Harriot Street	NA NA	NA NA	NA NA	
26.05	020700	DOL/OSHA Sampling Results	661 Lewis Street	NA NA	NA NA	NA NA	
26.06	020700	DOL/OSHA Sampling Results	675 Lewis Street	I NA	NA NA		
26.07	020700	DOL/OSHA Sampling Results	679 Lewis Street	IVA	NA	NA .	
26.08	020700	DOL/OSHA Sampling Recults	82 Port Reading Avenue	NA NA		-	
26.09	020700	DOL/OSHA Sampling Results	88 Port Reading Avenue	NA NA	NA	NA NA	
26.10	020700	DOL/OSHA Sampling Results	7 Wedgewood Avenue		***		
27.01	312300	Compaction Testing Results	7 Wedgewood Avenue	NA	NA NA	NA I	
27.02		Compaction Testing Results	576 Bamford Avenue				
27.03		Compaction Testing Results	640 Barnford Avenue				
27.04	312300	Compaction Testing Results	88 Claire Avenue	 			
27.05	312300	Compaction Testing Results	122 Harriot Street				
27.06	312300	Compaction Testing Results	661 Lewis Street				
27.07		Compaction Testing Results	675 Lewis Street				
27.08		Compaction Testing Results	679 Lewis Street				
27.09		Compaction Testing Results	82 Port Reading Avenue	 			
27.10		Compaction Testing Results	88 Port Reading Avenue				
28		HUD/CDBG-DR - Contractor Information Form	7 Wedgewood Avenue				<u> </u>
29	GC	HUD/CDBG-DR - Business Contact Log	 	ļI			
30	GC	HUD/CDBG-DR - Community Outreach Log	1				
31	GC	HUD/CDBG-DR - Section 3 Business Certification	 				
32	GC	HUD/CDBG-DR - Section 3 Business Certification HUD/CDBG-DR - Section 3 Resident Certification					
33		Closeout Submittal DPMC 11(Final Invoice), 11.2 (SOV) & 11.2a (Cert Prime)	 	-			
34	017800	Closeout Submittal DPMC 20 Final Contract Acceptance				+	
35	017800	Closeout Submittal DPMC 20r(2) ORIGINAL Consent of Surety w/raised seal (cannot be emailed)					
36	017800	Closeout Submittal DPMC 20d Certificate of Substantial Completion					
37	017800	Closeout Submittal One (1) Year Performance Warranty					

REVIEW CODE KEY:

APP = APPROVED

AAN = APPROVED A\$ NOTED

R = REVIEWED

WO #2

P1121-12

TRACKING SECTION						
# #	DESCRIPTION	ADDRESS	DATE REC'D	REVIEW CODE	DATE APPROVED	NOTES
		NI.		RFR = RETURNED		
				REJ = REJECTED		
				NR = NOT REVIEW	ED	
				NA = NOT APPLICA	BLE	
				RR = RECEIVED FO	R RECORD	

WOODBRIDGE: Hydrant & Water Usage/Water & Sewer Disconnects

Hydrants	Middlesex Water does not charge for usage of devices or consumption of water. Contractor is responsible for signing out a hydrant meter/RPZ with a deposit check for \$5,350 submitted at the time of pick up. The deposit check will be returned upon the return of the device.
Water	Middlesex Water will shut water of at curb, remove the meter and send disconnect letter to DPMC. Contractor to have licensed plumber cut and cap water line. Contractor's plumber to provide a cut and cap letter on Company letterhead with license number.
Sewer	Contractor to have licensed plumber cut and cap the sewer. Contractor to contact Tom Flynn with Woodbridge Twp., Engineering Department, at 732-602-6057 to schedule (24 hours advanced notice). Woodbridge Twp. will witness the cut and cap prior to closing up hole. Contractor's plumber to provide a cut and cap letter on Company letterhead with license number.

PRE-BID MEETING SIGN-IN SHEET

PROJECT #:

P1121-12

PROJECT TITLE:

Demolition of Residential Dwellings Woodbridge, Middlesex County Blue Acres Program

DATE & TIME:

10/15/19 @ 10AM

COMPANY NAME (PRINT)	REPRESENTATIVE (PRINT)	SIGNATURE	TELEPHONE NUMBER	E-MAIL	1
DPM&C	Bill Byster	MB	TVOIVIDENC		-
DPM&C	Regina Bruno	Jesina Bruno			
AECOM	Humberto Morales	Hunto Male			3
DEP	SHARURE PATE				-
DEP	Gary Parent	a laint			
Eicon EnterPrises	Harfin Mceas				
MTM METTO CORP	Milus Daneysun				C
Wild Heart	Scan Brown And	4-)A.
ALL frompurgement	MIEN MONCHIL.				

PRE-BID MEETING SIGN-IN SHEET

PROJECT #:

P1121-12

PROJECT TITLE:

Demolition of Residential Dwellings Woodbridge, Middlesex County Blue Acres Program

DATE & TIME:

10/15/19 @ 10AM

COMPANY NAME (PRINT)	REPRESENTATIVE (PRINT)	SIGNATURE	TELEPHONE NUMBER	E-MAIL
TBC	Marcolucci	my		
				X- 1

STATE OF NEW JERSEY DEPARTMENT OF TREASURY DIVISION OF PROPERTY MANAGEMENT AND CONSTRUCTION PO BOX 034, TRENTON, NJ 08625-0034

PROJECT #: P1121-12 Bulletin A

Demolition of Residential Properties

576 Bamford Avenue, Woodbridge Township
640 Bamford Avenue, Woodbridge Township
88 Claire Avenue, Woodbridge Township
122 Harriot Street, Woodbridge Township
661 Lewis Street, Woodbridge Township
675 Lewis Street, Woodbridge Township
679 Lewis Street, Woodbridge Township
82 Port Reading Avenue, Woodbridge Township
88 Port Reading Avenue, Woodbridge Township
7 Wedgewood Avenue, Woodbridge Township
MIDDLESEX COUNTY, N.J.

A/E:

AECOM

DATE:

September 26, 2019

BULLETIN "A"

Bidder must acknowledge receipt of this Bulletin on bid form in the space provided therefore.

This Bulletin is issued for the purpose of amending certain requirements of the original Contract Documents, as noted hereinafter, and is hereby made part of and incorporated in full force as part of the Contract Documents. Unless specifically noted or specified hereinafter, all work shall comply with the applicable provisions of the Contract Documents.

A) DIANE B. ALLEN EQUAL PAY ACT

Pursuant to N.J.S.A. 34:11-56.14(b), any employer, regardless of the location of the employer, who enters into a contract with a public body to perform any public work for the public body shall provide to the Commissioner of the New Jersey Department of Labor and Workforce Development, through certified payroll records required pursuant to P.L.1963, c.150 (C.34:11-56.25 et seq.), information regarding the gender, race, job title, occupational category, and rate of total compensation of every employee of the employer employed in the State in connection with the contract. The employer shall provide the commissioner, throughout the duration of the contract or contracts, with an update to the information whenever payroll records are required to be submitted pursuant to P.L.1963, c.150 (C.34:11-56.25 et seq.).

Information regarding the Diane B. Allen Equal Pay Act and its requirements may be obtained from the New Jersey Department of Labor and Workforce Development (LWD) web site at: https://nj.gov/labor/equalpay/equalpay.html

BULLETIN "A" September 24, 2019 Page 2

LWD forms may be obtained from the online web site at: https://nj.gov/labor/forms_pdfs/equalpayact/MW-562withoutfein.pdf

- B) Attached documents for Bulletin "A":
 - a. Attachment "A" Statement of Assurances
 - b. Attachment "B" Additional Information for HUD Statement of Assurances for Contractor
 MUST BE COMPLETED AND RECEIVED PRIOR TO CONTRACT AWARD
 - c. Attachment "C" Section 3 Utilization Plan Template MUST BE COMPLETED AND RECEIVED PRIOR TO CONTRACT AWARD

END OF BULLETIN "A"

ATTACHMENT "A"

STATEMENT OF ASSURANCES FOR CONTRACTOR/CONSULTANT

ADDITIONAL FEDERALLY FUNDED AGREEMENT PROVISIONS APPLICABLE TO COMMUNITY DEVELOPMENT BLOCK GRANTDISASTER RECOVERY FUNDED PROJECTS

The purpose of this Statement of Assurances is to list requirements applicable to programs funded in whole or in part by Community Development Block Grant-Disaster Recovery ("CDBG-DR") funds received from the U.S. Department of Housing and Urban Development ("HUD").—Not all of the requirements listed herein shall apply to all activities or work under the Contract.

As used herein, "Contractor" and "Consultant" refer to any contractors or consultants awarded a Contract to provide goods or perform services in connection with the Project and paid with CDBG-DR funds.

Contractor/Consultant agrees to comply with all applicable federal CDBG-DR laws, guidelines and standards in a manner satisfactory to the State and HUD, including all administration and compliance requirements set forth by this Statement of Assurances. To the extent that Contractor/Consultant utilizes any subconsultants/subcontractors, Contractor/Consultant shall require and ensure that each subconsultant/subcontractor comply with all applicable federal CDBG-DR laws, guidelines and standards; any subcontracts entered into by Consultant shall set forth these requirements. Contractor/Consultant also agrees to comply with all applicable cross-cutting statutes and regulations, subject to waivers cited in the Federal Register, Docket No. FR-5696-N-01 (March 5, 2013) (Allocations, Common Application, Waivers, and Alternative Requirements for Grantees Receiving CDBG - DR funds in Response to Superstorm Sandy), as supplemented by additional applicable Notices published by HUD in the Federal Register.

Contractor/Consultant agrees to comply with the requirements of Title 24 of the CFR, Part 570 (HUD regulations concerning Community Development Block Grants).

The failure to list herein a legal requirement applicable to services performed by Contractor/Consultant does not relieve the Contractor/Consultant from complying with that requirement.

A. GENERAL PROVISIONS

- 1. Under provisions of the Hatch Act that limit the political activity of employees and HUD regulations governing political activity (24 CFR 570.207), CDBG funds shall not be used to finance the use of facilities or equipment for political purposes or to engage in other partisan political activities, such as candidate forums, voter transportation, or voter registration. However, a facility originally assisted with CDBG funds may be used on an incidental basis to hold political meetings, candidate forums, or voter registration campaigns, provided that all parties and organizations have access to the facility on an equal basis, and are assessed equal rent or use charges, if any.
- 2. No federally appointed funds shall be used for lobbying purposes regardless of level of government, in accordance with 2 CFR 200.450.
- 3. HUD rules prohibit the use of CDBG funds for inherently religious activities, as set forth in 24 CFR 570.200(j), except for circumstances specified in the Department of Housing and Urban

Revised 2/26/2018

- Development Allocations, Common Application, Waivers, and Alternative Requirements for Grantees Receiving CDBG Disaster Recovery Funds in Response, 78 FR 14329 (March 5, 2013).
- 4. HUD rules impose drug-free workplace requirements in Subpart B of 2 CFR part 2429, which adopts the government-wide implementation (2 CFR Part 182) of sections 5152-5158 of the Drug-Free Workplace Act of 1988.
- 5. Citizens will be provided with an appropriate address, phone number, and times during which they may submit complaints regarding activities carried out utilizing these CDBG-DR funds. The State will provide a written response to every citizen complaint within fifteen (15) working days of the complaint.
- B. PERSONALLY IDENTIFIABLE INFORMATION: To the extent the Contractor/Consultant receives personally identifiable information, it will comply with the Privacy Act of 1974 and HUD rules and regulations related to the protection of personally identifiable information. The term "personally identifiable information" refers to information which can be used to distinguish or trace an individual's identity, such as their name, social security number, biometric records, etc., either alone or when combined with other personal or identifying information which is linked or linkable to a specific individual, such as date and place of birth, mother's maiden name, etc. See 2 CFR 200.79 & OMB M-07-16. Contractor/Consultant shall require all persons that have access to personally identifiable information (including subcontractors/subconsultants and their employees) to sign a Non-Disclosure Agreement.

C. FINANCIAL MANAGEMENT AND PROCUREMENT

- 1. To the extent applicable, Contractor/Consultant shall adhere to the principles and standards governing federal grant distribution as set forth in the OMB Uniform Administrative Requirements, Cost Principles and Audit Requirements for Federal Awards (2 CFR Part 200).
- 2. Contractor/Consultant shall comply with all applicable laws pertaining to financial management, including 2 CFR Part 180 and 2 CFR Part 2424, which prohibit the making of any award or permitting any award (sub grant or contract) at any tier to any party that is debarred or suspended or is otherwise excluded from or ineligible for participation in federal assistance programs. To the extent that it uses subcontractors or subconsultants, Contractor must verify that none of them are on the List of Parties Excluded from Federal Procurement or Non-procurement Programs promulgated in accordance with Executive Orders 12549 and 12689, "Debarment and Suspension," as set forth at 2 CFR Part 2424. No Contractors or Subcontractors that are on the List may receive any CDBG funds.
- Conflict of interest rules, as set forth in 24 CFR 570.489, 24 CFR 570.611, and 2 CFR 200.112, apply. Contractor/Consultant shall disclose in writing any potential conflict of interest to DPMC and DEP.
- 4. To the extent applicable, Contractor/Consultant shall comply with 24 CFR Part 570 regarding the management and disposition of cash, real and personal property acquired with CDBG-DR funds.
- 5. To the extent applicable, Contractor/Consultant shall comply with 24 CFR 570.489(j) regarding change of use of real property. These standards apply to real property within its control (including activities undertaken by subcontractors/subconsultants). These standards apply from the date CDBG-DR funds are first spent until five years after the close-out of the Program.

Revised 2/26/2018 2

D. RECORDS AND RECORDS RETENTION

- 1. In accordance with 2 CFR 200.333, 24 CFR 570.502 and 570.506, Contractor/Consultant shall retain financial records, supporting documents, statistical records, and all other records pertinent to this Agreement. The retention period shall be the longer of three (3) years after the expiration or termination of this Agreement, or three years after the submission of the annual performance and evaluation report in which the project is reported on for the final time, except that records for activities subject to the reversion of assets provisions at § 570.503(b)(7) or change of use provisions at § 570.505 must be maintained for as long as those provisions continue to apply to the activity. Notwithstanding the above, if any litigation, claim, or audit pertaining to the Agreement is started before the expiration of the applicable retention period, records must be retained until completion of the action and resolution of all issues which arise from it, or until the end of the required retention period, whichever is later.
- 2. Contractor/Consultant shall provide the State and HUD, including their representatives or agents, access to and the right to examine all records, books, papers, or documents related to the Contract and the use of CDBG funds.
- **E. FEDERAL LABOR STANDARDS:** To the extent applicable, Contractor/Consultant shall comply with Federal Labor Standards, including:
 - 1. Section 110 of the Housing and Community Development Act of 1974, 42 U.S.C. §5310, 24 CFR §570.603 and HUD Handbook 1344.1 Federal Labor Standards Requirements in Housing and Urban Development Programs, as revised, which require that all laborers and mechanics (as defined at 29 CFR §5.2) employed by Contractor/Consultant (including its subcontractors/subconsultants) in connection with construction contracts over \$2,000, are paid wages at rates not less than those prevailing on similar construction in the locality as per the Davis-Bacon Act (40 U.S.C. §3141 et seq.), as amended; except that these requirements do not apply to the rehabilitation of residential property if such property contains less than 8 units;
- 2. The Contract Work Hours and Safety Standards Act (40 U.S.C. 3701 et seq.), requiring that mechanics and laborers (including watchmen and guards) employed on federally assisted contracts of \$100,000 or greater be paid wages of not less than one and one-half times their basic wage rates for all hours worked in excess of forty hours in a work-week, and projects must comply with safety standards:
- 3. The Federal Fair Labor Standards Act (29 U.S.C. 201 et seq.), requiring that covered nonexempt employees be paid at least the minimum prescribed wage, and also that they be paid one and one-half times their basic wage rate for all hours worked in excess of the prescribed work-week;
- 4. The Copeland "Anti-Kickback" Act (18 U.S.C. 874) as supplemented in Department of Labor regulations (29 CFR part 3), which apply to contracts and subcontracts for construction, prosecution, completion, or repair of public buildings, public works or buildings, or works financed in whole or in part by Federal loans or grants, and requires payment of wages once a week and allows only permissible payroll deductions;
- 5. Department of Labor regulations in parallel with HUD requirements above:
 - a. 29 CFR part 1: Procedures for Predetermination of Wage Rates

Revised 2/26/2018

- b. 29 CFR part 5: Labor Standards Provisions Applicable to Contracts Covering Federally Financed and Assisted Construction (Also, Labor Standards Provisions Applicable to Nonconstruction Contracts Subject to the Contract Work Hours and Safety Standards Act)
- c. 29 CFR part 6: Rules of Practice for Administrative Proceedings Enforcing Labor Standards
 In Federal and Federally Assisted Construction Contracts and Federal Service Contracts
- d. 29 CFR part 7: Practice Before the Administrative Review Board With Regard to Federal and Federally Assisted Construction Contracts.
- 6. All applicable Federal Labor Standards provisions set forth in form HUD-4010. Consultant/Contractor will ensure that form HUD-4010 is included in all bid packages and subcontracts entered into with contractors, consultants, or other third parties to supply goods or perform services in connection with the Contract activities and paid with CDBG-DR funds.

F. <u>SECTION 3 REQUIREMENTS</u>

1. To the extent applicable, Contractor/Consultant shall comply with Section 3 of the Housing and Urban Development Act of 1968, as amended ("Section 3"). Section 3 is intended to encourage recipients of HUD funding to direct new employment, training, and contracting opportunities to the greatest extent feasible to low- and very low-income persons, and to businesses that employ these persons, within their community. Section 3 applies to grantees and subrecipients that receive assistance exceeding \$200,000 in certain types of HUD funding, including CDBG funding, and to contractors and subcontractors that enter into contracts in excess of \$100,000 funded by certain types of HUD funding, including CDBG funds, for any activity that involves housing construction, rehabilitation, and demolition, or other public construction. A guide to Section 3 applicability and compliance requirements is located at HUD's

website, http://portal.hud.gov/hudportal/HUD?src=/program_offices/fair_housing_equal_opp/section3/section3, under Frequently Asked Questions (FAOs).

2. Pursuant to 24 CFR 135.38, the following language shall be included in all contracts and subcontracts:

a. The work to be performed under this contract is subject to the requirements of section 3 of the Housing and Urban Development Act of 1968, as amended, 12 U.S.C. 1701u (section 3). The purpose of section 3 is to ensure that employment and other economic opportunities generated by HUD assistance or HUD-assisted projects covered by section 3, shall, to the greatest extent feasible, be directed to low- and very low-income persons, particularly persons who are recipients of HUD assistance for housing.

b. The parties to this contract agree to comply with HUD's regulations in 24 CFR part 135, which implement section 3. As evidenced by their execution of this contract, the parties to this contract certify that they are under no contractual or other impediment that would

prevent them from complying with the part 135 regulations.

c. The contractor agrees to send to each labor organization or representative of workers with which the contractor has a collective bargaining agreement or other understanding, if any, a notice advising the labor organization or workers' representative of the contractor's commitments under this section 3 clause, and will post copies of the notice in conspicuous places at the work site where both employees and applicants for training and employment positions can see the notice. The notice shall describe the section 3 preference, shall set forth minimum number and job titles subject to hire, availability of apprenticeship and

- training positions, the qualifications for each; and the name and location of the person(s) taking applications for each of the positions; and the anticipated date the work shall begin.
- d. The contractor agrees to include this section 3 clause in every subcontract subject to compliance with regulations in 24 CFR part 135, and agrees to take appropriate action, as provided in an applicable provision of the subcontract or in this section 3 clause, upon a finding that the subcontractor is in violation of the regulations in 24 CFR part 135. The contractor will not subcontract with any subcontractor where the contractor has notice or knowledge that the subcontractor has been found in violation of the regulations in 24 CFR part 135.
- e. The contractor will certify that any vacant employment positions, including training positions, that are filled (1) after the contractor is selected but before the contract is executed, and (2) with persons other than those to whom the regulations of 24 CFR part 135 require employment opportunities to be directed, were not filled to circumvent the contractor's obligations under 24 CFR part 135.
- f. Noncompliance with HUD's regulations in 24 CFR part 135 may result in sanctions, termination of this contract for default, and debarment or suspension from future HUD assisted contracts.
- g. With respect to work performed in connection with section 3 covered Indian housing assistance, section 7(b) of the Indian Self-Determination and Education Assistance Act (25 U.S.C. 450e) also applies to the work to be performed under this contract. Section 7(b) requires that to the greatest extent feasible (i) preference and opportunities for training and employment shall be given to Indians, and (ii) preference in the award of contracts and subcontracts shall be given to Indian organizations and Indian-owned Economic Enterprises. Parties to this contract that are subject to the provisions of section 3 and section 7(b) agree to comply with section 3 to the maximum extent feasible, but not in derogation of compliance with section 7(b).

G. FAIR HOUSING AND NON-DISCRIMINATION

- To the extent applicable, Contractor/Consultant shall comply with the following fair housing and non-discrimination laws. Any act of unlawful discrimination committed by Contractor/Consultant or failure to comply with applicable laws shall be grounds for termination of the Contract.
 - a. Title VI of the Civil Rights Act of 1964, as amended, 42 U.S.C. §200d et seq., and the regulations issued pursuant thereto (24 CFR Part 1), which provide that no person in the United States shall on the grounds or race, color, or national origin, be excluded from participation in, be denied the benefits of, or be otherwise subjected to discrimination under any program or activity for which it receives federal financial assistance and shall immediately take any measures necessary to effectuate this assurance. If any real property or structure thereon is provided or improved with the aid of federal financial assistance extended to it this assurance shall obligate it, or in the case of any transfer of such property, and transferee, for the period during which the property or structure is used for another purpose involving the provision of similar services or benefits.
 - b. Fair Housing Act (Title VIII of the Civil Rights Act of 1968, as amended, 42 U.S.C. 3601–3619), which requires administering all programs and activities relating to housing and community development in a manner to affirmatively further fair housing. Title VIII further prohibits discrimination against any person in the sale or rental of housing, or the provision of brokerage services, including in any way making unavailable or denying a dwelling to any person, because of race, color, religion, sex, national origin, handicap or familial status.

- c. Title II of the Civil Rights Act of 1968 (25 U.S.C. 1301-1303), which prohibits discrimination because of race, color, religion, or natural origin in certain places of public accommodation.
- d. Architectural Barriers Act (ABA) of 1968, 42 U.S.C. 4151 *et seq*. The ABA requires access to buildings designed, built, altered, or leased by or on behalf of the federal government or with loans or grants, in whole or in part, from the federal government. As used in the ABA, the term "building" does not include privately owned residential structures not leased by the government for subsidized housing programs.
- e. Title IX of the Education Amendments Act of 1972, 20 U.S.C. 1681 *et seq.*, which prohibits discrimination on the basis of sex in any federally funded education program or activity.
- f. Section 504 of the Rehabilitation Act of 1973, as amended, 29 U.S.C. §794, which provides that no otherwise qualified individual shall solely by reason of his or her handicap be excluded from participation, denied program benefits, or subjected to discrimination under any program or activity receiving federal funding assistance.
- g. Section 508 of the Rehabilitation Act of 1973, as amended, 29 U.S.C. §794d, which requires Federal agencies to make their electronic and information technology (EIT) accessible to people with disabilities, and applies to all federal agencies when they develop, procure, maintain or use electronic and information technology.
- h. Section 109 of Title I of the Housing and Community Development Act of 1974, and the regulations issued pursuant thereto (24 CFR 570.602), which provides that no person in the United States shall, on the grounds of race, color, national origin, or sex, be excluded from participation in, be denied the benefits of, or be subjected to discrimination under, any program or activity funded in whole or in part with funds provided under that Part. Section 109 further prohibits discrimination to an otherwise qualified individual with a handicap, as provided under Section 504 of the Rehabilitation Act of 1973, as amended, and prohibits discrimination based on age as provided under the Age Discrimination Act of 1975. The policies and procedures necessary to ensure enforcement of section 109 are codified in 24 CFR 6.
- i. Section 104(b)(2) of the Housing and Community Development Act of 1974, 42 U.S.C. 5304(b), which requires communities receiving community development block grants to certify that the grantee is in compliance with various specified requirements.
- j. Age Discrimination Act of 1975, 42 U.S.C. 6101 et seq., which prohibits discrimination on the basis of age in programs and activities receiving federal financial assistance.
- k. Title II of the Americans with Disabilities Act of 1990, 42 U.S.C. 12131 et seq., as amended by the ADA Amendments Act of 2008, which prohibits discrimination against people with disabilities by public entities, which includes any state or local government and any of its departments, agencies or other instrumentalities.
- 1. Housing for Older Persons Act of 1995 ("HOPA") (42 U.S.C. 3607), which governs housing developments that qualify as housing for persons age 55 or older.
- m. Accessibility requirements contained in Title III of the Americans with Disabilities Act of 1990 (42 U.S.C. 12181 et seq.).
- n. Executive Order 11063: Equal Opportunity in Housing, November 20, 1962, as amended by Executive Order 12259, and the regulations issued pursuant thereto, which pertain to equal opportunity in housing and non-discrimination in the sale or rental of housing built with federal assistance.
- o. Executive Order 11246 (Johnson), September 24, 1965, as amended by Executive Order 11375 (Johnson), October 13, 1967, as amended by Executive Order 13672 (Obama), July 21, 2014, which prohibit discrimination in employment on the basis of race, color, religion, sex, sexual orientation, gender identity, or national origin. Further, contractors and subcontractors on federal and federally assisted construction contracts shall take affirmative action to ensure that equal opportunity is provided in all aspects of their employment,

Revised 2/26/2018 6

- including, but not limited to: employment, upgrading, demotion or transfer, recruitment or recruitment advertising, layoff or termination, rates of pay or other forms of compensation, and selection for training and apprenticeship.
- p. Executive Order 12086: Consolidation of contract compliance functions for equal employment opportunity, October 5, 1978.
- q. Executive Order 12892: Leadership and Coordination of Fair Housing in Federal Programs: Affirmatively Furthering Fair Housing, January 17, 1994.
- r. Executive Order 12898: Federal Actions to Address Environmental Justice in Minority Populations and Low-Income Populations, February 11, 1994.
- s. Executive Order 13166: Improving Access to Services for Persons with Limited English Proficiency (LEP), August 11, 2000, and Federal Register Notice FR-4878-N-02 (available online at http://www.gpo.gov/fdsys/pkg/FR-2007-01-22/pdf/07-217.pdf), which require recipients of federal financial assistance to ensure meaningful access to programs and activities by LEP persons. (The State's Language Access Plan (LAP) is available online at http://www.renewjerseystronger.org/wp-content/uploads/2014/08/NJ-DCA-LAP_Version-1.0_2015.01.14-for-RenewJerseyStronger.pdf).
- Executive Order 13217: Community-Based Alternatives for Individuals with Disabilities, June 19, 2001.
- u. Executive Order 13330: Human Service Transportation Coordination, February 24, 2004.
- v. Implementing regulations for the above:
 - i. 24 CFR part 1: Nondiscrimination in Federally Assisted Programs of HUD.
 - ii. 24 CFR part 3: Nondiscrimination on the Basis of Sex in Education Programs or Activities receiving Federal Financial Assistance.
 - iii. 24 CFR 5.105: Other Federal Requirements.
 - iv. 24 CFR part 6: Nondiscrimination in Programs, Activities Receiving Assistance under Title I of the Housing and Development Act of 1974.
 - v. 24 CFR part 8: Nondiscrimination Based on Handicap in Federally Assisted Programs and Activities of the Department of Housing and Urban Development.
 - vi. 24 CFR 50.4(1) and 58.5 (i): Environmental Justice.
 - vii. 24 CFR 91.225(a)(1): Affirmatively Furthering Fair Housing.
 - viii. 24 CFR 91.325(a)(1): Affirmatively Furthering Fair Housing.
 - ix. 24 CFR 91.325(b)(5): Compliance with Anti-discrimination laws.
 - x. 24 CFR 91.520: Performance Reports.
 - xi. 24 CFR part 100 part 125: Fair Housing.
 - xii. 24 CFR part 107: Non-discrimination and Equal Opportunity in Housing under Executive Order 11063 (State Community Development Block Grant Grantees).
 - xiii. 24 CFR part 121: Collection of Data.
 - xiv. 24 CFR part 135: Economic Opportunities for Low- and Very Low-Income Persons.
 - xv. 24 CFR part 146: Non-discrimination on the Basis of Age in HUD Programs or Activities Receiving Federal Financial Assistance.
- xvi. 24 CFR 570.206(c): Fair Housing Activities.
- xvii. 24 CFR 570.487(b): Affirmatively Furthering Fair Housing.
- xviii. 24 CFR 570.487(e): Architectural Barriers Act and Americans with Disabilities Act (State Community Development Block Grant Grantees).
- xix. 24 CFR 570.490(a)-(b): Recordkeeping requirements.
- xx. 24 CFR 570.491: Performance Reviews and Audits.
- xxi. 24 CFR 570.495(b): HCDA Section 109 nondiscrimination.
- xxii. 24 CFR 570.506(g): Fair Housing and equal opportunity records.
- xxiii. 24 CFR 570.601: Affirmatively Further Fair Housing.
- xxiv. 24 CFR 570.608 and Part 35: Lead-Based Paint.
- xxv. 24 CFR 570.614: Architectural Barriers Act and Americans with Disabilities Act.

xxvi. 24 CFR 570.904: Equal Opportunity and Fair Housing Review

xxvii. 24 CFR 570.912: Nondiscrimination compliance

H. <u>CONTRACTING WITH SMALL AND MINORITY FIRMS AND WOMEN'S BUSINESS ENTERPRISES</u>

1. Contractor/Consultant shall take all necessary affirmative steps to ensure contracting opportunities are provided to small, minority-owned, woman-owned, and veteran-owned businesses, and labor area surplus firms. As used in this contract, the terms "minority-owned business," women-owned business," and "veteran-owned business" means a business that is at least fifty-one percent (51%) owned and controlled by minority group members, women, or veterans. For purposes of this definition, "minority group members" are African-Americans, Spanish-speaking, Spanish surnamed or Spanish-heritage Americans, Asian-Americans, and Native Americans. Consultant may rely on written representations by businesses regarding their status as minority, women and veteran businesses in lieu of an independent investigation.

2. Affirmative steps shall include:

- a. Placing qualified small and minority-, veteran- and women-owned businesses on solicitation lists;
- b. Ensuring that small and minority-, veteran- and women-owned businesses are solicited whenever they are potential sources, for goods and/or services required in furtherance of the Contract;
- c. Dividing total requirements, when economically feasible, into smaller tasks or quantities to permit maximum participation by small and minority-, veteran- and women-owned businesses;
- d. Establishing delivery schedules, where the requirement permits, which encourage participation by small and minority-, veteran- and women-owned businesses; and
- e. Using the service and assistance, as appropriate, of organizations such as the Small Business Administration, and the Minority Business Development Agency of the U.S. Department of Commerce; and
- f. Requiring the subcontractor, if subcontracts are to be let, to take the affirmative steps listed in subparagraphs (a) through (e) of this section.

I. <u>ENVIRONMENTAL REGULATORY COMPLIANCE</u>

To the extent applicable, Contractor/Consultant must comply with HUD regulations found at 24 CFR Parts 50 and 58, implementing the National Environmental Policy Act ("NEPA"), 42 U.S.C. §4321 et seq., and other Federal environmental requirements, including but not limited to:

- 1. Floodplain management and wetland protection:
 - a. Executive Order 11990, Protection of Wetlands (May 24, 1977) (42 FR 26961), 3 CFR, 1977 Comp., p. 121, as interpreted by HUD regulations at 24 CFR 55, particularly sections 2 and 5 of the order;
 - b. Executive Order 11988, Floodplain Management, May 24, 1977 (42 FR 26951), 3 CFR, 1977 Comp., p. 117, as interpreted in HUD regulations at 24 CFR part 55, particularly section 2(a) of the order;
- 2. The Coastal Zone Management Act of 1972 (16 U.S.C. § 1451 et seq.), as amended, particularly sections 307(c) and (d) (16 U.S.C. §§1456(c) and(d));
- 3. In relation to water quality:

Revised 2/26/2018 8

- a. Executive Order 12088, as amended by Executive Order 12580, relating to the prevention, control and abatement of water pollution;
- b. The Safe Drinking Water Act of 1974 (42 U.S.C. §§ 201, 300(f) et seq. and U.S.C. §349), as amended, particularly Section 1424(e) (42 U.S.C. §§ 300h-303(e)), which is intended to protect underground sources of water. No commitment for federal financial assistance can be entered into for any project which the U.S. Environmental Protection Agency ("EPA") determines may contaminate an aquifer which is the sole or principal drinking water source for an area (40 CFR 149); and
- c. The Federal Water Pollution Control Act of 1972, as amended, including the Clean Water Act of 1977, Public Law 92-212 (33 U.S.C. §1251, et seq.) which provides for the restoration and maintenance of the chemical, physical and biological integrity of the nation's water.
- Endangered Species Act of 1973 (16 U.S.C. §1531 et seq.), as amended, particularly section 7 (16 U.S.C. §1536);
- 5. The Fish and Wildlife Coordination Act of 1958, as amended;
- 6. Wild and Scenic Rivers Act of 1968 (16 U.S.C. § 1271 et seq.), particularly sections 7(b) and (c) (16 U.S.C. §1278(b) and (c));
- 7. Executive Order 11738 (Nixon), Sept. 10, 1973, providing for administration of the Clean Air Act and the Federal Water Pollution Control Act With Respect to Federal Contracts, Grants, or Loans, and EPA regulations (40 CFR 15);
- 8. The Clean Air Act of 1970 (42 U.S.C. § 7401 et seq.) as amended, particularly sections 176(c) and (d) (42 U.S.C. § 7506(c) and (d)), and 40 CFR 6, 51, 93, which prohibits engaging in, supporting in any way, providing financial assistance for, licensing or permitting, or approving any activity which does not conform to State or Federal implementation plans for national primary and secondary ambient air quality standards.
- 9. The Farmland Protection Policy Act of 1981, 7 U.S.C.A. §4201 et seq., particularly sections 1540(b) and 1541 (7 U.S.C. §4201(b) and §4202), and Farmland Protection Policy, 7 CFR 658, which require recipients of federal assistance to minimize the extent to which their projects contribute to the unnecessary and irreversible commitment of farmland to nonagricultural uses;
- 10. Noise abatement and control requirements at 24 CFR 51B:
- 11. Explosive and flammable operations requirements at 24 CFR 51C;
- 12. Requirements at 24 CFR 58.5(i) relating to toxic chemicals and radioactive materials;
- Environmental Justice, Executive Order 12898—Federal Actions to Address Environmental Justice in Minority Populations and Low-Income Populations, February 11, 1994 (59 FR 7629), 3 CFR, 1994 Comp. p. 859.

J. EQUAL EMPLOYMENT OPPORTUNITY

 All federally assisted construction contracts must include the equal opportunity clause provided under 41 CFR §60-1.4(b). Federally assisted construction contracts include any agreement or modification thereof between any applicant and a person for construction work which is paid for in whole or in part with funds obtained from the federal government. Construction work is defined as "the construction, rehabilitation, alteration, conversion, extension, demolition or repair of buildings, highways, or other changes or improvements to real property, including

Revised 2/26/2018 9

facilities providing utility services. The term also includes the supervision, inspection, and other onsite functions incidental to the actual construction." 41 CFR §60-1.3.

2. Pursuant to 41 CFR §60-1.4(b), the following language shall be included in all federally assisted construction contracts and subcontracts:

During the performance of this contract, the contractor agrees as follows:

- (1) The contractor will not discriminate against any employee or applicant for employment because of race, color, religion, sex, sexual orientation, gender identity, or national origin. The contractor will take affirmative action to ensure that applicants are employed, and that employees are treated during employment without regard to their race, color, religion, sex, sexual orientation, gender identity, or national origin. Such action shall include, but not be limited to the following: Employment, upgrading, demotion, or transfer; recruitment or recruitment advertising; layoff or termination; rates of pay or other forms of compensation; and selection for training, including apprenticeship. The contractor agrees to post in conspicuous places, available to employees and applicants for employment, notices to be provided setting forth the provisions of this nondiscrimination clause.
- (2) The contractor will, in all solicitations or advertisements for employees placed by or on behalf of the contractor, state that all qualified applicants will receive considerations for employment without regard to race, color, religion, sex, sexual orientation, gender identity, or national origin.
- (3) The contractor will not discharge or in any other manner discriminate against any employee or applicant for employment because such employee or applicant has inquired about, discussed, or disclosed the compensation of the employee or applicant or another employee or applicant. This provision shall not apply to instances in which an employee who has access to the compensation information of other employees or applicants as a part of such employee's essential job functions discloses the compensation of such other employees or applicants to individuals who do not otherwise have access to such information, unless such disclosure is in response to a formal complaint or charge, in furtherance of an investigation, proceeding, hearing, or action, including an investigation conducted by the employer, or is consistent with the contractor's legal duty to furnish information.
- (4) The contractor will send to each labor union or representative of workers with which he has a collective bargaining agreement or other contract or understanding, a notice to be provided by the agency contracting officer, advising the labor union or workers' representatives of the contractor's commitments under section 202 of Executive Order 11246 of September 24, 1965, and shall post copies of the notice in conspicuous places available to employees and applicants for employment.
- (5) The contractor will comply with all provisions of Executive Order 11246 of September 24, 1965, and of the rules, regulations, and relevant orders of the Secretary of Labor.
- (6) The contractor will furnish all information and reports required by Executive Order 11246 of September 24, 1965, and by the rules, regulations, and orders of the Secretary of Labor, or pursuant thereto, and will permit access to his books, records, and accounts by the contracting agency and the Secretary of Labor for purposes of investigation to ascertain compliance with such rules, regulations, and orders.

Revised 2/26/2018

- (7) In the event of the contractor's noncompliance with the nondiscrimination clauses of this contract or with any of such rules, regulations, or orders, this contract may be canceled, terminated, or suspended in whole or in part and the contractor may be declared ineligible for further Government contracts in accordance with procedures authorized in Executive Order 11246 of September 24, 1965, and such other sanctions may be imposed and remedies invoked as provided in Executive Order 11246 of September 24, 1965, or by rule, regulation, or order of the Secretary of Labor, or as otherwise provided by law.
- (8) The contractor will include the provisions of paragraphs (1) through (8) in every subcontract or purchase order unless exempted by rules, regulations, or orders of the Secretary of Labor issued pursuant to section 204 of Executive Order 11246 of September 24, 1965, so that such provisions will be binding upon each subcontractor or vendor. The contractor will take such action with respect to any subcontract or purchase order as may be directed by the Secretary of Labor as a means of enforcing such provisions including sanctions for noncompliance: Provided, however, that in the event the contractor becomes involved in, or is threatened with, litigation with a subcontractor or vendor as a result of such direction, the contractor may request the United States to enter into such litigation to protect the interests of the United States.

Revised 2/26/2018

ATTACHMENT "B"

ATTACHMENT TO STATEMENT OF ASSURANCES, SECTION 3 REQUIREMENTS AND CERTIFICATIONS

To the extent that Contractor utilizes any subcontractors, Contractor shall require and ensure that each subcontractor comply with all *applicable* federal CDBG-DR laws, guidelines and standards as well as codes, regulations and workers' safety rules that are administered by federal agencies (EPA, OSHA, and DOT), state agencies (state OSHA and DEP), and any other local regulations and standards (i.e. building codes) that may apply.

A. SECTION 3 REQUIREMENTS

Definitions:

- Low-Income: Low-income is used in the Section 3 regulation to include both low- and very low-income individuals. Low-income is defined as 80% or below the median income of that area. Very low-income is defined as 50% or blow the median income of that area. Local income levels can be obtained online at: http://www.huduser.org/DATASETS/il.html.
- New Hire: Full-time employee for a new permanent, temporary, or seasonal position that is created during the expenditure of Section 3 covered financial assistance.
- Section 3: Section 3 is a provision of the Housing and Urban Development Act of 1968, which recognizes that HUD funds are typically one of the largest sources of federal funding expended in communities through the form of grants, loans, entitlement allocations and other forms of financial assistance. Section 3 is intended to ensure that when employment or contracting opportunities are generated because a covered project or activity necessitates the employment of additional persons or the awarding of contracts for work, preference must be given to low- and very low-income persons or business concerns residing in the community where the project is located. Section 3 is both race and gender neutral. The preferences provided under this regulation are based on income level and location.
- Section 3 Business Concern: Businesses that can provide evidence that they meet one of the following: 1) Business is owned by a Section 3 resident; or 2) 51 percent or more owned by Section 3 residents; or 3) at least 30 percent of its full time employees include persons that are currently Section 3 residents, or within three years of the date of first employment with the business concern were Section 3 residents; or 4) provides evidence, as required, of a commitment to subcontract in excess of 25 percent of the dollar award of all subcontracts to be awarded to businesses that meet the qualifications above.
- Section 3 Resident: A "Section 3 resident" is: 1) a public housing resident; or 2) a low- or very low-income person residing in the metropolitan area or Non-metropolitan County in which the Section 3 covered assistance is expended.
- 2. NJ DCA Sandy Recovery Division (SRD)

- a. The successful bidder shall provide a Section 3 Utilization Plan (see attached Section 3 Plan Template) prior to contract award. The Section 3 Plan must include specific information regarding the following:
 - i. Identification of the Project Area;
 - ii. Identification of past experience with Section 3 and whether goals have been met;
 - iii. Specific information about the contractor's current workforce (payroll reports, etc.);
 - iv. Specific plans for hiring Section 3 eligible residents;
 - v. Specific plan for engaging Section 3 designated businesses and, if applicable, each HUD Section 3 certified business that will participate in the contract;
 - vi. A description of work each named Section 3 Business will perform with the dollar amount of participation;
 - vii. A signed Statement of Section 3 Utilization Commitment regarding Section 3 requirements;
 - viii. A firm commitment to include the HUD Section 3 Clause in all subcontracts; and
 - ix. A firm commitment to conduct aggressive outreach and notification to potential Section 3 residents and businesses of hiring opportunities using site signage, flyers, etc.
- b. Contractor shall perform outreach with outside organizations to identify workforce development opportunities and to facilitate the hiring of Section 3 Residents and Section 3 Businesses. See sample forms provided.
 - Targeted Outreach Organizations include Public Housing Authorities in impacted areas, New Jersey One Stop Career Centers, Urban League, NAACP, Hispanic Chamber of Commerce, Small Business Administration (SBA) Development Centers.
 - ii. To find Section 3 residents, New Jersey has NJ One Stop Career Centers throughout the state, which are available to assist in posting available jobs and finding qualified individuals. Their job posting website is: http://jobs4jersey.com. These centers have the ability to post job openings to their website and send out e-mails to qualified individuals.
 - iii. To find Section 3 businesses, HUD has a Section 3 Business Registry. Qualified Section 3 businesses can be found at https://portalapps.hud.gov/Sec3BusReg/BRegistry/BRegistryHome. Section 3 eligible business concerns have the ability to "self-certify" on the HUD Registry. In addition, Section 3 eligible business concerns can register with

their local housing authority as a Section 3 business and obtain certification. Note that at any time NJ DCA-SRD can request proof and documentation of eligibility from the Section 3 business concern.

- c. Contractor and all sub-contractors must submit documentation demonstrating their efforts to reach the Section 3 contracting, hiring, and training goals using appropriate forms that identify their efforts. See sample forms provided.
- d. Contractor and all sub-contractors must submit with each invoice the Contractor Information Form and Section 3 Resident Certification Form, identifying new employees.
- e. Contractor and all sub-contractors must submit with each invoice the Contractor Information Form and Section 3 Business Concern Certification Form, identifying subcontractors.
- f. NJ DCA-SRD has designated a Section 3 Coordinator to ensure businesses are in compliance with HUD and NJ DCA-SRD's Section 3 guidelines. The Section 3 Coordinator will be responsible for overseeing the implementation of all Section 3 Utilization Plans approved by Subrecipients and that such plans are an official part of the contract. The Section 3 coordinator is available to answer questions from the Subrecipients.

CONTRACTORS CERTIFICATION OF ELIGIBILITY

To be submitted prior to award of contract

The bidder certifies that to the best of its knowledge and belief, neither it, nor any person or firm which has an interest in the contractor's firm, nor any of the contractor's subcontractors, is ineligible to:

(1)	be awarded contracts by any agency of the United States	s Government of HUD; or,
(2)	Participate in HUD programs pursuant to 24 CFR part 24	4.
	Name of Bidder	
	Address	<u> </u>
Ву	Signature	
¥	Print Name and Title	

Date

CERTIFICATION OF BIDDER REGARDING SECTION 3 To be submitted prior to award of contract

Name of Bidder		Project Number
The undersi	gned hereby certifies that:	
1.	Section 3 provisions are included in the Contra	act,
	A written Section 3 plan in compliance with the Template (Attachments B and C hereto) will be the contract (if bid equals or exceeds \$100,000).	e prepared and submitted prior to the award of
Print Name	and Title	
Signature		Date

SUCCESSFUL BIDDER SECTION 3 PLAN FORMAT

To be submitted prior to award of contract

If award is received, ______ (name of Bidder) agrees to implement the

and bu	ing specific affirmative action steps direct sinesses within Woodbridge Township.	ed at mercasing the		ower mco.	me residen
1.	To ascertain from the locality's CDBG pa project area, and where advantageous, se implementing the affirmative action plan	gram official the exa the assistance of lo	ect boundaries of cal officials in p	of the Secti preparing a	on 3 covere
2.	To attempt to recruit from within the mun	cipalities the necessa	ary number of l	ower incor	ne resident
3. 4. 5. 6. 7. 8. 9. 10.	through local advertising media, signs plants organizations, and public or private instituted Service Employment and Redevelopment League, Concentrated Employment Programment To maintain a list of all lower income are referral from any source, and to employ signs.	ted at the proposed sitions operating within (SER), Opportunities are, Hometown Plan, residents who have a chause in all subcontain all required document are exempt.) He associations to secontain all required document are correspondence, memorataken. The proposed in the company or again 3 plan. contracts to be award to the contracts to the contr	ite for the projet nor serving the U.S. Emapplied either divise eligible and stracts over \$10 mentation. (Lost ure their coope e notified of peroranda, etc., where the serving serving serving serving serving the serving serving serving the serving servin	ect, and content on Center (aployment son their own if a vacan 0,000, to oans, grants, tration for the inding substituted of the comportunity of the composition of t	nmunity rea, such as (OIC), Urba Service. In or on acy exists. Ibtain all It, contracts, This program contractual ment that all acy Officer to
				<u>_</u>	
	± 121			*	
Name (of Bidder				
i vanie (
- vanie v					
Signatu	ıre				

CERTIFICATION OF PROPOSED SUBCONTRACTOR REGARDING SECTION 3 To be submitted prior to award of contract

Name of S	Subcontractor	Project Name and Number
The under	rsigned hereby certifies that:	
1.	Section 3 provisions are included	n the Contract.
2.	A written Section 3 plan in complete (Attachments B and C has the contract (if the subcontract equations)	ance with the Section 3 Plan Format and Utilization Plan ereto) will be prepared and submitted prior to the award of als or exceeds \$100,000).
Print Nam	e and Title	
Signature		Date

ATTACHMENT "C"

Section 3 Utilization Plan Template

SECTION 3 PLAN

This document serves as the Section 3 Plan for ______ (insert Project Name) in compliance with the requirements of Section 3 of the Housing and Urban Development Act of 1968, as amended.

The purpose of Section 3 of the Housing and Urban Development Act of 1968, as amended (12. U.S.C. 1701u) (Section 3), is to ensure that training, employment and other economic opportunities generated by certain HUD financial assistance shall, to the greatest extent feasible, and consistent with existing Federal, State and Local laws and regulations, be directed to the greatest extent possible to low- and very low-income persons, particularly those who are recipients of government assistance for housing, and to business concerns, which provide economic opportunities to low- and very low-income persons.

NUMERICAL GOALS FOR TRAINING AND EMPLOYMENT OPPORTUNITIES

(insert Bidder's name) will, to the greatest extent feasible, when awarding contracts or providing training and/or employment opportunities for activities or projects subject to the requirements of Section 3, strive to comply with the goals established in this section.

The numerical goals established in this section represent minimum numerical targets.

Training and employment opportunities will be made available to Section 3 residents as follows:

(i) 30 percent of the aggregate number of new hires/training opportunities resulting from funds awarded.

PREFERENCE FOR SECTION 3 RESIDENTS IN TRAINING AND EMPLOYMENT OPPORTUNITIES

In providing training and employment opportunities, generated from the expenditure of Section 3 activities to Section 3 residents, the following order of preference will be followed:

Highest Priority: Low- and very-low income residents certified as Section 3 eligible residing in the services area or municipality where the project is located.

Second Priority: Section 3 residents of the County in which the project is taking place.

Third Priority: Participants of public and social service programs.

Third Priority: Other Public Housing residents.

Fourth Priority: Participants in Youth build programs.

Fifth Priority: Other Section 3 residents, including residents of the Metropolitan area or non-Metropolitan county.

LIST OF STRATEGIES TO BE ADOPTED FOR COMPLIANCE WITH THE STATED EMPLOYMENT, TRAINING AND CONTRACTING GOALS

In compliance with the Section 3 Plan requirements, the Bidder must submit specific information about their current workforce (payroll reports, etc.) as of the date the Section 3 Plan is submitted for approval along with anticipated new hires. A list of employees can be submitted on the Existing Worker Utilization Report Form or an official company form that includes the same information requested on the Existing Worker Utilization Report Form.

The Bidder must also develop a list of strategies to be adopted for compliance with the stated employment, training and contracting goals.

Contracts in excess of \$100,000 must include the Section 3 Clause.

PLAN FOR SECTION 3 TRAINING AND EMPLOYMENT

Name of Bidder:	_		
Project Name:			

Job Category	Total Estimated Positions Needed for Project Number Positions Od by Perma Employ		Number of Positions to be filled with Section Residents	
* 1				
			3	

EXISTING WORKER UTILIZATION REPORT FORM

Name of Bidder:		
Project Name:	0	

COMPLETE THE INFO	COMPLETE THE INFORMATION FOR <u>ALL</u> EMPLOYEES					Trade	de Classification			tion	
Name of Employee	Employee ID (If SSN, last four Digits)	Address (street address and zip code)	Date of Hire	Yes	No		Journeyman	Helper	Apprentice	Trainee	Other
28	3	<u> </u>			M				-		
14	(9)										
ii,	29									=	
= =											
							. 85				
					OX.						
E 3-							YA.				
WOR	EKFORCE GOALS	: SECTION 3 - 30% OF NEV	V HID	RES							

NUMERICAL GOALS FOR CONTRACTING ACTIVITIES:

These goals apply to contract awards in excess of \$100,000 in connection with a Section 3 eligible project, and it applies to contractors, subcontractors, developers, and/or sub-recipients.

_____ (insert Bidder's name) commits to award to Section 3 business concerns:

- 1. At least 10 percent of the total dollar amount of all Section 3 covered construction contracts.
- 2. At least 3 percent of the total dollar amount of all other Section 3 covered contracts.

PREFERENCE FOR SECTION 3 BUSINESS CONCERNS

The following order of preference will be followed when providing contracting opportunities to Section 3 businesses:

Highest Priority: Section 3 business concerns that provide economic opportunities for Section 3 residents in the service area or municipality in which the Section 3 covered project is located.

Second Priority: Participants of public and social service programs.

Third Priority: Other Section 3 residents.

PLAN FOR SECTION 3 SUB-CONTRACTING

Name of Bidder:	-		
Project Name:	_		

Total Contract Bid	Number of	Total Subcontracts	Total Section 3	Sect	ion 3	
Value (\$)	Sub-Contracts	Dollar Value (\$)	Subcontracts Dollar Value (\$)	Percent Proposed	Percent Required	
					10	
					-	
	10					
		(1-)				

STATEMENT OF SECTION 3 UTILIZATION COMMITMENT

In compliance with the requirements of Section 3 of the Housing and Urban Development Act of 1968, as amended, I the undersigned certify that I am fully empowered to enter into this Statement of Section 3 Utilization Commitment on behalf of this company I am certifying that the information contained within this Section 3 Utilization Plan is accurate and correct and that I understand that the NJ DPMC may impose penalties and sanctions for the submission of any false and inaccurate statements within this document.

Bidder Authorized Representative		
Signature of Authorized Representative		
Title		
Bidder Section 3 Coordinator (Leave blank if the same as authorized representative)	=======================================	
E-mail Address	Phone	
Bidder Name		
Bidder Complete Address	-	

SECTION 3 CLAUSE

All contracts subject to the Section 3 requirements will include the following clause:

- A. The work to be performed under this contract is subject to the requirements of Section 3 of the Housing and Urban Development Act of 1968, as amended, 12 U.S.C. 1701u (Section 3). The purpose of Section 3 is to ensure that employment and other economic opportunities generated by HUD assistance or HUD-assisted projects covered by Section 3, shall, to the greatest extent feasible, be directed to low- and very low-income persons, particularly persons who are recipients of HUD assistance for housing.
- B. The parties to this contract agree to comply with HUD's regulations in 24 CFR part 135, which implement Section 3. As evidenced by their execution of this contract, the parties to this contract certify that they are under no contractual or other impediment that would prevent them from complying with the part 135 regulations.
- C. The contractor agrees to send to each labor organization or representative of workers with which the contractor has a collective bargaining agreement or other understanding, if any, a notice advising the labor organization or workers' representative of the contractor's commitments under this Section 3 clause, and will post copies of the notice in conspicuous places at the work site where both employees and applicants for training and employment positions can see the notice. The notice shall describe the Section 3 preference, shall set forth minimum number and job titles subject to hire, availability of apprenticeship and training positions, the qualifications for each; and the name and location of the person(s) taking applications for each of the positions; and the anticipated date the work shall begin.
- D. The contractor agrees to include this Section 3 clause in every subcontract subject to compliance with regulations in 24 CFR part 135, and agrees to take appropriate action, as provided in an applicable provision of the subcontract or in this Section 3 clause, upon a finding that the subcontractor is in violation of the regulations in 24 CFR part 135. The contractor will not subcontract with any subcontractor where the contractor has notice or knowledge that the subcontractor has been found in violation of the regulations in 24 CFR part 135.
- E. The contractor will certify that any vacant employment positions, including training positions, that are filled (1) after the contractor is selected but before the contract is executed, and (2) with persons other than those to whom the regulations of 24 CFR part 135 require employment opportunities to be directed, were not filled to circumvent the contractor's obligations under 24 CFR part 135.
- F. Noncompliance with HUD's regulations in 24 CFR part 135 may result in sanctions, termination of this contract for default, and debarment or suspension from future HUD assisted contracts.
- G. With respect to work performed in connection with Section 3 covered Indian housing assistance, Section 7(b) of the Indian Self-Determination and Education Assistance Act (25 U.S.C. 450e) also applies to the work to be performed under this contract. Section 7(b) requires that to the greatest extent feasible (i) preference and opportunities for training and employment shall be given to Indians, and (ii) preference in the award of contracts and subcontracts shall be given to Indian organizations and Indian-owned Economic Enterprises. Parties to this contract that are subject to the provisions of Section 3 and Section 7(b) agree to comply with Section 3 to the maximum extent feasible, but not in derogation of compliance with Section 7(b).

Table of Contents

			PAGE NO.		
Instructions to	Page 1 – 83				
TECHNICAL	PAGE NO.				
Division 1 - G	eneral Requirem	ents			
Section Section Section Section Section	on 011100 on 012100 on 013000 on 013216 on 014113 on 014523	Summary Allowances Administrative Requirements Construction Sequence Regulatory Compliance Testing and Inspection Services	011100-1 012100-1 013000-1 013216-1 014113-2 014523-1		
Section Sectio	on 015100 on 015526 on 015626 on 016100 on 017800	Temporary Utilities Traffic Controls Temporary Fencing Product Requirements Closeout Submittals	015100-1 015526-1 015626-1 016100-1 017800-1		
Section	on 020590 on 020700	Removal of Asbestos Materials Demolition	020590-17 020700-7		
Division 22 – I Section	Mechanical on 220000	Plumbing	220000-2		
Section	Earth Work on 312300 on 312500 Exterior Improve	Excavation, Backfilling, and Grading Erosion and Sedimentation Controls	312300-3 312500-3		
	on 329200	Turf and Grasses	329200-3		
Appendix A Drawings Appendix B Asbestos Tables and Laboratory Test Results Appendix C Intentionally Omitted Appendix D Submittal Log Appendix E Sample Contractor Warranty Appendix F HUD CDBG-DR Forms (executed forms must be submitted with each invoice) Appendix G Certification of Asbestos Abatement Letter Appendix H Certification of Clean Fill Material Letter Appendix I Certification of Imported Topsoil Material Letter Appendix J Intentionally Omitted Appendix K DPMC ACM Waiver Request and Approval for 10 Day Notification Appendix L Intentionally Omitted					

TABLE OF CONTENTS Rev. 12/10/2018

STATE OF NEW JERSEY DEPARTMENT OF THE TREASURY DIVISION OF PROPERTY MANAGEMENT AND CONSTRUCTION



REVISED DECEMBER 2015

INSTRUCTIONS TO BIDDERS AND GENERAL CONDITIONS

TABLE OF CONTENTS

INSTRU	JCTIONS TO BIDDERS	
IB 1 Bid	Proposals	5
IB 2 Bid	Modification	7
IB 3 Con	sideration of Bid	7
IB 4 Awa	ards	8
IB 5 Qua	lification of Bidders	8
	osit and Bid Bond	
	formance and Payment Bond	
	letins and Interpretations	
	ignments	
	deral Excise Taxes and State Sales Tax	
	strictive Specifications	
	fer of Gratuities	
12 01		. 12
GENER	AL CONDITIONS	
A DTICI	E 1 - GENERAL PROVISIONS	15
1.1	Definitions	
1.1	Contract Documents to be provided by DPMC	
1.3	Intent of the Contract	
1.3		
	Workdays	
1.5	Assignments	
1.6	State Sales Tax	
	E 2 - OWNER/DPMC	
2.1	DPMC's Representation	
2.2	Right to Perform Work	
2.3	Means and Methods	
	LE 3 - Architect/Engineer	
3.1	Duties and Responsibilities	
3.2	Progress Meetings	
3.3	Site Observations	
3.4	Shop Drawings and Submittals and Invoices	
3.5	Payment Approvals	
	E 4 - THE CONTRACTOR	
4.1	Review of the Contract Documents and Field Conditions	
4.2	Insurance	
4.3	Permits, Laws, and Regulations	
4.4	Responsibility for the Work	
4.5	Indemnification	
4.6	Supervision	
4.7	Shop Drawings and Other Submittals	
4.8	As-Built Drawings	
4.9	Excavations, Cutting and Patching	
4.10	Testing	. 30

4.11	Equipment and Materials	31	
4.12	Temporary Facilities		
4.13	Storage and Site Maintenance		
4.14	Cut-overs and interruptions		
4.15	Protection/Safety		
4.16	Uncovering and Correction of Work		
4.17	Layout and Dimensional Control		
4.18	Project Sign		
4.19	Security		
4.20	DPMC Field Office		
4.21	Photographs		
4.22	Repair of Finished Surfaces, Applied Finishes, Glass		
ARTIC	LE 5 - SUBCONTRACTORS		
5.1	Subcontractors and Material Supplier Approvals	44	
5.2	Contractor-Subcontractor Relationship		
ARTIC	LE 6 - CONSTRUCTION PROGRESS SCHEDULE		
6.1	General		
6.2	Construction Progress Schedule (Critical Path Method CPM Consultan		
Retai	ned by the State)		
6.3	Construction Progress Scheduling Provided by the Contractor		
ARTIC	LE 7 - CONTRACT DURATION/TIME OF COMPLETION		
7.1	Contract Duration/Notice to Proceed		
7.2	Substantial Completion	58	
7.3	Final Completion.		
7.4	Partial Occupancy for Use	59	
7.5	Delay, Disruption and Interference		
ARTIC	LE 8 - CLOSE-OUT		
8.1	Close-out Procedures/Final Payment	62	
8.2	Operations, Equipment and Maintenance Manuals		
8.3	Training		
8.4	Guarantee	63	
ARTIC	LE 9 - PAYMENTS	64	
9.1	Invoices	64	
9.2	Interest	64	
9.3	Schedule of Values and Final Payment		
9.4	Certification of Payments to Subcontractor		
9.5	Stored Materials		
9.6	Allowances	67	
9.7	Retainage	67	
9.8	Miscellaneous 68		
	LE 10 - CHANGES IN THE WORK	70	
10.1	Changes in the Work		
10.2	Acceleration		
	LE 11 - CLAIMS AND DISPUTES		
11.1	Contractor Claims		
11.2	Mutual Rights and Responsibilities of All Contractors and the A/E		

ARTICLE 12 - TERMINATION/SUSPENSION		
12.1	Suspension of the Work / Stop Work	74
12.2	Termination for Cause	74
12.3	Owner's Right to Complete the Work	74
12.4	Termination for Convenience	75
ARTICLE 13 - OTHER REQUIREMENTS		77
13.1	Prevailing Wage	77
13.2	Patents	78
13.3	Right to Audit	78
13.4	Insurance	79
13.5	Assignment of Antitrust Claims	83
END, GENERAL CONDITIONS		

INSTRUCTIONS TO BIDDERS

IB 1 Bid Proposals

IB 1.1 Sealed proposals for the work described herein must be received and time-stamped in the Plan Room, Division of Property Management and Construction (DPMC), 9th Floor, 33 West State Street, P O Box 034, Trenton, NJ 08625-0034. The closing date and time for bids will be stated in the Advertisement for Bid. Bidders are cautioned that reliance on the US Postal Service or other mail delivery or courier service for timely delivery of proposals is at the bidders' risk. Failure by a bidder to have a sealed proposal reach DPMC by the prescribed time will result in rejection of the unopened submission.

IB 1.2 Bids may be accepted on the following branches of work, as applicable:

- a. Lump Sum All Trades
- b. General Construction
- c. Structural Steel
- d. Plumbing
- e. Heating, Ventilating and Air Conditioning
- f. Electrical
- g. Special Categories as may be required
- IB 1.3 Contractors classified by DPMC may obtain contract documents at the DPMC address above, or upon written request, subject to payment of applicable fees. Each bidder is herewith put on notice that its general classification by DPMC is not the sole basis for qualification for the award of work. The Director reserves the right to deny award to any bidder that is not clearly responsible, based upon experience, past performance, financial capability or other material factors, to perform the work required herein.
- IB 1.4 The schedule of non-refundable bid fees below is based upon individual trade construction cost estimates. Upon request and at no cost the DPMC will furnish a set of the contract documents for review in the offices of the division at the address noted in paragraph IB1.1 above.

DPMC BID DOCUMENTS FEE SCHEDULE (PER PACKAGE):

TRADE ESTIMATE	DOCUMENT FEE	MAILING FEE
\$100,000 or less	No charge	\$25.00
Greater than \$100,000	\$ 65.00	\$25.00

IB 1.5 Bid proposals based upon the plans, specifications, general, special and supplementary conditions and bulletins shall be deemed as having been made by the contractor with full knowledge of the conditions therein. Bidders are required to visit the site prior to submitting proposals for the work herein described, and to have thoroughly examined the conditions under which the contract is to be executed, including those reasonably observable conditions of the premises which would hinder, delay, or otherwise affect the performance of the contractor required under the terms of the contract. The State will not allow claims for additional costs as a result of the contractor's failure to become aware of the reasonably observable conditions affecting its required performance. The bidder is required to make appropriate allowances in the preparation of the bid for the

accommodation of such conditions. Bidders must warrant in the bid documents that the bidder is familiar with conditions existing at the site at the time the bid is submitted.

- IB 1.6 Bid proposals shall be submitted on the standard form provided by DPMC, enclosed in a sealed envelope issued by DPMC. The name and address of the bidder must be indicated on the envelope, as well as indication of the DPMC project number, project location and other appropriate identification.
- IB 1.7 All amounts in the bid documents shall be stated in numerical figures only.
- IB 1.8 The bidder must include in the bid envelope: (1) the proposal signed by the bidder, (2) the executed affidavit of non-collusion, (3) the executed Source Disclosure Certification Form as further described in section IB1.11, (4) the executed Disclosure of Investment Activities in Iran Form and (5) bid security as further described in Section IB6.
- IB 1.9 Proposals shall remain open for acceptance and may not be withdrawn for a period of 60 calendar days after the bid opening date.
- IB 1.10 Proposals not submitted and filed in accordance with instructions contained herein and in the Advertisement for Bids may be rejected as non-responsive.

IB 1.11 Procurement Reform

- a. RESTRICTIONS ON POLITICAL CONTRIBUTIONS In accordance with N.J.S.A. 19:44A-20.13, *et seq.*, bidders submitting a bid on or after October 15, 2004, shall be required to submit a Certification and Disclosure Form and Ownership Disclosure Form for all Business Entities. These forms must be submitted by the bidder and approved prior to contract award.
 - N.J.S.A. 19:44A-20.13, *et seq*, prohibits State departments, agencies and authorities from entering into a contract that exceeds \$17,500 with an individual or entity that has made a contribution to that political party committee. N.J.S.A. 19:44A-20.13, *et seq*, further requires the disclosure of all contribution to any political organization organized under section 527 of the Internal Revenue Code that also meets the definition of "continuing political committee" within the meaning of N.J.S.A. 19:44A-3(n) and N.J.A.C. 19:25-1.7. The successful bidder shall also be required to adhere to all continuing obligations contained in N.J.S.A. 19:44A-20.13, *et seq*, regarding contributions and disclosures as required in N.J.S.A. 19:44A-20.13, *et seq*.
- b. Source Disclosure Certification Pursuant to N.J.S.A. 52:34-13.2, *et seq.*, all bidders submitting a proposal shall be required to complete a Source Disclosure Certification that all services will be performed in the United States. The bidder shall disclose the location by country where services under the contract will be performed and any subcontracted services will be performed. The Source Disclosure Certification will be attached to the bid proposal.
- c. MacBride Principles Pursuant to N.J.S.A. 52:34-12.2, a bidder must complete a certification on the DPMC form provided prior to contract award to attest, under penalty of perjury, that neither the person or entity, nor any of its parents, subsidiaries, or affiliates pursuant to N.J.S.A. 52:34-12.2, that the bidder has no ongoing business activities in Northern Ireland and does not maintain a physical

presence therein through the operation of offices, plants, factories, or similar facilities, either directly or indirectly, through intermediaries, subsidiaries or affiliated companies over which it maintains effective control; or will take lawful steps in good faith to conduct any business operations it has in Northern Ireland in accordance with the MacBride principles of nondiscrimination in employment as set forth in N.J.S.A. 52:18A-89.8 and in conformance with the United Kingdom's Fair Employment (Northern Ireland) Act of 1989, and permit independent monitoring of their compliance with those principles. If a contractor who would otherwise be awarded a contract or agreement does not complete the certification, then the Director may determine, in accordance with applicable law and rules, it is in the best interest of the State to award the contract or agreement to the next responsible bidder who has completed the certification. If the Director finds the contractor to be in violation of the principles which are the subject of this law, s/he shall take such action as may be appropriate and provided for by law, rule or contract, including, but not limited to, imposing sanctions, seeking compliance, recovering damages, declaring the contractor in default and seeking debarment or suspension of the contractor.

d. Investment Activities in Iran - Pursuant to N.J.S.A. 52, 32-55, et seq., any person or entity that submits a bid or proposal or otherwise proposes to enter into or renew a contract must complete a certification with their bid on the DPMC form provided to attest, under penalty of perjury, that neither the person or entity, nor any of its parents, subsidiaries, or affiliates, is identified on the Department of Treasury's Chapter 25 list as a person or entity engaging in investment activities in Iran. The Chapter 25 list is found on the Division of Purchase and Property's website at www.state.nj.us/treasury/purchase/pdf/Chapter25List.pdf. Bidders must review this list prior to completing the certification. Failure to complete the certification may render a bidder's proposal non-responsive. If the Director finds a person or entity to be in violation of law, s/he shall take action as may be appropriate and provided by law, rule or contract, including but not limited to, imposing sanctions, seeking compliance, recovering damages, declaring the party in default and seeking debarment or suspension of the party.

IB 2 Bid Modification

- IB 2.1 A bidder may modify its bid proposal by electronic mail or letter at any time prior to the scheduled closing time for receipt of bids, provided such communication is received by the DPMC prior to such closing time. A mailed confirmation of any modification signed by the bidder must have been mailed and time-stamped by the US Postal Service prior to the specified closing time. Such confirmation, whether transmitted electronically or by mail, shall be accompanied by a newly executed affidavit of non-collusion.
- IB 2.2 Communications shall not reveal the basic bid price but shall only provide the amount to be added, subtracted or modified so that the final prices or terms will not be revealed until the sealed proposal is opened. If written confirmation of the telegraphic modification is not received within two working days after the scheduled closing time, no consideration will be given to the telegraphic modification.

IB 2.3 Bids may be withdrawn upon receipt of a bidder's written request prior to the time fixed for the bid opening. A bidder's right to withdraw a bid is lost after a bid has been opened. If an error has been made in the bid amount, request for relief from the bid may be made in writing to the Director. The written request shall be signed by an authorized corporate officer. A determination of whether the bidder will be released shall be at the sole discretion of the Director, who shall issue a finding within five working days of receipt of all pertinent information relating to such request for relief.

IB 3 Consideration of Bids

IB 3.1 Award of Contracts or Rejection of Bids:

- a. Contracts will be awarded to the lowest responsible bidder. The awards will be made, or the bids rejected, within 60 calendar days from the date of the opening of bids. At the discretion of the Director, a bid extension may be requested from the bidders if circumstances warrant an extension.
- b. The Director reserves the right to award the contract on the basis of the single bid for the entire work, or on the basis of a separate bid and alternate, or any combination of separate bids and alternates, which the Director deems best serves the interest of the State.
- c. The Director reserves the right to waive any bid requirements when such waiver is in the best interests of the State, and where such waiver is permitted by law. Such waiver shall be at the sole discretion of the Director.
- d. The Director reserves the right to reject any and all bids when such rejection is in the best interests of the State. The Director also may reject the bid of any bidder which, in the Director's judgment, is not responsible or capable of performing the contract obligations based on financial capability, past performance, or experience. A bidder whose bid is so rejected may request a hearing before the Director by filing a written notice.

IB 3.2 The bidder to be awarded the contract shall execute and deliver the requisite contract documents, including payment and performance bonds, within the time specified. Upon the bidder's failure or refusal to comply in the manner and within the time specified, the Director may either award the contract to the next low responsible bidder or re-advertise for new proposals. In either case, the Director may hold the defaulting bidder and its surety liable for the difference between the applicable sums quoted by the defaulting bidder and the sum which the State may be obligated to pay to the contractor which is contracted to perform and complete the work of the defaulting bidder.

IB 4 Awards

- IB 4.1 In executing a contract, the successful bidder agrees to perform the required work in a good and workmanlike manner to the reasonable satisfaction of the Director, and to complete all work within the number of calendar days specified in its contract.
- IB 4.2 Successful bidders will be notified of the time and place for the signing of contracts. Key requirements in the contract, including, but not limited to, the number of days of performance of the contract, manner and schedule of payments, and other administrative details will be reviewed at the award meeting. The time and place of the first job meeting will be announced at the award meeting.
- IB 4.3 The State reserves the right to award the contract upon the basis of a single bid for the entire work, or on the basis of separate bids for each prime trade when the total of the separate bids is less than the single bid. Alternates will be accepted or rejected in numerical sequence as cited in the bid documents and shall not be selected at random except as provided herein. Add alternates and deduct alternates will be specified separately. The State may choose from the add and deduct alternates without priority between the two groups so long as selection within each group is in numerical sequence from the first to the last. This limitation shall not apply, however, to any alternates concerning proprietary items. The Director, with the approval of the Using Agency, may accept alternates out of sequence, provided the Director states the reasons for so doing, in writing, within five working days following the opening of bids.
- IB 4.4 Should submission of unit prices be required for specified items of work in bid proposals, they will be considered in the evaluation of bids as set forth in the bid proposal form.
- IB 4.5 The successful bidder and all of its subcontractors are required to comply with the requirements of N.J.S.A. 10:5-31 et seq., regarding Equal Employment Opportunity in Public Works Contracts.

IB 5 Oualification of Bidders

- IB 5.1 If the successful bidder is a corporation not organized under the laws of the State of New Jersey or is not authorized to do business in this State (foreign corporation), the award of the contract shall be conditioned upon the prompt filing by the said corporation of a certificate to do business in this State and complying with the laws of this State in that regard. This filing must be made with the Division of Revenue. No award of contract will be made until the Division of Revenue confirms this authorization.
- IB 5.2 The State requires that each contractor, except in the case of a single contractor, shall perform a minimum of 35 percent of the contract work by the contractor's own forces. However, the Director has the sole discretion to reduce this percentage depending upon the nature and circumstances in any particular case, if the Director determines that to do so would be in the best interests of the State, and provided that the bidder submits a written request with the original bid proposal.
- IB 5.3 The State reserves the right to reject a bidder at any time prior to the signing of a contract if information or data is obtained which, in the opinion of the Director, adversely affects the responsibility and/or the capability of the bidder to undertake and to complete the work, regardless of the bidder's previous qualification or classification. The State may

conduct any investigation as it deems necessary to determine the bidder's responsibility and capacity, and the bidder shall furnish all information and data for this purpose as requested by the State.

IB 5.4 Each bidder must be classified by DPMC in accordance with the provisions of the classification statute, NJSA 52:35-1, et seq.,. In the case of a single bid for all of the work, the bidder shall include in the bid the names of its principal subcontractors (in categories as listed in IB1.2 above), which must also be classified in accordance with the said statute.

IB 5.5 At the time of the bid due date, the bidder and the subcontractors must be registered in accordance with "The Public Works Contractor Registration Act", N.J.S.A. 34:11-56.48, et seq. All questions regarding registration shall be addressed to:

Contractor Registration Unit New Jersey Department of Labor Division of Wage & Hour Compliance P O Box 389 Trenton NJ 08625-0389 Telephone: 609-292-9464 FAX: 609-633-8591

IB 5.6 In accordance with N.J.S.A. 52:32-44, *et seq*. Public Law 2001, Chapter 134, all contractors and subcontractors providing goods/services to State agencies and authorities are required to provide the contracting agency or authority with proof of registration with the Department of Treasury, Division of Revenue. The basic registration process involves the filing of Form NJ-Reg., which can be filed online at www.state.nj.us/njbgs/services.html or by calling (609) 292-7077 or (609) 292-1730.

IB 6 Deposit and Bid Bond

- IB 6.1 The Proposal, when submitted, shall be accompanied by a Bid Bond satisfactory to the Director, for the sum of not less than fifty percent (50%) of the Total Bid including alternates, if applicable.
- IB 6.2 The Bid Bond shall be properly filled out, signed, and witnessed.
- IB 6.3 The Bid Bond shall be accompanied by a copy of the power of attorney executed by the surety company or companies. The power of attorney shall set forth the authority of the attorney-in-fact who has signed the bond on behalf of the surety company to bind the company and shall further certify that such power is in full force and effect as of the date of the bond.
- IB 6.4 If the bidder whose proposal is accepted is unable to provide the performance and payment bonds or fails to execute a contract, then such bidder and the bid bond surety, where applicable, shall be obligated to pay to the State the difference between the amount of the bid and the amount which the State contracts to pay another party to perform the work. The bidder and the surety shall pay, upon demand, the entire amount of the State's difference in cost. Should there be a deficiency in excess of the bid deposit, the bidder shall make immediate payment to the State for any such deficiency. Nothing contained herein shall be construed as a waiver of any other legal remedies that the State may have against the contractor.

IB 6.5 Attorneys-in-fact who sign bid bonds or contract bonds must file a certified power-of-attorney with the State indicating the effective date of that power.

IB 7 Performance and Payment Bond

IB 7.1 The successful bidder shall furnish within ten (10) calendar days after notice of award both a performance bond in statutory form in an amount equal to one hundred percent (100%) of the total contract price as security for the faithful performance of this contract and a payment bond in statutory form in amount equal to one hundred percent (100%) of the contract price as security for the payment of all persons and firms performing labor and furnishing materials in connection with this contract. The performance bond and the payment bond may be combined or in separate instruments in accordance with law. If combined, they must be for 200% of the award amount. No contract shall be executed unless and until each bond is submitted to and approved by the State. The surety must be presently authorized to do business in the State of New Jersey. In addition to the other coverage provided, the Bond shall cover all Contract guarantees and any other guarantees/warranties issued by the Contractor.

IB 7.2 The cost of all performance and payment bonds shall be paid for by the successful bidder.

IB 7.3 If at any time the State, for justifiable cause, is dissatisfied with any surety which has issued or proposes to issue a performance or payment bond, the contractor shall, within ten calendar days after notice from the State to do so, substitute an acceptance bond (or bonds). The substituted bond(s) shall be in such form and sum and executed by such other surety or sureties as may be satisfactory to the State. The premiums on such bond(s) shall be paid by the contractor. No contract shall be executed and/or no payment made under a contract until the new surety or sureties shall have furnished such an acceptable bond to the State.

IB 7.4 Bonds must be legally effective as of the date the contract is signed. Each must indicate the contractor's name exactly as it appears on the contract. Current attorney-in-fact instruments and financial statement of the surety must be included with the bonds. Bonds must be executed by an authorized officer of the surety. Bonds furnished under this section shall conform in all respects to the requirement and language of NJSA 2A:44-143 to 147.

IB 8 Bulletins and Interpretations

IB 8.1 No interpretation of the meaning of the plans, specifications or other pre-bid documents will be provided to any bidder unless such interpretation is made in writing to all prospective bidders prior to the opening of bids. Any such interpretations must be identified in bid proposals submitted. Any interpretations which are not entered in accordance with this provision shall be unauthorized and not binding upon the State.

IB 8.2 Every request for an interpretation relating to clarification or correction of the plans, specifications, or other bid documents must be made in writing, addressed to the architect/engineer and the DPMC Director, and must be received at least five (5) working days prior to the date fixed for the opening of the bids. Any and all interpretations, clarifications or corrections and any supplemental instructions must be issued by the Director in the form of written bulletins and mailed by certified mail, return receipt requested, or by electronic notice to all prospective bidders not later than three (3) working days prior to the date of the opening of bids. All bulletins issued shall become part of the

contract documents and shall be acknowledged in all bid proposals. Failure of a bidder to acknowledge receipt of all such bulletins and interpretations by the time of bid opening shall result in its proposal being considered non-responsive, at the option of the Director.

IB 8.3 Each bidder shall be responsible for thoroughly reviewing the contract documents prior to the submission of bids. Bidders are advised that no claim for expenses incurred or damages sustained as a result of any error, discrepancy, omission, or conflict in the contract documents shall be recognized by the State unless, and only to the extent that, a written request for interpretation, clarification or correction has been submitted in compliance with Section IB8.2 and provided the matter has not been addressed by the State through the issuance of a bulletin interpreting, clarifying or correcting such error, discrepancy, omission or conflict.

IB 9 Assignments

IB 9.1 The contractor shall not assign all or any part of this contract without written consent of the State. Money due (or to become due) the contractor hereunder shall not be assigned for any purposes whatsoever.

IB 10 Federal Excise Taxes and State Sales Tax

IB 10.1 In general, bidders, in preparing bids, must take into consideration applicable Federal and State tax laws.

IB 10.2 Materials, supplies or services for exclusive use in erecting structures or buildings or otherwise improving, altering or repairing all State-owned property are exempt from the State sales tax. The successful bidder must submit Division of Taxation form ST13, Exempt Use Certificate, to the seller of all materials, supplies or services that will be incorporated into the Work.

IB 10.3 Bidders must determine the current status and applicability of any tax laws, and the contractor may make no claim based upon any error or misunderstanding as to the applicability of any tax laws.

IB 10.4 Purchases or rentals of equipment are not exempt from any tax under the State Sales Tax Act.

IB 11 Restrictive Specifications

IB 11.1 Should any bidder determine before the bid due date that any portion of the specifications or drawings specify a particular product which can be provided by only one supplier or manufacturer, with the result that competitive prices are not available, the bidder shall immediately notify the Director in writing of such fact.

IB 11.2 If such notice is not given in a timely manner, it shall be assumed that the bidder has included the estimate of such sole source in the bid. However, if the Director is notified in a timely manner of the sole source of supply or manufacture, the Director may order the product re-bid or take other lawful action. Such action shall be at the Director's sole discretion.

IB 12 Offer of Gratuities

IB 12.1 Bidders are advised that the laws of New Jersey (NJSA 52:34-19) make it a misdemeanor to offer, pay or give any fee, commission, compensation, gift or gratuity to any person employed by the State. Also, Executive Order #189 (1988) requires that all requests for proposals and contracts issued by the State specify prohibitions on vendor (contractor) activities, the violation of which shall render the vendor liable to ineligibility for State contracts, pursuant to the debarment procedures set forth in N.J.A.C. 17:19-4.1., et seq. These prohibited activities include the following:

- a. No vendor shall pay, offer to pay, or agree to pay, either directly or indirectly, any fee, commission, compensation, gift, gratuity, or other thing of value of any kind to any State officer or employee or special State officer or employee, as defined by NJSA 52:34D-13b. and e., in the Department of Treasury or any other agency with which such vendor transacts or offers or proposes to transact business, or to any member of the immediate family, as defined by NJSA 52:13D-13i., of any such officer or employee, or any partnership, firm, or corporation with which they are employed or associated, or in which such officer or employee has an interest within the meaning of NJSA 52:13D-13g.
- b. The solicitation of any fee, commission, compensation, gift, gratuity or other thing of value by any State officer or employee or special State officer or employee from any State vendor shall be reported in writing forthwith by the vendor to the Attorney General and the Executive Commission on Ethical Standards.
- c. No vendor may, directly or indirectly, undertake any private business, commercial or entrepreneurial relationship with, whether or not pursuant to employment, contract or other agreement, express or implied, or sell any interest in such vendor to, any State officer or employee or special State officer or employee having any duties or responsibilities in connection with the purchase, acquisition or sale of any property or services by or to any State agency or any instrumentality thereof, or with any person, firm or entity with which he is employed or associated or in which he has an interest within the meaning of NJSA 52:13D-13g. Any relationships subject to this provision shall be reported in writing forthwith to the Executive Commission on Ethical Standards, which may grant a waiver of this restriction upon application of the State offer or employee or special State officer or employee upon a finding that the present or proposed relationship does not present the potential, actuality or appearance of a conflict of interest.
- d. No vendor shall influence, or attempt to influence or cause to be influenced, any State officer or employee or special State officer or employee in his official capacity in any manner which might tend to impair the objectivity or independence of judgment of said officer or employee.
- e. No vendor shall cause or influence, or attempt to cause or influence, any State officer or employee or special State officer or employee to use, or attempt to use, his official position to secure unwarranted privileges or advantages for the vendor or any other person.

f. The provisions cited above in paragraphs IB12.1.a. through e. shall not be construed to prohibit a State officer or employee or special State officer or employee from receiving gifts from or contracting with vendors under the same terms and conditions as are offered or made available to members of the general public subject to any guidelines the State Ethics Commission on Ethical Standards may promulgate under paragraph IB12.1.c. above.

END OF INSTRUCTIONS TO BIDDERS

GENERAL CONDITIONS

ARTICLE 1 - GENERAL PROVISIONS

1.1 DEFINITIONS:

- 1.1.1 <u>Architect/Engineer</u>: The Architect/Engineer ("A/E") is the consultant engaged by the DPMC to prepare the design and perform certain contract administration functions in accordance with the provisions of its contract with the DPMC.
- 1.1.2 <u>Bulletin</u>: A document, issued by DPMC prior to the opening of bids, which supplements, revises or modifies the bid document(s).
- 1.1.3 <u>Change in the Work</u>: A change in the Project and the Contract Documents, including, but not limited to, an increase or decrease in the Work, an acceleration or extension of time for the performance of the Work.
- 1.1.4 <u>Change Order</u>: A written order, directing or authorizing a Change in the Work executed by the DPMC and agreed to by the Contractor (except in the case of unilateral change orders executed by DPMC) that includes all adjustments to work, compensation and/or time warranted by the Change in the Work.
- 1.1.5 <u>Code Official</u>: the individual licensed by the NJ Department of Community Affairs authorized to enforce the NJ Uniform Construction Code (UCC) and approve or reject the Work for NJ UCC compliance.
- 1.1.6 <u>Construction Management Firm or "CMF"</u>: A person or firm that may be engaged by the DPMC to assist DPMC in the administration of its contracts.
- 1.1.7 <u>Contract</u>: The entire and integrated agreement between the Contractor and the DPMC encompassing all of the Contract Documents.
- 1.1.8 <u>Contract Documents</u>: The executed form of Contract, General Conditions, Supplementary Conditions, Supplementary Instructions, Bulletins, plans, specifications, instructions to bidders, addenda, responses to requests for information, Price Proposal, Change Orders, other amendments, including construction change directives, and all exhibits, appendices and documents attached to or referenced in any of the foregoing materials.
- 1.1.9 <u>Contract Limit Lines</u> The lines shown on the Contract Drawings that define the boundaries of the Project, and beyond which no construction work or activities may be performed by the Contractor unless otherwise noted on the drawings or specifications.
- 1.1.10 <u>Contractor</u>: The business entity with whom the DPMC enters a contract for the performance of the construction of a construction Project by the terms set forth in the Contract Documents.
- 1.1.11 <u>Contract Price</u>: The sum stated in the Contract, as it may be adjusted in accordance with the Contract Documents, that represents the total amount payable by the DPMC to the Contractor for performance of the Work.
- 1.1.12 Day: A calendar day, unless otherwise designated.

- 1.1.13 <u>Director</u>: The person authorized by statute to administer the design, engineering and construction of all State buildings and facilities. The Director is the contracting officer representing the State personally or through authorized representatives in all relationships with Contractors, consultants and Architects/Engineers. This includes designees or an authorized administrative contracting officer acting within the limits of his or her authority. The Director or his or her duly authorized representative is the interpreter of the conditions of this contract and the judge of its performance.
- 1.1.14 <u>Division of Property Management and Construction (DPMC)</u>: The State of New Jersey's contracting agency for the design and construction of State facilities.
- 1.1.15 <u>Final Acceptance and Completion</u>: The date following receipt and acceptance by DPMC of all administrative and close-out documents. Following acceptance, the DPMC will issue a Certificate of Final Acceptance and Completion for the Project.
- 1.1.16 Generally Accepted Accounting Principles: The common set of accounting principles, standards and procedures that companies use to compile their financial statements. Accounting records must identify all labor and material costs and expenses, whether they are direct or indirect. The identity must include at least the Project number for direct expenses and/or account number for indirect expenses.
- 1.1.17 <u>NJUCC or Code</u>: The New Jersey Uniform Construction Code which governs the permit and approval process for construction projects.
- 1.1.18 Notice: A written directive or communication given by DPMC to the Contractor to act or perform work or carry out some other contractual obligation, or a written communication to be served by the Contractor upon the State. A notice served on the Contractor will be deemed to have been duly served if delivered to an individual or member of the firm or entity or to an officer of the corporation for whom it was intended. This includes regular mail, e-mail, delivery by courier, or registered or certified mail, or facsimile to the Contractor's business address cited in the Contract documents. A notice from the Contractor to the State shall be deemed to have been duly served only if delivered to the Director or the Director's duly authorized representative.
- 1.1.19 <u>Notice to Proceed</u>: The written communication issued by the DPMC to the Contractor directing the Contractor to begin the Work. The contract calendar day duration period will commence on the effective date noted.
- 1.1.20 <u>Project</u>: The term for the entire public works engagement. It includes the design, construction work and all administrative aspects required to fully complete the engagement.
- 1.1.21 <u>Punch List</u>: The list of incomplete or defective Work, compiled by DPMC and/or its authorized representative, which remains to be completed after achievement of Substantial Completion.
- 1.1.22 <u>Schedule</u>: The time tracking mechanism that establishes the Project's allotted time requirements for completion as more specifically described in Article 6 of these General Conditions. When the construction activity items of the schedule have a monetary value associated with them, the schedule is referred to as a "costed" or "cost-loaded" schedule.

- 1.1.23 <u>Site</u>: The geographical location of the facility or property at which the Work under the Contract is to be performed.
- 1.1.24 <u>State or Owner</u>: The State of New Jersey, acting through DPMC.
- 1.1.25 <u>Subcontractor</u>: The business entity that enters into an agreement with the Contractor for the performance of work or materials under this Contract. Also refers to any agreement between a Subcontractor and any of lower tier Subcontractors. Such an agreement creates no relationship, legal or otherwise, between the DPMC and the Subcontractor(s) and/or lower tier Subcontractor(s).
- 1.1.26 <u>Substantial Completion</u>: The date when all essential requirements of the Contract Documents have been satisfied so that the purpose of the Contract Documents is accomplished, as determined by the DPMC including training of staff by the Contractor on all equipment, and resulting in the issuance of a temporary Certificate of Occupancy, a permanent Certificate of Occupancy or a permanent Certificate of Acceptance and when the Work and the facility can be safely occupied and used in accordance with its intended purpose. DPMC may condition issuance of a Certificate of Substantial Completion upon satisfactory receipt of critical documents.
- 1.1.27 <u>Unit Schedule Breakdown</u>: A detailed list of the Work activities required for Project construction, other elements associated with fulfilling the requirements of the Contract (bonds, insurance, etc.), major items of material, labor or equipment, and the prices associated with each of them.
- 1.2.28 <u>Using Agency:</u> The State department or agency for whom the construction project is being completed.
- 1.1.29 <u>Work</u>: All construction, supervision, labor, material and equipment necessary to complete the obligations under the Contract including Operation and Maintenance Manuals, Punch List completion, and As-Built Documents.

1.2 CONTRACT DOCUMENTS TO BE PROVIDED BY DPMC

Upon Contract award, the DPMC will furnish to the Contractor, free of charge, three copies of the drawings and specifications, and any additional instructions by means of supplemental contract documents as otherwise necessary for the proper execution of the Work, unless otherwise provided in the Contract Documents. Upon request, additional copies of the contract documents will be furnished at the Contractor's expense.

1.3 INTENT OF THE CONTRACT

1.3.1 The drawings, specifications and all of the Contract Documents are intended to require the Contractor to provide for everything necessary to accomplish the proper and complete finishing of all work. For the Project, the Contractor shall perform all of the obligations and work identified in the Contract Documents, regardless of the manner in which it is divided among the trades or the order in which it appears in the Contract Documents. All work and materials included in the specifications and not shown on the drawings, or shown on the drawings and not in the specifications shall be performed and/or furnished by the Contractor. The Contractor shall include any incidental materials

and/or Work not indicated in the drawings and/or the specifications which are nevertheless necessary for the development of the Project and are reasonably inferable from the contract documents and industry practice. The Contractor shall perform all such work and furnish all such materials as if particularly delineated or described in the contract documents as part of the bid proposal.

- 1.3.2 The Contractor acknowledges that in preparing its bid, the Contractor had the obligation to raise any reasonably observable errors, omissions, ambiguities or discrepancies and request an interpretation of the alleged errors, omissions, ambiguities or discrepancies. If the Contractor failed to do so, it will have waived all rights to a Change Order or claim and the Contractor will be responsible to complete the Work as required, consistent with the intent of the Contract Documents as interpreted by the DPMC, without additional compensation.
- 1.3.3 No interpretation of the meaning of the plans, specifications or other Contract Documents provided prior to bid submission shall be binding upon the State for any purpose unless issued in a Bulletin.
- 1.3.4 The Contractor shall abide by and comply with the intent and meaning of the Contract Documents taken as a whole, and shall not take advantage of any error or omission, should any exist. Should the Contractor become aware of the existence of any error, omission or discrepancy, the Contractor shall immediately notify the DPMC and the Architect/Engineer of any such errors, omissions, ambiguities or discrepancies and seek correction or interpretation thereof prior to commencement of the Work at issue. The Architect/Engineer shall issue a written interpretation. The Contractor shall do no work outside of the Contract Documents, unless written authorization to proceed from the DPMC is received by the Contractor.
- 1.3.5 Each and every provision required by law to be inserted in the Contract Documents is deemed to have been inserted therein. If any such provision has been omitted or has not been correctly inserted, then upon application of either party, the Contract may be modified to provide for such insertion or correction.
- 1.3.6 The order of precedence pertaining to interpretation of Contract Documents is as follows:
 - a. Executed Contract
 - b. Bulletins and Instructions
 - c. Supplemental General Conditions
 - d. Specifications and General Conditions
 - e. Drawings, in the following order of precedence:
 - (1) Notes on drawings
 - (2) Large scale details
 - (3) Figured dimensions
 - (4) Scaled dimensions

- 1.3.7 Where there may be a conflict in the Contract Documents not resolvable by application of the provisions of this Article, then the more expensive labor, materials, or equipment shall be assumed to be required and shall be provided by the Contractor.
- 1.3.8 On all work, it shall be the responsibility of the Contractor, by personal inspection of the existing building, facility, plant or utility systems, to ascertain the accuracy of any information given. This shall be the case, whether or not such information is indicated on the drawings, included in the specifications, or shown in any other documentation that is available. The Contractor shall have an affirmative duty to make reasonable inquiry for all available information. The Contractor shall include the costs of all material and labor required to complete the Work based on inspection and reasonably observable conditions.

1.4 WORKDAYS

Regular working hours will be defined in the Contract Documents. Changes thereto may be granted with written approval of the DPMC representative. Any work required to be performed after regular working hours or on Saturdays, Sundays, or legal holidays as specially set forth in the Contract documents, as may be reasonably required and consistent with contractual obligations, shall be performed at the amount set forth in the Contractor's bid without additional expense to the State. The Contractor shall obtain written approval of the DPMC representative for performance of work after regular working hours or on non-regular workdays at least forty-eight (48) hours prior to the commencement of overtime, unless such overtime work is caused by an emergency. If the Contractor seeks such approval for the overtime work, same shall be performed at no additional cost to the DPMC except in the event of an emergency, at which time, the DPMC, in its sole discretion, shall determine if the submitted overtime is compensable.

1.5 ASSIGNMENTS

The Contractor shall not assign all or any part of this Contract without the written consent of the Director. Money due (or to become due) the Contractor hereunder shall not be assigned for any purpose whatsoever without the written consent of the Director.

1.6 STATE SALES TAX

- 1.6.1 Materials, supplies or services for exclusive use in the construction of structures or buildings or otherwise improving, altering or repairing all State-owned property are exempt from the State sales tax.
- 1.6.2 Purchases or rentals of equipment are not exempt from any tax under the State Sales Tax Act.

ARTICLE 2 - OWNER/DPMC

2.1 DPMC'S REPRESENTATION

The DPMC will be represented on the Project by DPMC's designated representative(s). DPMC's designated representative(s) have only those duties that are required of the Owner under this Contract.

2.2 RIGHT TO PERFORM WORK

The DPMC may, and reserves the right to, enter upon the premises at any and all times during the progress of the Work, or cause others to do so, for the purpose of performing any work or installing any apparatus or carrying on any construction not included in the Contract Documents, or for any other reasonable purpose.

The DPMC shall have the right to defer the beginning of Work or to suspend the whole or any part of the Work whenever, in the sole discretion of the DPMC, it may be necessary or expedient for the State to do so.

2.3 MEANS AND METHODS

The State will not be responsible for, nor have control or charge of construction means, methods, techniques, sequences of procedures, or safety precautions and programs in connection with the Work. The State will not be responsible for, nor have control or charge of, the acts or omissions of the Contractor, Subcontractors, or any of their agents or employees, or any other person performing any of the Work.

ARTICLE 3 - ARCHITECT/ENGINEER

3.1 DUTIES AND RESPONSIBILITIES

3.1.1 The Architect/Engineer ("A/E") is the consultant engaged by the DPMC to prepare the design and perform certain contract administration functions in accordance with the provisions of its contract with the DPMC.

3.2 PROGRESS MEETINGS

The Architect/Engineer will attend, chair and issue record minutes of bi-weekly job progress meetings.

3.3 SITE OBSERVATIONS

- 3.3.1 The Architect/Engineer will monitor the execution and progress of the Work. The Architect/Engineer will at all times be provided access to the Work. The Contractor shall provide facilities for such access so as to enable the Architect/Engineer to perform its functions.
- 3.3.2 The Architect/Engineer will not be responsible for, nor have control or charge of construction means, methods, techniques, sequences of procedures, or safety precautions and programs in connection with the Work. The Architect/Engineer will not be responsible for, nor have control or charge of, the acts or omissions of the Contractor, Subcontractors, or any of their agents or employees, or any other person performing any of the Work.

3.4 SHOP DRAWINGS AND SUBMITTALS AND INVOICES

As more specifically described in Article 4, the Architect/Engineer will review, approve or take other appropriate action relating to Contractor's submittals, including shop drawings, product data and samples, and as – built drawings, to assure conformance with the requirements of the Contract. Such actions shall be taken with reasonable promptness. Approval of a specific item shall not indicate approval of an assembly of which the item is a component.

3.5 PAYMENT APPROVALS

- 3.5.1 The Architect/Engineer is responsible for the timely review of all invoices submitted by the Contractor. The Architect/Engineer shall inform the Contractor of any deficiencies therein. When the payment voucher is deemed accurate, the Architect/Engineer shall recommend approval of Contractor invoices.
- 3.5.2 The Architect/Engineer will review and recommend approval of Contractor closeout documentation in conjunction with the final application for payment.

ARTICLE 4 - THE CONTRACTOR

4.1 REVIEW OF THE CONTRACT DOCUMENTS AND FIELD CONDITIONS

- 4.1.1 The Contractor has the duty to thoroughly examine and be familiar with all of the Contract Documents and the Project site. The Contractor shall investigate and accurately determine the nature and location of the Work, the current building equipment and systems, labor and material conditions, and all matters which may in any way affect the Work or its performance.
- 4.1.2 The Contractor shall be deemed to have verified all reasonably observable conditions outside the Contract limit lines to determine whether any conflict exists with the Work that the Contractor is required to perform under the Contract. This includes but is not limited to a check on elevations, utility connections and other site data. If a condition changed from the time of the bid to the time of the issuance of the Notice to Proceed, the Contractor shall notify the Architect/Engineer immediately. The Contractor shall immediately report any conflicts prior to the bid proposal due date or waive any claim for additional compensation arising from such conflict.
- 4.1.3 During the progress of the Work, the Contractor shall immediately report in writing any alleged error, inconsistency, ambiguity or omission in the Contract Documents to DPMC. The Contractor shall not continue with any work that is affected by such alleged error, inconsistency, ambiguity or omission until the DPMC has had the opportunity to respond. Any error, inconsistency, ambiguity or omission shall be addressed pursuant to appropriate procedures set forth in these General Conditions.
- 4.1.4 Following notification of an alleged error, inconsistency, ambiguity or omission, the DPMC may issue supplemental instructions for the proper execution of the Work. The Contractor shall do no work without proper supplemental instructions. In giving such supplemental instructions, the DPMC will have the right to direct the Contractor to make minor changes in the Work without payment of additional monies. This provision is not intended to infringe upon or limit the DPMC's authority to otherwise direct changes in the Work, described elsewhere in these general conditions.
- 4.1.5 Where certain work is shown in complete detail, but not repeated in similar detail in other areas of the drawings, or if there is an indication of continuation with the remainder being shown only in outlines, the Work shown in detail shall be understood to be required in other like portions of the Project.
- 4.1.6 Unless otherwise directed in writing by the DPMC, the Contractor shall perform no portion of the Work without appropriate approvals as may be applicable and required by the Contract Documents.
- 4.1.7 Unless otherwise provided in the Contract Documents, the Contractor shall provide and pay for all labor, equipment, materials, tools, construction equipment and machinery, water, heat, utilities, transportation and other facilities and services necessary for the proper execution, protection, and completion of the Work.

4.2 INSURANCE

The Contractor shall secure and maintain in force, for the term of the Contract, insurance coverage provided in Section 13.4. The Contractor shall provide the State of New Jersey with current certificates of insurance for all coverage and renewals thereof which must contain a provision that the insurance provided in the certificate shall not be canceled for any reason except after thirty (30) calendar day's written notice to the State of New Jersey. If cancellation occurs, the Contractor shall immediately procure new coverage, not allowing any lapse of coverage to occur.

4.3 PERMITS, LAWS, AND REGULATIONS

- 4.3.1 .1 The DPMC shall obtain and pay for the construction permits and inspections (building, plumbing, electrical, elevator and fire), required by the Department of Community Affairs (DCA). When permits are issued by DCA, the appropriate licensed Contractors and/or Subcontractors shall be required to fill out the Contractor section of the Sub-Code Technical Section and sign and affix their raised seal thereto.
- 4.3.2 .2 Unless otherwise provided in the Contract Documents, the Contractor shall secure and pay for all other permits and governmental fees, licenses and inspections necessary for the proper execution and completion of the Work, and which are legally required at the time of receipt of bids.
- 4.3.3 .3 All work must be done in accordance with the NJUCC. No work requiring inspections and approval by construction NJUCC code officials is to be covered or enclosed prior to inspection and approval by the appropriate NJUCC enforcement officials.
- 4.3.4 .4 The Work performed pursuant to this Contract is exempt from local ordinances, codes and regulations as related to the building and the Site on which it is located, except in certain limited circumstances, where construction could adversely affect adjacent property, public sidewalks and/or streets. In those instances, the Contractor shall coordinate its activities with municipal and/or highway authorities having appropriate jurisdiction.
- 4.3.5 Immediately upon receipt of the contract award documents from the DPMC, the Contractor shall notify all utility companies involved regarding utility services required for completion of the Work. Such notification shall be in addition to any notification requirements imposed by law, including, without limitation, the Underground Facility Protection Act, N.J.S.A. 48:2-73, et seq.
- 4.3.6 .6 The Contractor shall perform all soil conservation measures in accordance with County Soil Conservation District requirements.
- 4.3.7 .7 The Contractor shall perform all sewage disposal work in conformance with the regulations of the State's Department of Environmental Protection.
- 4.3.8 .8 The Contractor shall be responsible for obtaining timely NJUCC inspections of the Work from the applicable State agency. The Contractor shall request such

inspections through DPMC authorized representatives allowing for sufficient notice to enable NJUCC inspections to be scheduled without delay to the Work.

- 4.3.9 .9 Consistent with section 4.4 of these General Conditions, the Contractor shall be responsible for its own actions and protect, defend and indemnify the State from all fines, penalties or loss incurred for, or by reason of, the violation of any municipal ordinance or regulation or law of the State while the said work is in progress.
- 4.3.10 10 The Contractor shall comply with the Federal Occupational Safety and Health Act of 1970 and all of the rules and regulations promulgated there under.
- 4.3.11 If the Contractor causes a substantial violation of a State, local or federal statute or regulation on the Project, DPMC may declare the Contractor to be in default, and/or terminate the Contract.
- 4.3.12 12 Prior to the start of any crane equipment operations, the Contractor shall make all necessary applications and obtain all required permits from the Federal Aviation Administration (F.A.A.). When the F.A.A. has jurisdiction, the sequence of operations, timing and methods of conducting the Work shall be approved by the F.A.A.
- 4.3.13 The Contractor will establish an approved Silica Health and Safety Program when tasks generating crystalline silica dust are being performed. This program shall include engineering, work practice, and respiratory protection controls to reduce worker exposure to airborne respirable crystalline dust to levels that are as low as reasonably achievable. When tasks are performed that generate airborne crystalline dust, the Contractor will minimize worker exposure to dust by one, or a combination of the following methods: 1) dust suppression with water, 2) local exhaust ventilation to a high-efficiency dust collector, and/or 3) appropriate respiratory protection devices. The Contractor shall provide a trained, competent person, as defined by OSHA 29 CFR 1926, on site at all times to implement the Silica Health and Safety Program when tasks generating crystalline silca dust are being performed.

4.4 RESPONSIBILITY FOR THE WORK

- 4.4.1 .1 The Contractor shall be responsible to the State and to any separate Contractors and/or consultants including, without limitation, the Architect/Engineer, for the acts, errors and omissions of its employees, Subcontractors and their agents and employees that injure, damage or delay such other Contractors and/or consultants in the performance of their work.
- 4.4.2 .2 The Contractor shall be responsible for all damage or destruction caused directly or indirectly by its operations to all parts of the Work, both temporary and permanent, and to all adjoining property.
- 4.4.3 The Contractor shall, at its own expense, protect all finished work and keep the same protected until the Project (or identifiable portions thereof, that are declared as substantially complete and being used) is completed and accepted.
- 4.4.4 .4 The Contractor shall be responsible for safety and for any damage or injury which may result from the Contractor's failure or improper construction, maintenance or operation.

4.4.5 In order to protect the lives and health of its employees, the Contractor shall comply with all applicable statutes and regulations and pertinent provisions of the "Manual of Accident Prevention in Construction" issued by the Associated General Contractors of America, Inc. and shall maintain accurate records of all cases of death, occupational disease, and injury requiring medical attention or causing loss of time from work arising out of and in the course of employment on work under the Contract. If a conflict should exist with the requirements of the Federal Occupational Safety and Health Act of 1970, then the most stringent statute or pertinent provision shall apply.

4.5 INDEMNIFICATION

- 4.5.1 .1 The Contractor shall assume all risk of and responsibility for, and agrees to protect, defend and indemnify the State of New Jersey, its agents, and its employees, from and against, any and all claims, demands, suits, actions, recoveries, judgment and costs of expenses in connection therewith on account of the loss of life, property, injury or damage to the person, body or property of any person or persons whatsoever, resulting from the Contractor's performance on the Project or through the use of any improper or defective machinery, implements or appliances, or through any act or omission on the part of the Contractor or its agents, employees or servants, which shall arise from or result directly or indirectly from the Work and/or materials supplied under this Contract. This indemnification obligation is not limited by, but is in addition to, the insurance obligations contained in this Contract.
- 4.5.2 In any and all claims against the State or any of its agents or employees, any employees of the Contractor or Subcontractor or anyone directly or indirectly employed by any of them, or anyone for whose acts any of them may be liable, the indemnification obligation under this section shall not be limited in any way as to the amount or type of damages, compensation or benefits payable by or for the Contractor or any Subcontractor under worker's compensation acts, disability benefit acts, or other employee benefit acts.

4.6 SUPERVISION

- 4.6.1 .1 The Contractor shall attentively supervise and direct the Work. The Contractor shall be solely responsible for all construction means, methods, techniques, sequences and procedures and for coordinating all portions of the Work under the Contract.
- 4.6.2 .2 The Contractor shall employ a full-time competent superintendent and necessary foremen and assistants, who shall be in attendance on the Project Site during the progress of the Work. The superintendent shall represent the Contractor, and all communications given to the superintendent shall be binding upon the Contractor. The State reserves the right to require a change in superintendent if the superintendent's performance, as judged by the DPMC, is deemed to be inadequate. Upon application in writing, and if deemed appropriate and expressly approved by the DPMC, the requirement for a full-time superintendent may be waived. If such a waiver is permitted, the Contractor shall employ a full-time competent foreman who shall be in attendance on the site during the progress of work and shall represent the Contractor, and all communications given to the foreman

shall be binding upon the Contractor. The Contractor shall not employ persons unfit or unskilled in the assigned area of work.

- 4.6.3 .3 The Contractor shall ensure that its Subcontractors shall likewise have competent superintendents in charge of their respective portions of the Work at all times. Upon application in writing, and if deemed appropriate and expressly approved by the DPMC, the requirement for a full-time superintendent may be waived. If such a waiver is permitted, the Subcontractor shall employ a full-time competent foreman who shall be in attendance on the site during the progress of work and shall represent the subcontractor, and all communications given to the foreman shall be binding upon the subontractor. The Subcontractor shall not employ persons unfit or unskilled in the assigned area of work. If it becomes apparent that a Subcontractor does not have its portion of the Work under control of a competent foreman, the Contractor shall have the obligation to take appropriate steps to immediately provide proper supervision.
- 4.6.4 .4 The Contractor shall employ qualified competent craftsmen in their respective lines of work. The State may require evidence that all employees have received sufficient training to execute the Work.
- 4.6.5 If, due to a trade agreement or project labor agreement, standby personnel are required to supervise equipment installation or for any other purpose during the normal working hours of other trades, the Contractor normally required to provide the standby services shall be deemed to have evaluated and included the costs thereof in its bid price and shall provide said services without additional charge.
- 4.6.6 .6 The Contractor shall at all times enforce strict discipline and good order among its employees and shall not employ any unfit person or anyone not skilled in the task assigned.

4.7 SHOP DRAWINGS AND OTHER SUBMITTALS

- 4.7.1 .1 The Contractor shall, within two weeks of the Notice to Proceed, submit to the Architect/Engineer, shop drawings and sample submission schedule for approval, which shall be used as a basis for complying with the overall progress schedule. The Contractor shall obtain, from its Subcontractor(s), all submittals including shop drawings, details, and schedules. The Contractor shall review the submittals for completeness and conformity with the Contract Documents, and shall stamp the submittals "approved". The Contractor shall promptly forward two copies of each submittals in reproducible form to the Architect/Engineer, so as to cause no delay in its own work or that of any other contractor The DPMC Project number and the drawing and specification references shall be written or typed on all submissions. Failure to comply with these instructions will be sufficient reason to return the drawing to the Contractor without approval and any resulting delay in the Project shall be the sole responsibility of the Contractor.
- 4.7.2. The Architect/Engineer will review shop drawings and other submittals with reasonable promptness. The Contractor shall promptly make any corrections, if required by the Architect/Engineer, and resubmit a reproducible copy for approval. Within five (1) working days of final approval, the Contractor shall send the Architect/Engineer a

minimum of seven (7) prints of the finally approved shop drawings as well as seven (7) copies of all catalog cuts.

- 4.7.3 .3 The Contractor shall prepare original shop drawings, and not simply copy the Contract Drawings for submission as shop drawings. All shop drawing sizes shall be in multiples of 9" x 12" (e.g., 18" x 24", 24" x 27", 24" x 36", etc.) as approved by the Architect/Engineer.
- 4.7.4 Any deviations or changes from the requirements of the Contract Documents, must be approved by the Architect/Engineer. A Contractor seeking approval for any deviations or changes must: a) make a written request for the proposed change; b) provide to the Architect/Engineer a detailed narrative description of the proposed change; c) highlight on the applicable drawing the proposed change; and d) furnish a detailed description of all potential impacts on the schedule and project budget.

4.7.5 .5 Substitutions

- 4.7.5.1 Where any particular brand or manufactured article is specified, it shall be regarded as a standard. Similar products of other manufacturers, capable of equal performance and quality, may be accepted if approved by the Architect/Engineer and accepted by DPMC in writing.
- 4.7.5.2 In the event that a Contractor proposes a substitution to the specified equipment or materials, it shall be the Contractor's responsibility to submit proof of equality and to provide and pay for any tests which may be required by the DPMC in order to evaluate the proposal. If there is a substantial cost savings between the substitution and the specified equipment or material, the difference will be returned to the State in the form of a credit Change Order.
- 4.7.5.3.3 The application for the approval of a substitution must be submitted on the State form within 10 days of Notice to Proceed. Further, the submission shall include the following requirements:
 - a. A Full and complete identification information;
 - b. The identification of the paragraph and section of the specifications for which the substitution is proposed. The attachment of data indicating in detail whether and how the equipment or material differs, if at all, from the article specified;
 - d. A detailed explanation of any effect the proposed substitution will have on the scope of the Work and a certification that the Contractor agrees to be responsible for any and all resulting added costs to its Work and to any additional costs incurred by the Architect/Engineer in time, labor and/or redesign of the Contract Documents;
 - e. The submission of documents that demonstrate proof of equality, along with an agreement to have such tests performed at the Contractor's own expense as may be required for approval by the DPMC and/or the Architect/Engineer. The Contractor shall be responsible for the cost of reviews by the Architect/Engineer of subsequent submissions of additional information.

- 4.7.5.4 No Contractor shall base a bid on a substitution that may have been approved on previous Projects. Bids shall be based solely on plans and specifications of this Project.
- 4.7.5.5 The Contractor shall not proceed with the purchase or installation of a substitution without the written approval of DPMC. Any such installation may result in the assessment of costs for its removal at the Contractor's expense, and/or other damages and/or termination of the Contract for default.

4.7.6 Additional Submissions

- 4.7.6.1.1 Samples: The Contractor shall furnish, for approval, all required samples. Such samples shall be submitted in accordance with the shop drawing and sample submittal schedule. All work must be installed in accordance with approved samples.
- 4.7.6.2.2 Utility Service Connections: With respect to plumbing, fire-protection, HVAC, electrical and other machinery and mechanical equipment items requiring utility service connections, the Contractor must submit the respective shop drawings with the manufacturer's certified rough-in drawings, indicating accurate locations and sizes of all service utility connections.
- 4.7.6.3.3 Sleeve and Opening Drawings: Prior to installing service utilities or other piping, through structural elements of the building, the Contractor shall prepare and submit, for approval by the Architect/Engineer, accurate dimensional drawings indicating the positions and sizes of all sleeves and openings required to accommodate the Work and installation of the Contractor's piping, equipment, etc. All such drawings must contain reference to the established dimensional grid of the building. Such drawings must be submitted in accordance with the approved shop drawing and sample submission schedule.
- 4.7.6.4 .4 Control Valve and Circuit Location Charts and Diagrams: For all plumbing, fire- protection, HVAC and electrical work, the Contractor shall prepare a complete set of inked or typewritten control valve and circuit location diagrams, charts and lists identifying and locating all such items, and shall place the charts, diagrams and lists under frame glass in designated equipment rooms. The Contractor shall also furnish one- line diagrams, as well as such color-coding of piping, wiring and other necessary identifications as specified or required. This information is to be framed under glass and displayed where directed.
- 4.7.6.5.5 Coordination Drawings: The Contractor shall create and update a complete, composite set of Coordination Drawings. The purpose of these drawings is to identify coordination and interference problems prior to installation. Coordination Drawings are required for all equipment rooms, above ceiling spaces, shared chases, and other areas where the Work of two or more trades is to be installed. The drawings shall be drawn to a scale not smaller than 1/4"=1'-0" (30"x42" sheet size) and shall show clearly in both plan and elevation that all Work can be installed without interference. At a minimum these drawings shall indicate:
 - a. The interrelationship of equipment and systems;
 - b. Required installation sequences;

c. Equipment foundations and pads, equipment, piping, conduits, racks, ductwork, insulation, panels, control centers, sprinkler and fire protection systems etc. and required clearances.

The Contractor shall prepare the coordination drawings based on the submitted shop drawings and Contract Documents. The Contractor shall prepare, submit and receive approvals for the Coordination Drawings before any sleeves or inserts are set, any floor openings are core drilled, or any equipment, equipment foundations, or related work is installed. The cost of preparing approved Coordination Drawings shall be included in the Contractor's price. DPMC may require the Contractor to identify Coordination Drawings as an item within the Schedule of Values, and incorporate them into in the Project schedule.

4.8 AS-BUILT DRAWINGS

- 4.8.1 .1 The Contractor and each Subcontractor shall maintain on the Project Site at all times one set of drawings to be marked "AS-BUILT." The DPMC has the right to rely on accuracy of the "as-built" drawings provided by the Contractor. During the course of the Project, the Contractor shall mark these drawings with colored pencils to reflect any changes, as well as the dimension and the location of all pipe runs, conduits, traps, sprinkler and fire protection lines, footing depths or any other information not already shown on the drawings or differing therefrom. All buried utilities outside the building shall be located by a survey performed by a licensed surveyor who shall certify as to its accuracy. These marked-up drawings and surveys shall remain current and shall be made available to the DPMC or Architect/Engineer at all times during the progress of the Work.
- 4.8.2 In instances where shop drawings and/or erection drawings, of a scale larger than the Contract Drawings, are prepared by the Contractor, such drawings may be acceptable "as-built" drawings provided they are updated. A master sheet of the same dimensions as the Contract Drawings shall be prepared by the Contractor that shall indicate, sheet by sheet, a cross-reference to all shop drawings pertaining to that drawing.
- 4.8.3 .3 The Contractor shall submit the "as-built" documents to the Architect/Engineer with a certification as to the accuracy of the information thereon at the time of Contract completion and before final payment will be made to the Contractor. After acceptance by the Architect/Engineer, the Contractor will furnish two sets of all shop drawings used for "as-built" documentation.
- 4.8.4 .4 All "as-built" drawings as submitted by Contractors shall be dated and labeled "AS-BUILT" above the title block. This information shall be checked, edited and certified by the Architect/Engineer, who will then transpose such information from the Contractor's "as-built" drawings to the original drawings. Where shop drawings have been used by the Contractor for "as-built" documentation, the master sheet providing cross reference information, as described in section 4.8.2, shall be included in the set of "as-built" drawings furnished to DPMC.

4.9 EXCAVATIONS, CUTTING AND PATCHING

- 4.9.1 .1 Soil borings, test pits or other subsurface information may be secured by an independent Contractor retained by the State prior to design and construction of the Project and, if obtained, may be included in the Contract Documents for the Contractor's use. The Contractor assumes full responsibility for interpretation of said information.
- 4.9.2 .2 The Contractor shall be responsible for furnishing and setting of sleeves, built-in items, anchors, inserts, and other necessary materials for its work and for all cutting, fitting, closing in, patching, finishing, or adjusting of its work in new and/or existing construction, as required for the completed installation.
- 4.9.3 .3 Approval in writing from the DPMC and the Architect/Engineer must first be obtained by the Contractor before cutting or boring through any roof, floor beams, floor construction or structural members.

4.10 TESTING

- 4.10.1 Contractor shall notify the DPMC in writing of all work required to be inspected or tested. The notice shall be provided no later than five working days prior to the scheduled inspection or test. The Contractor shall bear all costs of such inspections or tests, except for Code inspections as stated in section 4.3 of this document.
- 4.10.2 When mechanical, electrical or other equipment is installed, it shall be the responsibility of the installing Contractor to maintain, warrant and operate it for such period of time as required by the Contract Documents or as necessary for the proper inspection and testing of the equipment and for adequately instructing the State's operating personnel. All costs associated with the maintenance, warranty, operations, inspection and testing of equipment, as well as instructing State personnel, shall be borne by the Contractor installing the equipment. All tests shall be conducted in the presence of, and upon timely notice to, the DPMC, prior to acceptance of the equipment.
- 4.10.3 shall have the authority to direct in writing that special or additional inspections or tests be performed. The Contractor shall comply and give notice as detailed above.
- 4.10.4 In the event such special or additional inspections or testing reveal a failure of the Work to comply with the terms and conditions of the Contract, the Contractor shall bear all costs thereof, including all costs incurred by the State made necessary by such failures.
- 4.10.5 Contractor shall utilize inspection or testing from those firms/entities prequalified by DPMC. Failure to use a firm/entity pre-qualified by DPMC shall be grounds for rejection of the inspection or test as non-conforming.
- 4.10.6 submittals of inspections, test reports or requests for approval shall be accompanied by a certification signed by the Contractor, attesting to: the Contractor's knowledge of the submittal; acceptance of its findings; acknowledgment that material testing meets the required standards; and a certification of the report's representation of

the facts. Failure to provide the written certification shall be grounds for rejection of the submittal.

- 4.10.7 Contractor shall ensure that a copy of the inspection report is transmitted directly to the Architect/Engineer and the DPMC. The Contractor shall ensure that it includes in all of its subcontracts and purchase orders for inspection and testing, the requirement for the inspection or testing firm/entity to submit a copy of the report directly to the DPMC representative. The Contractor shall ensure that all such reports are submitted within fourteen (14) calendar days of the test or inspection.
- 4.10.8 In addition to tests performed by the Contractor, the State reserves the right to engage an independent testing agency or firm to perform testing inspections. The Contractor shall provide full access, provide samples, and cooperate fully with this testing agency.
- 4.10.9 esting requirements for real property installed equipment (RPIE) to be furnished by the Contractor, when such testing is required by Code, Contract, or the manufacturer, shall be performed by a testing laboratory pre-qualified by DPMC, or in the absence of such, by the manufacturer or its authorized representative. The Contractor shall provide five working days' notice to the DPMC representative, to allow sufficient opportunity to witness the test.
- 4.10.10 The DPMC may order that any part of the Work be re-examined by the DPMC, and if so ordered, the Contractor shall open or uncover such work for re-inspection by the DPMC. If such work is found to be in accordance with the Contract, the DPMC shall pay the cost of re-inspection; however, if such work is not found to be in accordance with the Contract, the Contractor shall be responsible for the cost of re-inspection and replacement of any defective or non-conforming work.

4.11 EQUIPMENT AND MATERIALS

- 4.11.1 Contractor warrants that all materials and equipment furnished under the Contract will be new, unless otherwise specified, and that all work will be of good quality, free from faults, defects, and installed in conformance with the Contract Documents. All work not conforming to these requirements, including substitutions not properly approved and authorized, may be considered defective and rejected by the DPMC or the Architect/Engineer. If required by the Architect/Engineer or the DPMC, the Contractor shall furnish satisfactory evidence as to the kind and quality of materials and equipment. This warranty shall be in addition to but not in lieu of any other warranty or guarantee provided for in the Contract.
- 4.11.2 Contractor shall submit to the Architect/Engineer an original and six copies of the request for approval of materials on the form provided by DPMC for approval. Each item of material listed shall be marked "As Specified", "Substitution" or "Unspecified" as appropriate.
- 4.11.3 Contractor shall furnish and deliver the necessary equipment and materials in ample quantities and as frequently as required to avoid delay in the progress of the Work and shall store them so as not to cause interference with the orderly progress of the Project.

- 4.11.4 Contractor shall furnish and pay for all necessary transportation, storage, scaffolding, centering, forms, water, labor, tools, light and power and mechanical appliances and all other means, materials and supplies for properly executing the Work under this Contract, unless expressly specified otherwise in the Contract Documents. The Contractor shall have its representatives at the Site to accept delivered materials. State agencies employees and/or representatives will not accept materials, nor will State agency employees and/or representatives be responsible for damage, theft, or disappearance of the Contractor's materials, equipment, tools, or other property.
- 4.11.5 Products manufactured in the United States shall be used in this work, whenever available. Wherever practicable, preference shall be given at all times to material and equipment manufactured or produced in the State of New Jersey, where such preference is reasonable and will best serve the interest of the State.
- 4.11.6 materials, equipment, or supplies for the Work shall be purchased by the Contractor subject to any lien or encumbrance or other agreement by which an interest is retained by the seller. This clause shall be a condition included in all agreements between the Contractor and its Subcontractors. The Contractor warrants, by signing its invoice, that it has good and sufficient title to all such material, equipment and supplies used by it in the Work, free from all liens, claims or encumbrances.

4.12 TEMPORARY FACILITIES

The Contractor shall be responsible for providing for its own storage areas, employee vehicular parking and staging areas, excavation borrow/spoils designated areas, commercial canteen areas, and all other areas necessary for use by the Contractor. The Contractor shall locate these areas to suit Project requirements, subject to DPMC approval.

- 4.12.1 Field Offices The Contractor will provide and maintain during the contract duration an on-Site suitable weather-tight insulated field office conveniently located, and shall maintain therein a complete set of Contract Documents including plans, specifications, CPM network diagrams, Change Orders, logs and other details and Project correspondence. Subject to the DPMC's written approval and at a date designated by DPMC, the field office may be removed upon enclosure of the building and space may be allocated for field offices within the building. The contents and operations will be transferred to the interior of the Project building by the Contractor, and said office(s) shall be maintained by the Contractor until final acceptance or until the DPMC approves its removal. The Contractor will be responsible to obtain and pay for all permits required for the Contractor's field offices.
- 4.12.2 elephones The Contractor shall provide its own telephones. The State will be responsible only for the cost of calls made by State employees. if there is a documented cost for same.
- 4.12.3 age The Contractor will provide and maintain, for its own use suitable and safe temporary storage, tool shops, and employees' sheds for proper protection, storage work and shelter. The Contractor shall maintain these structures properly and remove the structures at the completion of work. The Contractor shall be responsible to maintain

these facilities and the areas around the facilities in a clear and clean manner. The Contractor shall be responsible for correcting defects and damage caused by such use. Rooms in buildings at the Project Site may be used as shops and storerooms, conditioned upon written approval from DPMC.

4.12.4 Facilities

- a. The Contractor shall provide and pay for suitable temporary toilets at an approved location on the Site and prior to the start of any field work. The toilet facilities shall comply with federal, State and local laws and regulations. The Contractor will be responsible for maintenance, removal and relocation as described hereinafter.
- b. The Contractor shall provide a temporary toilet and/or indoor toilet connected to water and sewer to accommodate the meeting room and the Architect/Engineer's office, as well as the DPMC office.
- c. Toilets shall be serviced by a qualified and experienced firm authorized to maintain services.
- d. Each portable toilet facility shall be maintained in a neat and clean condition and serviced at least twice a week, including the removal of waste matter, sterilizing, recharging tank, refilling tissue holders, and thoroughly cleaning and scrubbing entire interior.
- e. Toilet facilities in a multiple-story building shall be located on no less than every other floor, unless otherwise directed in writing.
- f. Toilet service shall be relocated inside the building and connected to water and sewer as the progress of the Work will allow.
- g. When temporary toilets are connected to water and sewer lines, precautions shall be taken to prevent freezing.
- h. The Contractor shall remove the temporary toilet units from the Work Site at the completion of the Work, or when so directed by the DPMC or the Architect/Engineer.
- i. Workers are not to use the finished bathroom and toilet facilities in the Project buildings. Reasonable steps must be taken by the Contractor to enforce this rule.

4.12.5 ccess, Roads and Walks

- a. The Contractor shall be responsible for providing and maintaining unobstructed traffic lanes on the designated construction access routes shown on the Contract Drawings or as reasonably required so as to perform the Work. The Contractor shall provide and maintain all reasonably required safety devices. The Contractor shall provide any necessary additional materials, grading and compaction, and shall remove snow and debris as necessary to provide and maintain the access roadbed and pedestrian ways in serviceable condition.
- b. The Contractor shall be responsible for constructing and maintaining all roadways, drives and parking areas within or proximate to the Site free and clear

of debris, gravel, mud, snow, ice, or any other Site materials, by ensuring that all reasonably necessary measures are taken to prevent such materials from being deposited on such surfaces. This includes, as may be appropriate, the cleaning of vehicle wheels and/or other necessary maintenance, prior to exit from the Construction Site. Should such surface require cleaning, the Contractor will clean these surfaces without additional cost to the State. The Contractor will be held accountable for any citations, fines, or penalties imposed on the State for failing to comply with local rules and regulations related to Site and off-Site maintenance.

- c. The Contractor shall not commence final construction of permanent driveways, parking areas or walks without the written approval of the DPMC. The Contractor shall provide additional materials and labor for maintaining and reworking the sub-grade prior to completion of the Work, to ensure improvements conform fully to the specifications.
- d. The Contractor shall obtain written permission from the State for the use of any existing driveways or parking areas not specifically designated for such use in the Contract Documents. If permission is granted, the Contractor shall maintain such driveways and areas in good condition during the construction period, and at the completion of the Project, shall leave them in the same or better condition as at the start of the Work. Conditions before use shall be carefully photographed and documented by the Contractor.

4.12.6 Light and Power

- a. The Contractor shall extend electrical service to the building or buildings at locations approved by the DPMC. Temporary electrical service shall be independent of the existing permanent service. Initial temporary service shall be three phase or single phase as indicated in the Contract Documents. The Contractor is responsible to investigate and verify the appropriateness and availability of electrical service with the local utility company prior to the bid date. The Contractor's bid shall be deemed to include all costs associated with providing this power. Temporary light and power installations, wiring, and miscellaneous electrical hardware must meet the electrical Code and will be inspected by NJUCC officials. The Contractor shall provide the necessary distributing facilities and a meter, and shall pay the cost of running temporary services from the nearest utility company power pole. All costs shall be included in the Contractor's bid.
- b. In the event that a water well is the source of water supply for the Project, the extension of electrical service shall include the necessary wiring of sufficient capacity to the location of the well for the operation of the well pump. Where service of a type other than herein mentioned is required, the Contractor requiring it shall install and pay all costs of such special service. The size and incoming service and main distribution switch and panel shall be sized as any service by NEC requirements.
- c. The Contractor shall provide all electrical service for the operation of elevator equipment during construction.

- d. The Contractor shall pay for the cost of all electric energy used on distribution lines installed.
- e. The Contractor shall provide and pay for all maintenance, servicing, operation and supervision of the service and distribution facilities.
- f. If the Contractor fails to carry out its responsibility in the supplying uninterrupted light and power as set forth herein, the Contractor shall be held responsible for such failure, and the DPMC shall have the right to take such action as is deemed proper for the protection and conduct of the Work. Any costs associated with DPMC obtaining or supplying light and power shall be deducted from any payment due to the Contractor.
- g. The Contractor shall comply with the requirements of the Federal Occupational Safety and Health Act of 1970 with regard to temporary light and power.

4.12.7 emporary Enclosures

Whenever necessary in order to maintain proper temperatures for the execution or protection of the Work, the Contractor shall furnish and maintain temporary enclosures for all openings in exterior walls that are not enclosed with finished materials. Temporary wood doors shall be provided at door openings.

4.12.8 emporary Heating, Ventilation and Air Conditioning

a. Prior to Enclosure - Prior to the building being enclosed by walls and roof, if the outside temperatures falls below 45 degrees Fahrenheit ("F") at any time during the day or night, and heat is required for work in progress or for its protection or curing, the Contractor shall furnish, at its expense, acceptable means to provide sufficient temporary heat to maintain a temperature required by the Work being performed but in no case less than 45 degrees F.

b. Generally Enclosed

- (1) For the purposes of establishing the beginning of the Contractor's obligation to provide temporary heat, a building or major unit thereof shall be considered generally enclosed when (a) the exterior walls have been erected, (b) a temporary roof or permanent roof is installed and in a watertight condition, and (c) temporary or permanent doors are hung and window openings are closed with either permanent or temporary weathertight enclosures. A major unit of buildings as referred to herein shall be: (a) an entire separate structure, or (b) a fully enclosed wing which shall have a floor area equal to at least 50% (fifty percent) of the total floor area of the Project.
- (2) As soon as the DPMC determines that the building, or a major unit thereof, is "generally enclosed" by walls and roof, and when the outside temperature falls below 55 degrees F. at any time during the day or night, the Contractor shall furnish sufficient heat by the use and maintenance of LP gas heaters or other acceptable means to maintain a temperature of not less than 55 degrees F. within the enclosed area of the building at all

times, and shall remove such heaters when no longer required. The Contractor will be held responsible for providing temporary heat and for all damages resulting from freeze-ups, for the duration of the Project from the time the building is generally enclosed to final acceptance and occupancy. The Contractor shall remove soot, smudges, and other deposits from walls, ceilings, and all exposed surfaces which are the result of the use of heating equipment, including the permanent heating system, during the period of its use for supplying heat. The Contractor shall not do any finish work until the areas are properly cleaned. The Contractor shall provide or arrange, at its own expense, supervision of the heating equipment at all times prior to providing heat, using the permanent heating This obligation shall commence immediately after the acknowledged permanent enclosure of the building or buildings, as confirmed by the DPMC. The Contractor shall furnish and pay for all fuel for heat required during the period when the building is generally or permanently enclosed.

- (3) The Contractor shall not assume that the permanent heating system or any part thereof will be available for furnishing of temporary heat during the period for which temporary heat is required. The Contractor's base bid price shall therefore include the cost of all equipment necessary for providing temporary heat as required by the Contract Documents. The Contractor may use the permanent heating system, with written approval from DPMC. Such use however does not cause to commence the equipment's warranties and guarantees. The equipment's warranties and guarantees shall not commence to run until the State takes beneficial use of the Project and facility for the purposes intended.
- (4) All heating equipment shall be NFPA-approved and connected to approved flues to the atmosphere. Heaters shall be approved by a recognized testing laboratory and must be equipped with a positive shutoff safety valve.
- (5) Storage of gas cylinders within the building will not be permitted at any time.
- (6) The Contractor shall provide fire extinguishers on each floor where heaters are used, and the areas must be adequately ventilated.

c. Permanent Enclosure

- (1) When the building enclosure has been confirmed by the Architect/Engineer has been completed in accordance with the Contract Documents, and to the satisfaction of DPMC, it shall be considered permanently enclosed. The Architect/Engineer will also confirm in the job meeting minutes that the building, or a major unit thereof, is permanently enclosed.
- (3) The Contractor shall install adequate controls to make such temporary connection as required for the operation of the HVAC system.

Should the heating system be designed for the tie-in to existing steam lines for resource of heat, the State will provide steam for temporary heat through the Project permanent heating system, at no cost to the Contractor, after the tie-in is completed by the Contractor.

(4) When the building enclosure has been confirmed by the A/E as completed, the Contractor may request permission to operate the permanent HVAC system to meet its temporary HVAC obligation. The Contractor shall maintain a minimum temperature of 55 degrees F., or a higher temperature, not to exceed 75 degrees F., as may be directed by the Contract Documents for the proper conduct and protection of the Work. The Contractor shall do so until such time as its work is completed and accepted and the Contractor is relieved of this requirement in writing by the DPMC. The Contractor shall pay for and be responsible for the maintenance in accordance with the manufacturer's recommendations, operation and supervision of the HVAC system, including the cost of all water, electricity, and fuel, until the State assumes beneficial occupancy/use of the Project.

4.12.10 Temporary Water

- a. The Contractor shall provide, protect and maintain an adequate valved water supply. If the source of water supply is a well, provisions covering the supply water will include the installation of necessary power-driven pumping facilities. The well shall be protected against contamination. The water supply shall be tested periodically by the Contractor, and if necessary, shall be chlorinated and filtered. All costs of providing water will be paid for by the Contractor.
- b. The Contractor is responsible to protect all temporary and permanent water lines from damage or freezing. Should water connections be made to an existing line, the Contractor shall provide a positive shut-off valve at its own cost and expense.

4.12.11 Standby Personnel

If, pursuant to trade agreement to which the Contractor is a party, the Contractor is obligated, to employ standby personnel then the Contractor shall determine and include all such costs thereof in its bid proposal. The Contractor shall not, at any time, make a claim to the State for costs relating to standby maintenance or standby supervision for electric motor-driven or other equipment.

4.12.12 Dust Control

- a. The Contractor shall provide and maintain necessary temporary dust-proof partitions around areas of Work in any existing building or in new building areas as directed by the Architect/Engineer or the DPMC.
- b. The Contractor shall provide and maintain Site dust control of Projects with on-Site construction as directed by the Architect/Engineer or the DPMC.

4.13 STORAGE AND SITE MAINTENANCE

- 4.13.1 Contractor shall confine its apparatus, the storage of its equipment, tools and materials, and its operations and workers to areas permitted by law, ordinances, permits, and Contract as set forth in the Contract Documents, the rules and regulations of the State, or as ordered by the DPMC. The Contractor shall not unreasonably encumber the Site or the premises with materials, tools and equipment.
- 4.13.2 Contractor shall, at all times during the progress of the Work keep the premises and the job Site free from the accumulation of all refuse, rubbish, scrap materials and debris caused by its operations and/or the actions of its employees, Subcontractors and/or workers, to ensure that, at all times, the premises and Site shall present a neat, orderly and workmanlike appearance. This is to be accomplished as frequently as is necessary by the removal of such refuse, rubbish, scrap materials and debris from the Site and the State's premises. Loading, cartage, hauling and dumping of same will be at the Contractor's expense.
- 4.13.3 the completion of the Work, the Contractor shall remove all of its tools, construction equipment, machinery, temporary staging, false work, mock-ups, form work, shoring, bracing, protective enclosures, scaffolding, stairs, chutes, ramps, runways, hoisting equipment, elevators, derricks, cranes, and any other materials and equipment brought onto the Project Site.
- 4.13.4 the Contractor not promptly and properly discharge its obligation relating to Site maintenance and/or final clean up, the State shall have the right to employ others and to charge the resulting cost to the Contractor after first having given the Contractor a three-working day written notice of such intent.
- 4.13.5 Contractor's responsibilities for final clean up shall include:
 - a. Removal of all debris and rubbish resulting from or relating to the Contractor's work. Rubbish shall not be thrown from building openings above the ground floor unless contained within chutes.
 - b. Removal of stains from glass and mirrors. Glass shall be washed and polished inside and outside.
 - c. Removal of marks, stains, fingerprints, soil, dust or dirt from painted, decorated or stained woodwork, plaster or plasterboard, metal acoustic tile and equipment surfaces.
 - d. Removal of spots, paint and soil from resilient, glazed and unglazed masonry and ceramic flooring and wall work.
 - e. Removal of temporary floor protections; and cleaning, washing or otherwise treating and/or polishing, as directed, all finished floors.
 - f. Cleaning of exterior and interior metal surfaces, including doors, window frames and hardware, of oil stains, dust, dirt, paint, etc. Polishing and removal of fingerprints or blemishes from such surfaces shall be completed, as applicable.

- g. Restoration of all landscaping, roadways and walkways to preexisting condition. Damage to trees and plantings shall be repaired in the next planting season, and such shall be guaranteed for one year from the date of repair and/or replanting.
- 4.13.6 All construction equipment, materials and/or supplies of any kind, character or description, regardless of value, which remain on the job Site for more than 30 (thirty) calendar days from the date of the Certificate of Final Acceptance, shall become the property of the State. Such construction equipment, materials and/or supplies will be disposed of in any manner the State shall deem reasonable and proper. The cost of this disposal will be deducted from any sums due the Contractor. If the payments then or thereafter due the Contractor are not sufficient to cover such amount, the Contractor shall pay the difference to the State.

4.14 CUT-OVERS AND INTERRUPTIONS

All cut-overs of mechanical and electrical services to existing buildings shall be approved, scheduled and coordinated in advance with the DPMC's representative and performed at a time convenient to the occupants of said buildings so as not to unreasonably interfere with its operations.

4.15 PROTECTION/SAFETY

4.15.1 afety Precautions and Programs – The Contractor shall be responsible for initiating, maintaining and supervising all required safety precautions and programs in connection with the Work. The Contractor shall designate a responsible member of its organization at the Site whose duty shall be the prevention of accidents. This person shall be competent to review, implement and coordinate the safety programs being performed as required by Occupational Safety and Health Administration (OSHA) or any other agency having authority over safety on a State Construction Site.

4.15.2 ection of Persons

- a. The Contractor shall take all reasonable precautions for the safety of, and shall provide all reasonable protection to prevent damage, injury or loss to:
 - (1) Every employee on the Site and all other persons who may be affected thereby;
 - (2) All the Work and all materials and equipment to be incorporated therein, whether in storage on or off the Site, under the care, custody or control of the Contractor, or any of its Subcontractor(s) or lower tier sub-Subcontractor(s); and
 - (3) Other property at the Site or adjacent thereto (whether owned by the State or not), including but not limited to trees, shrubs, lawns, walks, pavements, roadways, structures and utilities not designated for removal, relocation or replacement in the course of construction.

- b. The Contractor shall give all notices and comply with all applicable laws, ordinances, rules, regulations and lawful orders of any public authority bearing on the safety of persons or property or their protection from damage, injury or loss.
- c The Contractor shall erect and maintain, as required by existing conditions and progress of the Work, all reasonable safeguards for safety and protection, including but not limited to rails, night-lights, aircraft warning lights, the posting of danger signs and other warnings against hazards, promulgating safety regulations, notifying Owners and users of adjacent utilities and other means of protection against accidental injury or damage to persons and property.
- d. The Contractor shall not load or permit any part of the Work to be loaded so as to endanger the safety of the project, its employees, or any other person on the project Site.
- e. The Contractor shall promptly remedy all damage or loss to any property caused in whole or in part by the Contractor, any of its Subcontractors, lower tier Subcontractors, or anyone directly or indirectly employed by any of them, or by anyone for whose acts any of them may be liable and for which the Contractor is responsible. These obligations are in addition to those stated elsewhere herein.

4.15.3 ection of Property

The Contractor shall have full responsibility to install, protect, and maintain all materials and supplies in proper condition whether in storage or off the site and to immediately repair and/or replace any such damage until Final Acceptance. The Contractor shall maintain an inventory of all materials and supplies for the Work at the Site, that are delivered to the site, or delivered to approved off-site storage facilities. The State shall not be liable for any damage, theft or negligent injury to the Contractor's property.

4.15.4 azardous Materials

- a. When the use or storage of explosives or other hazardous materials or equipment is necessary for the execution of the Work, the Contractor shall exercise the utmost care and shall carry on such activities under the supervision of properly qualified personnel.
- b. The Contractor shall maintain all records, reports and files of the general storage and handling of hazardous materials as required by any and all federal, State and/or local regulatory agencies.

4.16.5 Emergencies

In any emergency affecting the safety of persons or property, the Contractor shall act with diligence to prevent threatening injury, damage or loss. In such case, the Contractor shall immediately, but in no case, not more than 24-hours following the emergency, notify the DPMC and the Architect/Engineer of the action taken.

4.16 UNCOVERING AND CORRECTION OF WORK

4.16.1 covering of Work

- a. The Contractor is obligated to provide reasonable notice to the DPMC and/or the Architect/Engineer of all work scheduled to be covered, to permit DPMC and the Architect/Engineer the opportunity to inspect the Work prior to actual covering. If any portion of the Work is covered prior to inspection by the DPMC or the Architect/Engineer, it shall be uncovered for observation. Uncovering and replacement of the covering shall be at the Contractor's expense.
- b. The DPMC and/or the Architect/Engineer may request any work be uncovered by the Contractor for inspection. If such work is found to be in accordance with the Contract Documents, the cost of uncovering and replacement shall, by appropriate Change Order, be reimbursed to the Contractor. If such work is found not to be in accordance with the Contract Documents, the Contractor shall pay all associated costs.

4.16.2 rrection of Work

- a. The Contractor shall promptly correct all work rejected by the DPMC or the Architect/Engineer as defective or failing to conform to the Contract Documents, whether observed before or after final acceptance and whether or not fabricated, installed or completed. The Contractor shall bear all costs of correcting such rejected work, including the costs of all consultant services including but not limited to the Architect/Engineer's additional services.
- b. The Contractor shall remove from the site, at its own expense, all portions of the Work which are defective or non-conforming and which have not been corrected, unless removal is waived by the DPMC.
- c. If the Contractor fails to correct defective or non-conforming work in a reasonable time fixed by written notice from DPMC, then DPMC may make arrangements for such correction by others and charge the cost of so doing to the Contractor.
- d. If the Contractor does not proceed with the removal and correction of such defective or non-conforming work within a reasonable time, fixed by written notice from the DPMC or the Architect/Engineer, any materials or equipment shall become the property of the State and the DPMC may remove and dispose the non-conforming work in any manner to best meet the interest of the State. If such material is sold and the proceeds of the sale do not cover all costs which the Contractor should have borne and any additional cost incurred by the State in the uncovering, removal, disposal and correction of non-conforming work, the difference shall be charged to the Contractor and an appropriate credit Change Order shall be issued. If the payments then or thereafter due the Contractor are not sufficient to cover such amount, the Contractor shall pay the difference to the State.
- e. The Contractor shall be responsible for the cost of making good all work destroyed or damaged by such correction or removal.

f. Notwithstanding other obligations within the Contract Documents, nothing contained herein shall be construed to establish a time or date limitation upon which the DPMC must discover non-conforming work.

4.16.3 cceptance of Non-Conforming Work

The DPMC may determine that the best interests of the State will be served by accepting defective or non-conforming work instead of requiring its removal and correction. In such instance, the DPMC may, by any means available, exact an appropriate reduction in the Contract sum. Such adjustment shall be effected regardless of final payment having previously been made, and the Contractor and/or its surety shall be responsible for promptly remitting any funds due the State as a result thereof.

4.17 LAYOUT AND DIMENSIONAL CONTROL

4.17.1 Contractor shall be responsible for locating and laying out the building and all of its parts on the site, in strict accordance with the Contract Documents, and shall accurately establish and maintain dimensional control. The Contractor shall employ and pay for the services of a competent and licensed New Jersey engineer or land surveyor who shall be pre-qualified by DPMC to perform all layout work, and to test the level of excavations, footing base plates, columns, walls and floor and roof lines, and furnish to the Architect/Engineer, as the Work progresses, certifications that each of such levels is as required by the drawings. The plumb lines of walls, shall be tested and certified by the surveyor as the Work progresses.

4.17.2 Contractor's engineer/surveyor, in the course of layout work either on the site or within any building, shall establish all points, lines, elevations, grades and bench marks for proper control and execution of the Work. The Contractor's engineer/surveyor shall establish a single permanent benchmark as set forth in the Contract Documents to which all three coordinates of dimensional control shall be referenced. The Contractor's engineer/surveyor shall verify all Owner-furnished survey data including but not limited to topographical and utility location points, lines, elevations, grades and benchmarks, and buildings. Should any discrepancies be found between information given on the Contract Documents and the actual site or field conditions, the Contractor shall notify DPMC and the Architect/Engineer in writing of such discrepancy, and shall not proceed with any work affected until receipt of written instructions from the DPMC.

4.18 PROJECT SIGN

The Contractor shall erect and maintain one sign at the Project Site, as set forth in the Contract Documents and located as directed by the Architect/Engineer. Painting shall be done by a professional sign painter, with two coats of exterior paint, colors, letter face and layout as shown. No other sign will be permitted at the site. Upon completion of the Project, and when directed by the Architect/Engineer or the DPMC, the Contractor shall remove the sign.

4.19 SECURITY

- 4.19.1 Contractor shall provide all locks, doors and security construction and personnel as required to secure the Project building throughout the period of construction.
- 4.19.2 Contractor shall be responsible for the security of any temporary structures located on the premises outside of the building and/or any stored materials.

4.20 DPMC FIELD OFFICE

- 4.20.1 Contractor will provide on-site, suitable, separate, weather-tight, insulated (floor, walls, ceilings) field office facilities for the use of DPMC personnel, as more fully described in the Contract Documents. At a minimum, the Contractor is to supply this field office with toilet facilities, heating and air conditioning, tables and chairs, and phone and data communication lines. At a time determined by the DPMC or the Architect/Engineer, the Contractor shall remove field facilities upon enclosure of the Project building and shall relocate the contents and operations of the field office to the interior of the Project building until completion of the Project.
- 4.20.2 Contractor shall be responsible for the maintenance of both offices and the meeting room, including the cost of heating, air conditioning, electric current, and janitorial service.

4.21 PHOTOGRAPHS

- 4.21.1 The Contractor shall submit monthly progress photographs in duplicate to the DPMC, giving six (6) views of the Work with each application for payment until the Project is completed,.
- 4.21.2 photographs shall be 8" by 10" shall bear the date and time of the exposure, the DPMC Project number and title, the names of the Contractor and the name of the Architect/Engineer. All photographs shall also be submitted in digital format.

4.22 REPAIR OF FINISHED SURFACES, APPLIED FINISHES, GLASS

- 4.22.1 Contractor accepts sole responsibility for repair of uncontrolled dislodging, cracking, delaminating or peeling of finished surfaces such as concrete, pre-cast concrete, cast and natural stone, unit masonry, millwork, plaster, glass and applied finishes such as compound, paint, and special coatings, within the Contract Work and the limits of specified guarantee periods, regardless of the cause.
- 4.22.2 Contractor shall be responsible for replacement of all broken glass, regardless of the cause. The Contractor shall replace all broken, scratched or otherwise damaged glass before the completion and acceptance of the Work. If breakage is caused by the Owner, the Contractor will be reimbursed for the replacement costs. The Contractor shall wash all glass on both sides at completion, or when directed, removing all paint spots, stains, plaster, and other materials.

ARTICLE 5 - SUBCONTRACTORS

5.1 SUBCONTRACTORS AND MATERIAL SUPPLIER APPROVALS

- 5.1.1 Upon their execution, but not less than fourteen (14) calendar days prior to Subcontractor mobilization on the site, and/or Subcontractor billing, the Contractor shall forward to the Architect/Engineer on the form provided by the DPMC the names of all its Subcontractors and suppliers, of such others as the DPMC may direct, proposed to perform the principal parts of the Work. The Contractor shall forward the appropriate DPMC form to the Architect/Engineer for approval. Department of Labor Contractor Registration and New Jersey Business Registration Certificate are required for all Subcontractors.
- 5.1.2 If the DPMC has objection to any proposed or approved Subcontractor and/or material supplier, the Contractor shall substitute another Subcontractor and/or material supplier acceptable to DPMC. Under no circumstances shall the State be obligated for additional cost due to such substitution.
- 5.1.3 After the acceptance of bids, the Contractor shall make no substitution of any Subcontractor person or firm previously selected and approved, without prior written approval from the Architect/Engineer and DPMC. A Contractor seeking to substitute a Subcontractor person or firm shall provide written request for substitution no less than fourteen (14) calendar days prior to the execution of Work by the Subcontractor or material supplier.
- 5.1.4 Approval of a Subcontractor or material supplier by the DPMC and Architect/Engineer shall not relieve the Contractor of the responsibility of complying with all provisions of the Contract Documents. The approval of a Subcontractor or material supplier does not imply approval of any construction, material, equipment or supplies.

5.2 CONTRACTOR-SUBCONTRACTOR RELATIONSHIP

- 5.2.1 The Contractor acknowledges its full responsibility to the State for the acts and omissions of its Subcontractors and lower tier subcontractors, and of persons and firms either directly or indirectly employed by them, equally to the extent that the Contractor is responsible for the acts and omissions of persons and firms directly or indirectly employed by it. The Contractor acknowledges that it remains fully responsible for the proper performance of its Contract regardless of whether work is performed by the Contractor's own forces or by Subcontractors engaged by the Contractor.
- 5.2.2 Nothing contained in the Contract Documents shall create any contractual relationship between any Subcontractor and the State. Further, no Subcontractor or material supplier shall be deemed an intended third party beneficiary under this Contract.
- 5.2.3 The Contractor and all Subcontractors agree that, in the employment of both skilled and unskilled labor, preference shall be given to residents of the State of New Jersey, if such labor force is available.

5.2.4 The Contractor shall require, in its agreements with Subcontractors and as a condition of agreement, that each Subcontractor require in its agreement(s) with lower tier Subcontractors and Suppliers, that the Subcontractor understands that there is no contractual obligation of any kind between the State and Subcontractor and the Subcontractor's sole recourse lies with the Contractor and/or the surety, and not with the State, that each Subcontractor and lower tier Subcontractor, bound by the terms of the Contract Documents for this Contract, and assume toward the Contractor all the obligations and responsibilities which the Contractor assumes, pursuant to the Contract Documents.

ARTICLE 6 - CONSTRUCTION PROGRESS SCHEDULE

6.1 GENERAL

The State may contract for the services of a Critical Path Method (CPM) scheduling consultant for Project planning, scheduling and cost control. If such has been arranged, then section 6.2 shall apply to the Contract between the State and the Contractor. In the absence of a statement in the bid documents that a CPM consultant has been retained by the State, then section 6.3 shall apply.

6.2 CONSTRUCTION PROGRESS SCHEDULE (CRITICAL PATH METHOD -- CPM CONSULTANT RETAINED BY THE STATE)

6.2.1 Critical Path Method

- a. The Project will be monitored by a detailed critical path method scheduling system. This system shall be the basis for the evaluation of the Contractor's performance and for progress payments to the Contractor.
- b. The Contractor shall provide all the information necessary for the CPM consultant employed by DPMC to develop a CPM network plan demonstrating complete fulfillment of all construction Contract requirements and, as necessary, for the CPM consultant to maintain an accurate CPM schedule throughout the Project. The Contractor, in consultation with the CPM consultant, will establish construction logic and activity time duration consistent with Contract documents and Project requirements. The CPM consultant will establish the level of detail to be reflected on the CPM schedule. The Contractor shall utilize the schedule in planning, coordinating and performing the Work, including all activities of Subcontractors, equipment vendors and material suppliers.
- c. The Contractor agrees that the CPM consultant's Project network schedule is the designated plan for completion of all work in the allotted time, and the Contractor will assume full responsibility for the execution of the Work as shown. The Contractor shall indicate formal acceptance of the schedule by signing the final initial (baseline) network diagrams and computer schedule listing.
- d. The Contractor shall furnish sufficient labor and construction equipment to ensure the execution of the Work in accordance with the approved CPM progress schedule. If, in the opinion of the DPMC, a Contractor falls behind the CPM progress schedule, the Contractor shall take any and all such steps as may be necessary to bring its work into compliance with the CPM progress schedule. The DPMC may require the Contractor to increase the number of shifts, days of work and/or the amount of construction labor, plant and equipment, all without additional cost to the State.
- e. The Contractor shall make no claim for, and have no right to, additional payment or extension of time for completion of the Work, or any other concession because of any misinterpretation or misunderstanding on the Contractor's part of the CPM progress schedule, the Contractor's failure to attend the pre-bid

conference, or because of any failure on the Contractor's part to become fully acquainted with all conditions relating to the CPM progress schedule and the manner in which it will be used on the Project, or because of any Subcontractor's failure to properly participate in the development of a CPM progress schedule or to perform the Contract in accordance with the CPM progress schedule.

6.2.2 Initial Submittal

- a. To the extent necessary for the CPM consultant to reflect in the network diagrams the plan for completion of this Contract, the Contractor shall meet with and assist the CPM consultant and furnish, within ten (10) calendar days after award of this Contract, all necessary information for the preparation of the CPM progress schedule. This information shall include, but not necessarily be limited to, a logical sequencing of work operations, activity time estimates, intended crew flow, activity costs and estimated manpower requirements for each activity.
 - (1) The network diagram shall show the sequence and interdependence of activities required for the Project. In preparing the network diagram, the Contractor shall assist the CPM consultant by breaking up the Work into activities of a duration of no longer than ten (10) working days each, except as to non-construction activities (such as procurement of materials, delivery of equipment and concrete curing) and any other activities for which the CPM consultant may approve the showing of longer duration. The diagram shall show not only the activities for actual construction but also such activities as the Contractor's submittal of shop drawings, templates and equipment, material fabrication, delivery of equipment and material, substantial completion, final completion, punch list and closeout, and the delivery of Owner-furnished equipment, if applicable. The Contractor shall provide activity durations to the CPM consultant for each activity on the diagram.
 - (2) If requested by the CPM consultant, the Contractor shall furnish any information needed to justify the reasonableness of activity time duration. Such information shall include, but not be limited to, estimated activity manpower, unit quantities, and production rates.
 - (3) Failure by either the Contractor or the CPM consultant to include any element of work required for the performance of the Contract shall not excuse the Contractor from completing all work required within any applicable date, notwithstanding DPMC approval of the network diagrams.
 - (4) The CPM consultant will establish the level of detail to be reflected in the CPM system.
 - (5) Seasonal weather conditions shall be considered in the planning and scheduling of all work influenced by high or low ambient temperatures for the completion of all Contract work within the allotted Contract duration. In addition, appropriate allowances shall be made for anticipated time losses due to normal rain and snow conditions based on

the previous five year average for that geographical area, by statistically expanding the estimated time duration for weather-sensitive activities, to ensure that the required completion date is achieved.

- b. The Contractor shall be prepared to meet as many times as necessary with the CPM consultant to develop the information required for the timely development of the progress CPM schedule.
- c. The Contractor shall furnish a breakdown of its total Contract price by assigning dollar values to each applicable network activity, coded for the Contractor and each Subcontractor, which cumulatively equals the total Contract amount. Upon acceptance by DPMC, the values will be used as a basis for determining progress payments. Progress payments to the Contractor shall be dependent upon final acceptance by DPMC of the cost-loaded progress CPM schedule.
- d. Accompanying the network diagram and computer scheduling listing, the CPM consultant will furnish a computer-generated cost requisition listing, which will provide a separate tabulation of each activity shown on the CPM schedule in order of bid item or trade responsibility code as agreed to by DPMC. This listing will show, for each activity, the Contractor and each Subcontractor, the estimated dollar value of Work in place for totally or partially completed activities, including subtotals by bid items and grand totals for the entire Project. The cost requisition listing will also contain monthly activities reflecting the cost of Project overhead and administrative expenses, and activities reflecting the monthly cost of administering Project General Conditions.

6.2.3 Review and Approval:

After receipt of the initial network diagram, computer-produced schedule and cost requisition listing, the DPMC representative shall meet with the Contractor and CPM consultant for joint review, correction, or adjustment of the proposed plan and progress CPM schedule to evaluate the cost values assigned to each activity. Within ten (10) calendar days after the joint review, the CPM consultant will revise the network diagram and/or computer-produced schedule in accordance with agreements reached during the joint review, and shall submit two (2) copies each of the revised network diagram, computer-produced schedule and cost requisition listing to DPMC. The revised schedule documents will be reviewed by DPMC and, if found to be as agreed upon, will be approved. A copy of each will be returned to the CPM consultant for distribution and the CPM consultant shall forward same to the Contractor by email and/or overnight mail. The Contractor shall review these documents and shall indicate acceptance by signing the schedule documents. If the Contractor objects to the schedule documents, the Contractor shall forward these objections in writing to DPMC within ten (10) calendar days of the date of receipt of same or be deemed to have accepted the schedule documents. Objections shall include the precise activities of the schedule to which the Contractor objects and identify the basis of the objection. The Contractor will then meet with the DPMC representative and the CPM consultant to review the Contractor's objections. The CPM consultant may

revise the network diagram and the computer-produced schedule in accordance with the agreements reached during this final review and shall submit two (2) copies each of the revised network diagram, computer-produced schedule and cost requisition listing to DPMC. The re-submission will be reviewed by DPMC and, if found to be as agreed upon, will be approved and a copy of each will be returned to the CPM consultant for distribution and the CPM consultant shall forward same to the Contractor by email and/or overnight mail. The Contractor shall review these schedule documents to ensure that that the documents reflect all changes agreed upon, accept and sign. The Contractor shall indicate its acceptance by signing the scheduling documents, computer-produced schedule and cost requisition. Approval will be without reservation, and the Contractor will be deemed to have accepted the schedule as adequate, proper and binding in all respects and shall not raise further objections to the schedule.

b. After the network diagrams and computer-produced schedule have been signed by the Contractor, the CPM consultant shall forward to the Contractor and DPMC one set of copies of the network diagrams and computer-produced schedule. The network diagram and the computer-produced schedule with approved signatures shall constitute the Project work schedule until subsequently revised in accordance with the requirements of this section.

6.2.4 Progress Reporting and Changes:

- a. Once every month, or more often if required by DPMC, the Contractor shall meet with the CPM consultant and DPMC's representative(s) and provide the information necessary for the CPM consultant to prepare and submit to DPMC a revised (updated) network diagram and computer-generated schedule listing showing:
 - (1) Approved changes in activity sequencing;
 - (2) Changes in activity duration for activities not started or partially completed where agreed upon;
 - (3) The effect on the network of any delays in any activities in progress, and/or the impact of known delays which are expected to affect future work;
 - (4) The effect of Contractor modifications (activity duration, logic and cost estimates) to the network;
 - (5) Changes to activity logic, where agreed upon, to reflect revision in the Contractor's work plan, i.e., changes in activity duration, cost estimates, and activity sequences for the purposes of regaining lost time or improving progress; and
 - (6) Changes to milestones, due dates, and the overall Contract completion date which have been agreed upon by DPMC since the last revision of the CPM schedule.
- b. The CPM schedule shall accurately reflect the manner in which the Contractor intends to proceed with the Project and shall incorporate the impact of

all delays, Change Orders and change events as soon as these factors can be defined. All changes made to the schedule shall be subject to approval by DPMC prior to inclusion in the CPM schedule. If the DPMC representative and the Contractor are unable to agree as to the amount of time to be allowed for Change Order work, or the manner in which the Work is to be reflected on the network diagram, the CPM consultant will reflect the logic and time duration furnished by the Contractor for the Change Order work pending final DPMC decision. If non-approved Contractor logic and time durations are used, the Contractor agrees that any time which is projected to be lost on the Project as a result of these schedule changes will be considered the responsibility of the Contractor until a final agreement has been made or a final decision rendered by DPMC regarding the manner in which the Change Order work is to be reflected on the schedule. When this final decision has been made by DPMC, the CPM consultant shall revise the CPM schedule in accordance with such decision and issue a final analysis of the effect of the change on the Project.

- c. If the Contractor desires to revise the logic of the approved progress CPM schedule to reflect a sequence of construction that differs from that to which was previously agreed, the Contractor must first obtain the approval of DPMC.
 - (1) Once each month, at the same time the network is updated, the CPM consultant, the Contractor and the DPMC representative(s) shall jointly make entries on the preceding network diagram schedule to show actual progress, identify those activities started by date and those completed by date during the previous period, show the estimated time required to complete each activity started but not yet completed, show activity percent completed and/or dollars earned, and reflect any changes in the network diagram approved in accordance with the preceding paragraph. After completion of the joint review and DPMC's approval of all entries, the CPM consultant will submit updated network diagrams, an updated computer-produced calendar-dated schedule and cost requisition listing to DPMC.
 - (2) The resultant monthly CPM computer printout and network diagrams shall be recognized by the Contractor as its sole updated construction schedule to complete all remaining Contract work.
 - (3) In addition to the foregoing, once each month the Contractor will receive a narrative report prepared by the CPM consultant. The narrative report will include a description of the amount of progress made during the last month in terms of completed activities in the plan currently in effect, a description of problem areas, current and anticipated delaying factors and the estimated impacts the delays have on the performance of other activities and completion dates, and recommendations on corrective action for the Contractor. Within seven (7) calendar days after receipt of this report, the Contractor shall submit to DPMC a written explanation of corrective action taken or proposed. The DPMC, after reviewing the written submission, may take appropriate action.

6.2.5 Payments to Contractor

- a. The monthly submission of the computer-produced calendar-dated schedule shall be an integral part and basic element of the estimate upon which progress payments shall be made pursuant to the provisions of Article 9 of these General Conditions. The Contractor shall be entitled to progress payments only upon receipt by DPMC of an updated computer-produced calendar-dated schedule and cost requisition listing.
- b. Payments to the Contractor shall be based upon the results of the computer-generated cost requisition listing which shall be prepared in conjunction with each updating of the CPM system as described above. The Contractors shall provide sufficient documentation to confirm reported progress for any cost items appearing in the scheduling and requisition system.
- c. Payments to the Contractor shall be dependent upon the Contractor furnishing all of the information which, in the judgment of DPMC, is necessary to ascertain actual progress, and all the information and data necessary to prepare any necessary revisions to the computer-produced calendar-dated schedule, cost requisition listing and/or the network diagram. DPMC's determination that the Contractor has failed or refused to furnish the required information shall constitute a basis for withholding payments until the required information is furnished and the schedule and/or diagram is prepared or revised on the basis of such information.

6.2.6 Biweekly Progress Meetings

- a. Every two (2) weeks or as otherwise directed by DPMC, the Contractor shall attend a coordination and CPM scheduling meeting on the job site. At this meeting, the Contractor shall provide detailed information regarding the Work schedule to be performed during the upcoming two weeks to permit the CPM consultant to prepare schedules for the subsequent two week period. Biweekly scheduling by the Contractor shall be in accordance with the priorities and degree of concurrent work required by the official CPM schedule for the Project. The Contractor shall be prepared to explain any difference between the Contractor's biweekly schedules and the priorities required by the latest updating of the official CPM schedule.
- b. At the biweekly scheduling meeting, the CPM consultant shall review the schedule for the preceding two (2) weeks, and the Contractor shall report the progress actually achieved for each activity which was scheduled to be performed during the two weeks, including the actual dates on which the Work was performed. The Contractor agrees that this information shall constitute the official historical record of Project progress.
- c. At each biweekly scheduling meeting, the Contractor shall document any current delays to work operations. In addition, the Contractor shall provide any available information regarding any potential delays.
 - (1) Following the biweekly scheduling meeting, the CPM consultant will issue to the Contractor a two-week look-ahead schedule as developed

at the meeting that shall constitute the construction schedule for the coming two weeks. The CPM consultant will also issue a narrative biweekly progress analysis documenting progress achieved during the preceding two weeks and analyze delays reported to constitute current or anticipated impacts to timely construction.

(2) The Contractor shall be represented at the biweekly scheduling meeting by its superintendent, who shall have complete authority to provide the information required for the development of the next two (2) weeks schedule, which includes documentation of past progress and documentation of delays. The Contractor's representatives shall also be authorized to commit to the implementation of corrective action planned to overcome delaying conditions.

6.2.7 Responsibility for Completion

- a. The Contractor agrees that, when it becomes apparent from the current project CPM schedule that any Contract completion date will not be met, the Contractor will take any or all of the following actions, as required, at no additional cost to the State:
 - (1) Increase construction manpower.
 - (2) Increase the number of working hours per shift, shifts per working days, working days per week, or the amount of construction equipment, or any combination of the above; and/or
 - (3) Reschedule activities to achieve maximum practical concurrence.

6.2.8 Adjustment of Contract Completion Date

- a. The Contract completion dates will not be adjusted except under the specific and limited conditions set forth in the Contract Documents. In the event that the Contractor requests an extension of any Contract completion date, the Contractor shall furnish a justification of such extension and provide any and all supporting evidence that DPMC requires to evaluate the Contractor's request. The DPMC shall either approve, in whole or in part, or reject the Contractor's request and will advise the Contractor in writing of its decision. If the DPMC finds that the Contractor is entitled to any extension of any Contract completion date under the provisions of this Contract, the determination as to the total number of calendar days extension permitted shall be based upon the currently approved Project CPM schedule and on all data relevant to the extension request. Such data will be included in the next updating of the CPM schedule.
- b. The Contractor acknowledges and agrees that the evaluation of Project delays and determinations regarding Project time extension will be based upon the Project CPM schedule and the following criteria:
 - (1) Float time shown on the Project CPM schedule is not for the exclusive use of either the Contractor or DPMC. It is agreed that float time is available for use by all performing Work on the Project, including the Contractor, other contractors, subcontractor, lower tier subcontractors,

and suppliers to facilitate the effective use of available resources and to minimize the impact of problems of Change Orders which may arise during construction. The Contractor specifically agrees that float time may be used by DPMC or its representatives or consultants in conjunction with the review activities or to resolve Project problems. The Contractor agrees that there will be no basis for a Project time extension as a result of any Project problem, Change Order or delay which only results in the loss of available positive float on the Project CPM schedule. The Contractor further agrees that there will be no basis for a claim for cost escalation for any activity which is completed on or before its initially required late end date as shown on the initial approved Project CPM schedule, regardless of the justifiability or any delaying factors which might have resulted in the elimination of float which was originally available for the activity. If the Contractor refuses to perform work that is available to it, the DPMC may consider, the Contractor to be in breach of the Contract, regardless of the float shown to be available for the Work. In such instances, the DPMC may, without prejudice to any other right or remedy, declare the Contractor to be in default and terminate the employment of the Contractor pursuant to Article 12 of the General Conditions.

- (2) The Contractor agrees that no time extension will be granted for time lost due to normal seasonal weather conditions. In order to qualify for consideration for a time extension due to adverse weather conditions, it must be shown by clear and convincing evidence that the weather conditions during a given quarterly period (summer, fall, winter, spring) were more severe than the previous five-year (5) average for the Project geographical area, and that these weather conditions critically impacted the final Project completion date by delaying the performance of work on the main Project critical path. If abnormal weather losses can be shown to have affected the Project critical path, a non-compensable time extension will be considered for that portion of the proven weather-related delays, which exceeded normal weather losses that should have been anticipated for the quarterly period in question.
- (3) No time extensions will be considered for any weather conditions that do not affect work on the Project critical path as set forth on the current Project CPM schedule. The Contractor agrees that there will be no basis for a claim for any additional compensation resulting from any time extension issued for weather-related delays.
- (4) In order for a given cause (i.e., delay, Change Order, etc.) to be considered as a basis for a total Project time extension, it must meet both of the following criteria:
 - (a) It must be totally beyond the control of the Contractor and due to no direct or indirect fault of the Contractor; and
 - (b) It must result in a direct delay to work on the main Project critical path.

- (5) The Contractor acknowledges and agrees that actual delays to activities that, according to the Project CPM schedule, do not directly affect the main Project critical path and do not have any effect on the Contract completion date or dates, will not be the basis for a change therein.
- (6) Concurrent delays are defined as two or more delays or areas of work slippage that are totally independent of one another and which, if considered individually, would each affect the final Project completion date according to the Project CPM schedule. Where the CPM consultant determines that concurrent delays exist, the Contractor acknowledges and agrees that the following criteria will be used to evaluate time extension:
 - If the current Project CPM schedule shows two (2) or more (a) concurrent delays, with one analyzed to be the responsibility of DPMC and the other analyzed to be the responsibility of the Contractor, a non-compensable time extension will be considered only if the excusable delay affects the main Project critical path and this delay is shown to be a greater amount than the other concurrent delays when the impacts of the concurrent delays are independently considered. In this event, a compensable time extension will be considered only for that portion of time by which the excusable delay exceeds all concurrent non-DPMC caused delays. For example, if an excusable impact delays the Project by one-hundred (100) calendar days and concurrent contract-caused slippage independently delays the final completion date by ninety (90) calendar days, a time extension will only be considered for a maximum of ten (10) calendar days, provided the excusable delay is on the project critical path.
 - (b) If the CPM schedule shows concurrent delays with some excusable delays and some the fault of the Contractor, and if the Contractor-caused delays are analyzed to be the main determining impact to the main Project critical path, then there will be no basis for a total Project time extension regardless of the nature of the concurrent excusable delays. A concurrent time extension may, however, be considered for that portion of the total Project slippage which is shown on the CPM schedule to be totally attributable to excusable delays.
 - (c) If a time extension request is being made for concurrent delays which did not affect the Project critical path, this must be clearly stated in the Contractor's time extension request and all CPM activities which are claimed to have been affected by the cited delay must be specifically identified with all applicable impact dates.

6.3 CONSTRUCTION PROGRESS SCHEDULING PROVIDED BY THE CONTRACTOR

- 6.3.1 The Project shall be completed within the specified number of calendar days from the effective date of the Notice to Proceed.
- 6.3.2 The Contractor shall be responsible for preparing and furnishing to the DPMC through the Architect/Engineer before the first Contract requisition date, but in no event later than 30 (thirty) days after the effective date of the Notice to Proceed, a coordinated combined progress schedule that incorporates the progress schedules of the Contractors and all Subcontractors engaged on the Project. The schedule shall be in the form of a network diagram or other recognized graphic critical path progress schedule format that indicates, among other things, predecessor and successor activities, and major and intermediate milestones, in sufficient detail to satisfy the DPMC. (See also section 6.3.4 below.) The Contractor's initial invoice will not be processed by the DPMC until and unless such a single coordinated progress schedule has been submitted to and approved by the DPMC. Thereafter, the Contractor shall submit an updated coordinated progress schedule on a monthly basis. Receipt and approval of the updates will be a mandatory condition to payment.
- 6.3.3 Once each month, or more often if required by the DPMC, the Contractor shall meet with the Architect/Engineer and the DPMC representative to gather the information necessary for the Contractor's preparation of the revised/updated computer generated scheduling reports.
- 6.3.4 The progress schedule, based upon the logic and time estimates, shall indicate in suitable detail for display, all significant features of the Work of the Contractor and each Subcontractor, including but not limited to, the placing of orders, manufacturing durations, anticipated delivery dates for critical and long-lead items, submissions and approvals of shop drawings, construction activities, all work activities to be performed by the Contractor and its Subcontractors, the beginning and time duration thereof, and the dates of all milestones, substantial and final completion of the various elements of the Work, including punch list and close-out. Reports shall be in booklets, indexed and separated as categorized below. Each activity listed on the Schedule shall include, as a minimum, the following:
 - a. The activity description;
 - b. The trade (A/E, Owner, GC, Electrical, Plumbing, HVAC);
 - c. The duration in calendar days;
 - d. The Early Start date;
 - e. The Late Start Date;
 - f. The Early Finish date;
 - g. The Late Finish date;
 - h. The Total Float

- 6.3.5 The Contractor agrees that no time extension will be granted for time lost due to normal seasonal weather conditions. In order to qualify for consideration for a time extension due to adverse weather conditions, it must be shown by clear and convincing evidence that the weather conditions during a given quarterly period (summer, fall, winter, spring) were more severe than the previous five-year (5) average for the Project geographical area, and that these weather conditions critically impacted the final Project completion date by delaying the performance of work. If abnormal weather losses can be shown to have impacted the Project completion date, a non-compensable time extension will be considered for that portion of the proven weather-related delays, which exceeded normal weather losses that should have been anticipated for the quarterly period in question.
- 6.3.6 Immediately upon approval by DPMC, the Contractor shall prepare and distribute four copies of the progress schedule to the DPMC plus two copies to the Architect/Engineer. Each monthly updated coordinated schedule shall be signed and dated by the Contractor.
- 6.3.7 The Contractor shall furnish sufficient labor and construction plant and equipment to ensure the execution of the Work in accordance with the approved progress schedule. If any updated completion time or date for any activity does not conform to the durations or milestones shown in the approved progress schedule, the sequence of activities and/or the time for performance of activities shall be updated on the progress schedule to be approved by the DPMC and cured by the Contractor by any means, including performing concurrent operations, additional manpower, additional shifts, and overtime. No additional charges to the State will be allowed the Contractor for overtime, additional manpower, equipment, additional shifts, etc. (except as may be provided elsewhere in the Contract), if such expediting procedures or measures are necessary to meet the Contract completion date.
- 6.3.8 The progress schedule shall show:
 - a. Recommended Changes in activity sequencing;
 - b. Changes in activity duration for activities not started or partially completed, where agreed upon;
 - c. The effect on the network of the modifications (activity duration, Predecessors and Successors);
 - d. Changes for the purposes of regaining lost time or improving progress, and;
 - e. Changes to milestones, due dates, and the overall Contract completion date, which have been agreed upon by the DPMC's project manager since the last revision of the progress schedule.
- 6.3.9 The progress schedule shall accurately reflect the manner in which the Contractor intends to proceed with the Project and shall immediately incorporate and reflect the impact of all delays and change orders. All changes made to the schedule shall be subject to approval by the DPMC.

6.3.10 The DPMC will not authorize or approve any claims for additional payment or extension of time for completion of the Work, or any other concession because of any alleged misinterpretation or misunderstanding on the Contractor's part of the Project schedule, the Contractor's failure to attend the pre-bid conference, because of any failure on the Contractor's part to become fully acquainted with all conditions relating to the Project schedule and the manner in which it will be used on the Project, or because of any other failure by the Contractor to properly participate in the development of a progress schedule or to perform the Contract in accordance with the progress schedule.

ARTICLE 7 - TIME OF COMPLETION

7.1 CONTRACT DURATION/NOTICE TO PROCEED

- 7.1.1 Contract duration shall commence on the effective date set forth on the written Notice to Proceed. The Notice to Proceed will be issued by the DPMC after the DPMC's receipt and acceptance of properly executed Contract Documents, including performance and payment bonds, proof of insurance and permit technical information submitted by the Contractor and/or Subcontractors. The Contractor shall not be entitled to delay, disruption, acceleration or any other claims arising from a deferred issuance of the Notice to Proceed.
- 7.1.2 The Contractor shall perform no work at the Contract Site prior to the issuance of the Notice to Proceed.

7.2 SUBSTANTIAL COMPLETION

- 7.2.1 At the request of the Contractor, the Architect/Engineer or the DPMC, the Contractor and the DPMC representative may make a joint inspection of the Work for the purpose of determining if the Work is substantially completed in accordance with the definition provided in Article 1. If DPMC, in its sole discretion, finds that the Work is substantially complete, then the DPMC will issue a written Notice of Substantial Completion for Beneficial Use. Such Notice shall in no way relieve the Contractor of any contractual obligation(s) or relieve the Contractor from responsibility to promptly complete all remaining Contract Work including, but not limited to, punch list items.
- 7.2.2 The standard guarantee period for equipment, workmanship and materials shall commence on the date DPMC issues the Notification of Substantial Completion for Beneficial Use, or from the time of completion and acceptance of equipment, work or materials in question, whichever is later.
- 7.2.3 In the event that the Project is completed in phases or stages, and/or in the event that the DPMC takes possession of any part of the Work pursuant to Section 7.4 of these General Conditions, no part of the Project shall be deemed substantially complete for purposes of the New Jersey Statute of Repose, N.J.S.A. 2A:14-1.1, prior to the issuance of a formal Notice of Substantial Completion for Beneficial Use for the all of the Work.

7.3 FINAL COMPLETION

- 7.3.1 Final completion of the Contract shall occur when:
 - a. The DPMC and the Architect/Engineer have determined that the punch list has been completed;
 - b. The Contractor has complied with the Contract Document's closeout requirements;
 - c. The Contractor has submitted all Contract deliverables as required by the Contract Documents including but not limited to the following: "as-built"

documents, operating and maintenance manuals, attic stock, parts lists, repair source lists, training and certificates; and

d. The Contractor has submitted all warranties, guarantees and/or maintenance bonds required under the Contract.

7.4 PARTIAL OCCUPANCY FOR USE

- 7.4.1 Use and possession prior to completion: The DPMC shall have the right to take possession or use of any completed or partially completed part of the Project. Said possession or use shall not be deemed acceptance of the Work performed on the Project.
- 7.4.2 Prior to such possession or use, the DPMC shall furnish the Contractor with an itemized list of Work remaining to be performed or corrected on such portions of the Project that are to be possessed or used by the State. Failure by the DPMC to list any item of work shall not be deemed an acceptance of any Work under the Contract.
- 7.4.3 The Contractor shall not be entitled to recovery of money damages for any delays, disruptions or inefficiencies caused by such partial occupancy.

7.5 DELAY, DISRUPTION AND INTERFERENCE

7.5.1 Delay - Time Extension. If the Contractor's work is delayed, disrupted or interfered with by act, neglect or default of any party, including the State, the Architect/Engineer, or by strikes, lockouts, fire, unusual delay by common carriers, natural disasters, or by any cause for which the Contractor is not responsible; then for all such delays and suspensions, the Contractor shall be allowed one (1) calendar day addition to the time herein stated for each and every calendar day of such delay so caused in the completion of the Work as specified above, the same to be determined by the DPMC. No such extension shall be granted for any delay unless, within ten (10) calendar days after the beginning of such delay, a written request for additional time shall be filed with the DPMC.

7.5.2 Contractor's Damages for Delay, Disruption or Interference

The Contractor shall not be entitled to recovery of money damages from the DPMC caused by delay, disruption or interference with the Contractor's Work except as expressly provided under section 7.5.2 of these General Conditions paragraph. The Contractor expressly agrees that the Contractor's remedy for delay, disruption of interference shall be limited to an extension of time only and that there shall be no recovery of money damages by the Contractor for any delay, disruption or interference with the Contractor's work attributable to any cause whatsoever (other than the State's negligence, bad faith, active interference or other tortuous conduct). The Contractor expressly agrees that it shall not be entitled to recover damages due to delay, disruption or interference caused by any of the following:

- a. Delayed execution of the contract or any of the causes referenced in paragraph 7.5.2;
- b. Any act or omission by any party other than the State, including, but not limited to, the Architect-Engineer, any other Contractor or Subcontractor, any

CPM or other consultant retained by the State, any construction manager retained by the State, any agency or instrumentality of the federal government or of any local governmental entity or any utility (e.g., gas, electric, telephone, cable);

- c. Any act or omission of any agency or instrumentality of the State, other than the DPMC, including, without limitation, the Department of Environmental Protection and the Department of Community Affairs;
- d. Weather;
- e. Subsurface conditions of any type including, without limitation rock and underground utilities, whether or not such conditions were reasonably ascertainable to the Contractor at the time of bidding;
- f. Use of all or any portion the Project premises prior to completion of the Work to the extent that such use is permitted under the terms of the Contract;
- g. Delay in obtaining any permit or approval;
- h. Delay caused by the issuance of any court order, injunction or restraining order;
- i. Any delay which does not entitle the Contractor to an extension of the Contract Completion Time under Section 6.2.8 of these General Conditions; or
- j. Delay attributable to any other cause, other than a cause for which the State is legally restricted from enforcing a contractual "no damage for delay" clause under N.J.S.A. 2A:58B-3 or any other provision of law restricting or barring the enforcement of such clauses.

In interpreting this provision, the negligence or other wrongful conduct of others, including, without limitation, the Architect/Engineer, the CPM consultant, any construction management firm and any other firm or person retained by the State shall not be imputed to the State. Further, to the extent that the Contractor is entitled to recover monetary damages for delay under this Contract, such recovery shall be limited to actual direct costs incurred on account of the delay, and shall not include profit or other markup on such costs, home office overhead calculated under the Eichleay formula or any other kind of consequential or indirect cost or damage, including but not limited to any alleged cost or damage under the total cost method, the modified total cost method, or productivity factors (costs for inefficiency based on industry productivity factors such as those provided by the Mechanical Contractors Association of America (MCAA) Factors Affecting Labor Productivity).

7.5.3 In the event of the failure of the Contractor to complete its work within the time stated in its Contract, the Contractor shall be liable to the State in the sum as set forth as liquidated damages in the Contract, for each and every calendar day that the Contractor fails to attain contract completion of the work. This sum shall be treated as liquidated damages to compensate for the loss to the State of the use of premises in a completed state of construction, alteration or repair, and for added administrative and inspection costs to the State on account of the delay; provided, however, that the said liquidated damages shall be in addition to other compensatory or consequential losses or damages

that the State may incur by reason of such delay, such as, but not limited to, added costs of the Project and the cost of furnishing temporary services, if any. Any such sums for which the Contractor is liable may be deducted by the State from any moneys due or to become due to the Contractor.

- 7.5.4 It is hereby understood and mutually agreed by and between the Contractor and the State that the start date in the Notice to Proceed, the dates of all required intermediate milestones, and the times for substantial and final completion, as specified in the Contract Documents, are essential conditions of this Contract.
- 7.5.5 The Contractor agrees that said work shall be executed diligently, at such rate of progress as will ensure full completion of the Work within the time specified. It is expressly understood and agreed, by and between the Contractor and the State, that the time for the completion of the Work herein is a reasonable time, taking into consideration the average climactic range and usual industry conditions prevailing in this locality. If the said Contractor shall neglect, fail or refuse to complete the Work within the time herein specified, or any proper extension thereof granted by the DPMC, then the Contractor does hereby agree, as a part of the consideration for the awarding of its Contract, to pay the State the amount specified in section 7.5.3 above, as liquidated damages for loss of use of the Project as hereinafter set forth, for each and every calendar day that the Contractor may have exceeded the stipulated date in the Contract for substantially completing the Work.
- 7.5.6 It is further agreed that time is of the essence of each and every portion of this Contract and of the specifications wherein a definite and certain length of time is fixed for the performance of any act whatsoever; and where under the Contract an additional time is allowed for the completion of any Work, the new time limit fixed by such extension shall similarly be of the essence.

ARTICLE 8 - CLOSE-OUT

8.1 CLOSE-OUT PROCEDURES/FINAL PAYMENT

As part of the final completion procedures described in Article 7 and the requirements for payment as described in Article 9, the Contractor must complete all of the Close-out procedures as follows:

- a. Submit the "as-built" record documents as described in Article 4;
- b. Submit all operating and maintenance manuals, parts lists, repair source parts, and certificates as defined in 8.2 below;
- c. Provide the necessary training for operating systems and equipment as defined in 8.3 below; and
- d. Submit all guarantees as defined in 8.4 below.

8.2 OPERATIONS, EQUIPMENT AND MAINTENANCE MANUALS

- 8.2.1 The Contractor shall provide six (6) copies of all operating, equipment and maintenance manuals, and applicable warranties, as identified and described in the Contract Documents. The operating, equipment and maintenance manuals and warranties, including contact personnel, addresses and telephone numbers, must include a complete description of all systems and equipment and the method of operating and maintaining the equipment. These manuals must be submitted to the Architect/Engineer for review and approval at the earliest date possible following substantial completion, but in all cases prior to final acceptance. Included within the manuals shall be a list of names, addresses and telephone numbers of all the Subcontractors involved in the installations and of firms capable of performing services for each mechanical item.
- 8.2.2 As a pre-condition to the Final acceptance of a facility for beneficial use, the Contractor shall provide a "throw-away" copy of operations and maintenance manuals to allow the Using Agency's staff to operate the equipment prior to receiving the hard bound copies required by this Contract.

8.3 TRAINING

The Contractor shall provide formal instruction for DPMC-designated personnel, addressing the operation and maintenance of the facilities and all installed equipment for each operating system or major item of equipment or as otherwise specified. The operations and maintenance manuals shall be used as training materials. Unless otherwise accepted by the DPMC, training course format shall be split equally between classroom instruction and field exercise. All classroom instruction may be videotaped by the DPMC. Classroom instruction may be supported by professionally made videotapes. If used, a copy of each professional video that was utilized shall be provided to the DPMC at no cost for future training and reference.

8.4 GUARANTEE

- 8.4.1 The issuance of a final certificate for payment and/or partial or complete occupancy of the premises shall not be deemed an acceptance of Work not completed in accordance with the Contract Documents. The issuance of a final certificate for payment and/or partial or complete occupancy of the premises shall not relieve the Contractor or its surety of liability with respect to any express or implied warranties or responsibility for faulty materials or workmanship.
- 8.4.2 The Contractor shall guarantee and warrant, in writing, the Work performed and all materials furnished under this Contract against defects in materials and/or workmanship The Contractor shall be responsible for the value or repair of any damage to other Work or to the building premises resulting from the performance of the Contract.
- 8.4.3 The Contractor is responsible for the above-stated obligations for a period of one (1) year from the date established in 7.2.2 above. All guarantees, including bonds and registrations, required by the Contract Documents shall be in writing and delivered to the DPMC with submission of the invoice for final payment.
- 8.4.4 Contractor shall, at its own expense and without cost to the State, promptly after receipt of written notice thereof, make good any defects in materials or workmanship which may develop during stipulated guarantee periods, as well as any damage to other Work caused by such defects or by repairs. Any other defects in materials or workmanship not discovered during the guarantee period shall be repaired and/or replaced at the Contractor's expense, and such shall be completed within a reasonable time after written notice is given to the Contractor.
- 8.4.5 rsuant to the Contract Documents, certain permanent equipment, including elevators and HVAC systems, will have to be activated during construction of the Project to support construction operations. Despite any early activation during the construction of the Project, any and all equipment warranties must extend for the time periods required in the Contract Documents, starting at the date set forth in paragraph 7.2.2.
- 8.4.5 It is expressly acknowledged and agreed that the express and implied warranties and guarantees to which the State is entitled as well as all warranty and guarantee bonds issued by any surety, shall be in addition to and not in lieu of the State's right to seek recourse against the Contractor and the Contractor's surety for defective work.

ARTICLE 9 - PAYMENTS

9.1 INVOICES

- 9.1.1 Requests for payment under the Contract for materials delivered or services rendered require the proper completion and submittal of specific forms including, but not limited to, the following:
 - a. DPMC Form 11/AR50-1 DPMC Invoice;
 - b. DPMC Form 11-2 Monthly Estimate for Payment to Contractor;
 - c. DPMC Form 11-2a Certification of Prime Contractor;
 - d. DPMC Form 11-2b Certification of Subcontractor;
 - e. Copies of Subcontractor(s) invoices;
 - d. DPMC Form 11-3 Prime Contractors Summary of Stored Materials;
 - e. DPMC Form 11-3A Agreement and Bill of Sale Certification for Stored Materials;
 - f. Consent of Surety forms;
 - g. Certified Payroll Records;
 - h. Updated project schedule
 - i. Any other information or documentation required by other provisions of the Contract documents.
- 9.1.3 The Contractor shall submit the completed request for payment on a monthly basis for all properly completed billable work to the DPMC Project representative and at the address identified at the pre-construction conference.
- 9.1.4 One (1) original and one (1) copy of the request for payment packets shall be prepared and submitted unless otherwise specified.
- 9.1.2 No request for payment shall be deemed to be formally submitted and received for payment until all dollar amounts and completion percentages for each line item in the invoice has been determined and agreed upon by the State and the Contractor.
- 9.1.5 For the purpose of the State's Prompt Payment Act (N.J.S.A. 2A:30A-1 et seq.):
 - a. A proper invoice will be deemed to have been received by the owner when it is received by the person or entity designated by the State to review and sign the invoice on the State's behalf at the address designated in the pre-construction conference for receipt of invoices. Receipt of an invoice by such person or entity shall commence the running of the 20-day period for formal approval and certification as provided under N.J.S.A. 2A:30A-2(a);
 - b. The "billing date", as the term is used in N.J.S.A. 2A:30A-2, shall be the earlier of the date upon which an invoice for payment is approved for payment or twenty (20) days after the invoice is received, unless within such 20-day period

the invoice is found to be incomplete or otherwise unacceptable and returned to the contractor, with a written explanation of deficiencies;

- c. In the event that an invoice is found to be deficient and returned to the contractor, the "billing date" shall be calculated from the date that a corrected invoice is received.
- d. Payment shall be considered to have been made on the date on which a check for such payment is dated;
- e. Payment terms (e.g., "net 20") offered by the contractor shall not govern the State's obligation to make payment;
- f. The following periods of time will not be included in the calculation of the due date of any contractor invoice:
 - (1) Any time elapsed between receipt of an improper invoice and its return to the contractor, not to exceed twenty (20) calendar days; or
 - (2) Any time elapsed between the State's return of an improper invoice to the contractor and the State's receipt of a corrected invoice.
- 9.1.6 The provisions of this Article 9 shall not govern the State's payment obligations nor shall they supersede or modify any other contractual provision allowing the withholding of monies from the contractor to the extent that the contractor has not performed in accordance with the provisions of the contract. Nor shall this Article 9 govern the State's payment obligations nor supersede or modify any other contractual provision governing contractor claims for additional compensation beyond the base contract price and approved change orders.

9.2 INTEREST

- 9.2.1 Interest shall be payable on amounts due the contractor if not paid within thirty (30) calendar days after the billing date specified in the above subparagraph 9.1.5(b), as provided under the State's Prompt Payment of Contractors and Subcontractors Act (N.J.S.A. 2A:30A-01, et seq.) Interest on amounts due shall be payable to the contractor for the period beginning on the day after the required payment date and ending on the date on which the check for payment is drawn.
- 9.2.2 Interest may be paid by separate payment to the contractor, but shall be paid within thirty (30) calendar days of payment of the principal amount of the approved invoice.
- 9.2.3 Nothing in this Article 9 shall be construed as entitling the Contractor to payment of interest on any sum withheld by the State for any reason permitted under the contract or applicable law, or on any claim for additional compensation, over and above sums due under the base contract or approved change orders.

9.3 SCHEDULE OF VALUES AND FINAL PAYMENT

9.3.1 .1 Unless otherwise directed, the Contractor shall furnish a schedule of amounts for Contract payments (Unit Schedule Breakdown,) of the total Contract price, showing the amount included therein for each principal category of the Work and for each Contractor

and Subcontractor, in such detail as requested, to provide a basis for determining progress payments. The schedule, as approved, shall be used only as a basis for the Contractor's estimates for progress payments, and approval by the DPMC does not constitute acceptance of the allocability and allowability of costs to a specific element of Work. The Contractor is cautioned that no payment requests shall be approved until the Unit Schedule Breakdown has been approved in writing by the DPMC.

- 9.3.2 The State will make progress payments monthly as the Work proceeds based upon the Unit Schedule Breakdown.
- 9.3.2 .2 All material and Work paid pursuant to progress payments shall thereupon become the sole property of the State. This provision shall not be construed as relieving the Contractor from the sole responsibility for the protection of all material and Work upon which payments have been made for the restoration of any damaged work, or as waiving the right of the State to require the fulfillment of all of the terms and conditions of the Contract.
- 9.3.3 Following completion and acceptance of all work, the amount due the Contractor under this Contract shall be paid only upon satisfactory completion, by the Contractor, of all Contract close-out requirements, completion of a State audit on all Contract values and payments, and after the Contractor has furnished the State with a release of claims against the State, arising by virtue of this Contract, other than claims in stated amounts as may be specifically excepted by the Contractor from the release.
- 9.3.4 If for any reason the Contractor refuses final payment, the Project may be closed out by the State by the processing of a Final Contract Acceptance certification. The lack of such certificate shall not toll the limitations period applicable to Contractor claims against the State.
- 9.3.5 In addition to other warranties required by provisions of the Contract and specifications, the Contractor warrants that title to all Work, materials and equipment covered by an application for payment will pass to the State free and clear of all liens, claims, security interests or encumbrances, either upon incorporation into the construction or upon receipt of payment to the Contractor, whichever occurs first. This provision shall not be construed as relieving the Contractor from sole responsibility for the care and protection of materials and work upon which payments have been made, or for the restoration of any damaged work, or as a waiver by the State of its rights to require fulfillment of all terms of the Contract.
- 9.3.6 By recommending approval of any invoice, the Architect/Engineer shall not be deemed to represent that it has made exhaustive or continuous on-Site inspections to check the quality or quantity of the Work, or that it has reviewed the construction means, methods, techniques, sequences or procedures, or that it has made any examination to ascertain how and for what purpose the Contractor has used the moneys previously paid. The payment of an invoice does not constitute an acceptance of the Work. The State reserves the right to further inspect the Work and to withhold retainage and any additional funds required to pay for any corrective action for non-conforming work.
- 9.3.7 If any corporation licensed to do business in New Jersey shall be or become delinquent in the payment of taxes, assessments or fees due the State, unless under an

active appeal process or any final judgment in the State's favor against the Contractor, the DPMC may, in accordance with N.J.S.A. 54:49-19 or other applicable law withhold moneys due the said corporation for the purpose of assuring the payment to the State of such taxes, assessments, fees or judgment.

9.4 CERTIFICATION OF PAYMENTS TO SUBCONTRACTOR

Pursuant to N.J.S.A. 52:32-40, 41 and N.J.S.A. 2A:44-148; the Contractor shall submit a Certification of Prime Contractors form and a Certification of Subcontractor form for each Subcontractor identified in the Unit Schedule Breakdown, as part of the submission for each invoiced progress payment.

9.5 STORED MATERIALS

- 9.5.1 .1 Unless specifically allowed in the Contract Documents, all materials and equipment must be delivered and installed or stored on the Site prior to payment for such material or equipment.
- 9.5.2 .2 The DPMC may at its discretion allow payment for equipment stored off Site provided that the following has occurred:
 - a. The DPMC has approved the Contractor's written request;
 - b. The equipment has been properly stored in an approved location;
 - c. The Contractor has established the Owner's title to the specific equipment;
 - d. The Contractor has provided sufficient proof of insurance for the materials, equipment and the storage facility;
 - e. The Contractor has submitted a release of liens on said stored equipment;
 - f. The Contractor has submitted a statement agreeing to assume all costs for storage of material and equipment off Site, including, if required by the DPMC, the cost of storing such material and equipment in a bonded warehouse; and
 - g. The Contractor furnishes the "Prime Contractor's Summary of Stored Materials" and "Agreement and Bill of Sale Certification for Stored Materials," forms respectively.

9.6 ALLOWANCES

9.6.1 .1 The Contractor shall include in its bid all allowances as may be set forth in the Contract Documents. The Contractor shall purchase the "allowed materials" as directed by the DPMC on the basis of the lowest acceptable quote from at least three competitive offers or as a negotiated cost subject to DPMC approval. If the actual cost of the "allowed materials" is more or less than the stipulated allowance, the Contract price may be adjusted accordingly. The adjustment in Contract price shall be made on the basis of the actual purchase cost without additional charges for overhead, profit, bond premium or any other incidental expenses. The cost of installation of the "allowed materials." unless

otherwise specified, is to be included as the responsibility of the Contractor in whose Contract the allowance is included, and the Contractor installing such "allowed materials" shall not be entitled to additional payment for such installation.

- 9.6.2 .2 Unless otherwise provided in the Contract Documents:
 - a. These allowances shall cover the Contractor's true costs, including credit for any trade discount, of the materials and equipment required by the allowance, delivered at the Site, including all applicable taxes;
 - b. The Contractor's costs for unloading and handling, labor, installation costs, overhead, profit and other expenses reasonably required in connection with such allowance items shall be included in the Contract sum and not as part of the allowances.

9.7 RETAINAGE

- 9.7.1 In making progress payments for Contract work completed, the State will retain ten percent (10%) of the approved invoice amount until final acceptance and completion of all work covered by the Contract.
- 9.7.2 .2 The Contractor may, after 50% (fifty percent) of the Contract work is in place, and if the Work is proceeding on schedule, apply for a reduction in the amount retained by the State for the duration of the Contract. Such application must be in writing and accompanied by documentation granting formal consent of surety to the reduction in retainage request. If the DPMC determines that the Contractor's performance has been satisfactory and that the reduction is warranted and appropriate, the State may, with the next progress payment, release any portion of the accumulated retainage in excess of five percent (5%) of the Work in place and retain an amount equal to five percent (5%) of the Work in place for the duration of the Contract. If progress of the Work is not maintained in accordance with the approved schedule, the DPMC may elect to re-institute retainage of ten percent (10%) of the Work in place for the duration of the Contract.
- 9.7.3 Withholding Payment for Non-Delivery of Data:
 - a. If technical data such as "as-built" drawings, reports, spare parts lists, repair parts lists, or instruction books (including additional and maintenance manuals), or any part thereof, are not delivered within the time specified by this Contract or are deficient upon delivery, the DPMC has the discretion to withhold from each invoice a percentage (in addition to any other retainage required by the Contract) of the Contract price in accordance with the following table:

When total contract price is: Percentage to be withheld is:

Less than \$250,000. 10% \$250,000.01 through \$1,000,000 5.0% Over \$1,000,000 2.0%

b. The withholding of any sums pursuant to this article shall not be construed as, or constitute in any manner, a waiver by the State of the Contractor's obligation to furnish the data required under this Contract. In the event the

Contractor fails to furnish these items, the State shall have those rights and remedies provided by law and pursuant to this Contract, in addition to, and not in lieu of the sums withheld in accordance with this article.

9.8 MISCELLANEOUS

- 9.8.1 .1 Disputes regarding nonpayment of a Contractor's invoice under this Article 9 may be submitted to non-binding Alternative Dispute Resolution (ADR) upon mutual agreement of the State and the Contractor. In such event, the State and the Contractor shall share equally the fees and expenses of the selected mediator, arbitrator, umpire or other ADR neutral. Provided, however, that nothing herein shall be construed, in whole or in part, as a waiver, release or modification of the provisions of the New Jersey Contractual Act, N.J.S.A. 59:13-1, et seq., which governs claims against the DPMC.
- 9.8.2 .2 A Contractor not paid sums due under an approved invoice within thirty (30) days of the billing date may suspend performance without penalty for breach of contract, but only after providing the State with seven (7) days written notice of non-payment, and only in the event that the State fails to furnish the Contractor, within that seven-day period, a written statement of the amount withheld and the reasons for the withholding. Nothing herein shall be construed to excuse the Contractor's nonperformance, or to limit the State's rights and remedies relating to such non-performance, with regard to any monies withheld from the Contractor upon the proper notice provided under this Article 9, or with regard to any Contractor claim disputed by the DPMC.

ARTICLE 10 - CHANGES IN THE WORK

10.1 CHANGES IN THE WORK

- 10.1.1 The DPMC may at any time, issue a written Change Order which shall direct a change in the Work within the general scope of the Contract, including, but not limited to, changes:
 - a. In the plans and/or specifications;
 - b. In the method or manner of performance of the Work;
 - c. In the State-furnished facilities, equipment, materials, services, or site; or directing acceleration in the performance of the Work; and/or
 - d. In the time for the completion of the Work.

10.1.2 Change Orders

- 10.1.2.1 The Contractor agrees to prepare and submit, within ten (10) calendar days of encountering any conditions it considers a change, or upon receiving official notice of a proposed change or written direction to proceed with a change, a current DPMC form entitled "Contractor Change Order Request," to the DPMC. The Contractor shall submit an original of the form. Failure to submit a timely form may be grounds for rejection of the request for Change Order, at the DPMC's discretion.
- 10.1.2.2 All requests for Contract time extensions must be submitted in accordance with the requirements set forth in Articles 6 and 7, accompanied by copies of the current approved progress schedule and copies of a proposed progress schedule detailing the incorporation of the changed work and the effects of such incorporation on progress. Failure to provide all required information shall be grounds for rejection of the request.
- 10.1.2.3 DPMC will only consider a contract duration extension Change Order request arising from changes in the Work, if that change is proven by the Contractor to have caused a delay in the completion of the Project. When the Contract duration is increased as a result of a change, the resulting change in Contract amount will include the costs of extended performance, computed in accordance with the terms of this Section, and no further consideration of such costs arising from the specific modification will be given.
- 10.1.2.4 Every Change Order request submitted by the Contractor shall furnish a price breakdown, which shall cover all work involved in the change whether such work was deleted, added or changed and shall be in sufficient detail to permit an analysis of all material, labor, equipment, subcontract, overhead costs and profit. Any amount proposed for subcontracts shall be supported by an equally detailed breakdown. In addition, if the request includes a time extension, a justification (see section 10.1.4.) shall also be furnished. The request, together with the price breakdown and time extension justification, shall be furnished by the date specified by the DPMC.
- 10.1.2.5 The following rates shall apply in computing overhead (indirect costs) and profit for Change Orders that do not exceed \$25,000. The percentages shall be applicable for deleted work as well as additional work. When a change consists of both added and

deleted work, the applicable percentages shall be applied to the net cost or credit. In any event, the percentages shall not exceed the following:

- a. Overhead will be the sum of:
 - (1) fifteen percent (15%) of direct labor costs. NOTE: For the purpose of this article, the term "direct labor" shall include all foremen (identified by name and not included in the Project as the full-time superintendent or full time foreman as required elsewhere in the contract documents), equipment operators and skilled, semi-skilled and common laborers directly assigned to the specified operation. The term "direct labor costs" shall consist of the Contract or actual payroll rate of wage per hour and fringe benefits paid for each and every hour that such employees are actually engaged in the performance of the Work.
 - (2) fifteen percent (15%) of direct material costs. NOTE: For the purpose of this article, the term "direct material costs" shall consist of the actual costs of the materials including applicable tax and transportation charges.
- b. For rented equipment, an hourly rental rate will be used which will be determined based upon the monthly rental rates in the current edition of the Rental Rate Blue Book for Construction Equipment (Rental Book) and dividing it by 176. An allowance will be made for operating costs for each and every hour the equipment is actually operating in accordance with the rates listed in the Rental Book. The Contractor will be allowed only 65% (sixty-five percent) of the rental rate on Contractor-owned equipment.
- c. Bond premiums and payroll taxes, if applicable, will be allowed at actual cost. The Contractor shall submit from the surety to DPMC a letter for the bond premiums.
- d. The Contractor's profit on Subcontractor's work will be six percent (6%) of the Subcontractor's costs. Subcontractor indirect costs will be computed in the same manner as for the Contractor. The Contractor agrees to incorporate this article in each of its subcontracts. NOTE: When more than one tier of Subcontractor exists, for the purpose of markups, they shall be treated as one Subcontractor.
- e. A profit of six percent (6%), where profit is allowable by the terms of the applicable Contract provision, shall be added to the Contractor's total cost. Indirect costs shall not be duplicated in direct costs.
- 10.1.2.6 For Change Orders in excess of \$25,000 the maximum allowable percentages of 15% overhead and 6% profit applies unless negotiated lower based upon the nature, extent and complexity of the Work involved.
- 10.1.2.7 The DPMC, in order to avoid delays in the progress of work or when in the best interests of the State, has the discretion to direct the Contractor, in writing, to proceed with work claimed by the Contractor to be extra work, and/or to accelerate its work without a prior agreement on entitlement or costs. Such direction shall be in the form of a Letter of Direction. The Contractor may submit a claim for evaluation by

DPMC, for costs or for time on account of such work and/or acceleration on the form entitled "Contractor Change Order Request," completed in sufficient detail and in accordance with this article within ten (10) calendar days after receipt of the Letter of Direction. Nothing in this article shall excuse the Contractor from proceeding with the Work identified in the Letter of Direction and all other Contract Work. Issuance of a Letter of Direction under this article shall not be intended nor construed as an admission or acknowledgment by the State that the Contractor is entitled to additional compensation and/or time on account of such Work and/or acceleration.

10.2 ACCELERATION

The DPMC may order and direct the Contractor to accelerate its Work at any location(s) by increasing its forces, working overtime and/or working on Saturdays, Sundays, and holidays. If acceleration is required by the DPMC, and not due to any delays on the part of the Contractor, the Contractor will be reimbursed for additional costs.

ARTICLE 11 - CLAIMS AND DISPUTES

11.1 CONTRACTOR CLAIMS

- 11.1.1 Any claims made by a Contractor against the DPMC for damages, extra costs or any other claim made pursuant to the contract are governed by and subject to the New Jersey Contractual Liability Act, N.J.S.A. 59:13-1 et seq., as well as all the provisions in this Contract.
- 11.1.2 Upon presentation by the Contractor of a request in writing, the DPMC may review any decision or determination of the State or the Architect/Engineer as to any claim, dispute or any other matter in question relating to the execution or progress of the Work or the interpretation of the Contract Documents. Consistent with the intent of this Contract, the DPMC may schedule a conference for the purpose of settling or resolving such claims, disputes or other matters. Where such a conference is conducted, the Contractor and/or the Architect/Engineer shall be afforded the opportunity to be heard on the matter in question. Following review of the Contractor's request, the DPMC and the Contractor may settle or resolve the disputed matter, provided however that any such negotiations, conferences, settlement or resolution shall be subject to all requirements imposed by law, including where applicable, the New Jersey Contractual Liability Act (N.J.S.A. 59:13-1 et seq.). The DPMC's participation in any effort to negotiate, settle or resolve any such claim or dispute with the Contractor shall not operate to toll or extend the time limitations for notice or suit under the New Jersey Contractual Liability Act.

11.2 MUTUAL RIGHTS AND RESPONSIBILITIES OF ALL CONTRACTORS AND THE ARCHITECT/ENGINEER

- 11.2.1 Any Contractor or the Architect/Engineer which by its own acts, errors or omissions, damages or unnecessarily delays the Work or otherwise causes damage to the State, any other Contractor or the Architect/Engineer, shall be directly responsible to the aggrieved party or parties, for all costs and expenses incurred due to any such delays and/or damages whether by settlement, compromise or arbitration or judgment.
- 11.2.2 Any Contractor damaged by the actions of another Contractor or Architect/Engineer shall have a direct right to recovery against the party causing such damages, but shall not have a right to recover such damages against the State.
- 11.2.3 In addition, the party responsible for causing such damages agrees to defend, indemnify and save harmless the State from all such claims and damages. Nothing contained in this paragraph shall be construed to relieve the responsible party from any liability or damage sustained on account of such acts, errors or omissions.
- 11.2.4 The State shall not be held vicariously liable to any Contractor for any damages or extra costs caused by any acts or omissions by another party including but not limited to actions of the Architect/Engineer as specified in the above paragraph. The Contractor's exclusive remedy shall be against the party directly responsible for causing such damages or extra costs.

ARTICLE 12 - TERMINATION/SUSPENSION

12.1 SUSPENSION OF THE WORK / STOP WORK

- 12.1.1 If the Contractor fails to correct defective work or persistently fails to carry out the Work in accordance with the Contract Documents, or if the DPMC determines that it is in the best interest of the Project to do so, the DPMC may order the Contractor to stop the Work, or any portion thereof, until the cause for such order has been eliminated and the DPMC provides written notice to the Contractor that the stopped Work may resume.
- 12.1.2 DPMC shall have the right to defer the beginning or to suspend the whole or any part of the Work herein contracted to be done whenever, in the opinion of the DPMC, it may be necessary or expedient for the State to do so.

12.2 TERMINATION FOR CAUSE

- 12.2.1 If the Contractor persistently or repeatedly refuses or fails to supply enough properly skilled workers or proper materials so as to avoid or eliminate delays in the orderly progress of the Work in accordance with the approved schedule; or if the Contractor fails to make prompt payment to any Subcontractor or for materials or labor; or persistently disregards laws, ordinances, rules, regulations or orders of any public authority having jurisdiction; or if the Contractor is guilty of a material breach of a provision of the Contract Documents or otherwise fails to carry out the Work in accordance with the Contract Documents, then the DPMC may, without prejudice to any other right or remedy, and after giving the Contractor and its surety three (3) working days written Notice to forthwith address such breach and default with diligence and promptness, terminate the employment of the Contractor by the issuance of a written Notice to that effect to the Contractor and its surety, should the Contractor fail to comply with the demands of the original above mentioned Three Day Notice.
- 12.2.2 Upon such termination, the DPMC may take possession of the Site and of all the materials, equipment, and tools on the Site and of any materials stored off Site paid for by DPMC, and may finish the Work by whatever method the DPMC may deem expedient. In such case, the Contractor shall not be entitled to receive any further payment until the Work is finished.
- 12.2.3 In the event of termination for default, the surety shall either complete the principal's work or finance the completion of the Work. The surety shall not have the right to do nothing. In the event of the surety's breach of its obligations to the State, the surety shall be subject to all available damages under the law, including but not limited to debarment and the penalties imposed by New Jersey's Consumer Fraud Act.
- 12.2.4 Within seven (7) calendar days following receipt of Notice of Termination by the surety, the surety shall submit in writing its intention to satisfy its bond obligation to the State as obligee, and to explain its plan to complete the Work, tender a completing Contractor or finance the completion of the Work.
- 12.2.5 If the surety elects to take over the Work and complete same or to tender a completing Contractor, it must furnish notice of its intent to do so in writing over the

signature of an authorized representative and such notice shall be served upon the DPMC within seven (7) calendar days after service upon the surety of the Notice of Termination. This document shall identify the Contractor to perform this work.

- 12.2.6 If the surety elects to satisfy its bond obligation by financing the completion of the Work, in lieu of taking over same, the surety and State shall enter into an agreement, within thirty (30) days of the termination Notice, setting forth the details of the payments to be made by the surety. All current obligations for labor and materials incurred and outstanding by the defaulting Contractor on this Project shall be paid by the surety without delay, subject to allowance of reasonable time to verify such claims by the surety.
- 12.2.7 If the surety fails to satisfy its bond obligations within the time frames established above, the DPMC may undertake the completion of the Project in any manner deemed appropriate. In that circumstance, the surety shall not be relieved of any of its payment and performance bond obligations.
- 12.2.8 If the unpaid balance of the Contract sum exceeds the cost of finishing the Work (including but not limited to liquidated damages for delays and all other remaining damages sustained by the State originating from such breach of Contract), such excess shall be paid to the Contractor. If such costs exceed the unpaid balance, the Contractor and its surety shall be obligated to pay the difference to the DPMC promptly upon receipt of billing from the State, and this obligation shall survive the termination of the Contract.

12.3 OWNER'S RIGHT TO COMPLETE THE WORK

12.3.1 Alternatively, should the Contractor fail or refuse to correct its breach and default after receiving the required notice as provided under Section 12.2 hereof, the DPMC, in lieu of terminating the Contractor's employment, may provide for the correction and completion of all remaining Work by other means, and deduct all costs associated with such correction and completion from any undisbursed balance of funds (including earned retainage) remaining under the Contract. Such deduction may be documented by issuance of one or more deductive change orders. DPMC's correction or completion of Work under this paragraph shall not operate to waive, release or diminish the liability of the Contractor and its surety to the State for any breach or default by the Contractor.

12.4 TERMINATION FOR CONVENIENCE

- 12.4.1 .1 The DPMC may, at any time, terminate the Contract in whole or in any part for the DPMC's convenience and without cause when the DPMC in its sole discretion views termination to be in the public interest.
- 12.4.2 .2 Upon receipt of an order of Termination for Convenience, the Contractor shall not proceed with any item of work which is not specified in the Order of Termination. The Contractor shall complete all items of work specified in the termination order. Such work shall include punch list items and all work necessary to ensure the safety of the public, to properly secure existing work already constructed or partially constructed and to secure the Project Site. This work so ordered shall be performed in accordance with the Contract Documents, and may include items of work not in the original Contract. The Work performed shall be considered substantially complete upon completion and

acceptance of all items of work specified in the Order, except punch list items. After completion of the punch list items and all documents required by the Contract, the Contract shall terminate upon issuance of a Final Certificate and payment. The DPMC reserves the right to declare in default a Contractor who fails to carry out the conditions set forth in an Order of Termination for Convenience.

- 12.4.3 When the DPMC orders termination of the Contract for Convenience, all completed items of work as of that date will be paid for at the Contract prices.
- 12.4.3.1Payment for partially completed work will be paid for at agreed prices.
- 12.4.3.2 Payment for new items, if any, will be made either at agreed prices or in accordance with Article 10.
- 12.4.3.3Materials obtained by the Contractor for the Work but which have not been incorporated therein may, at the option of the State, be purchased from the Contractor at actual cost delivered to a prescribed location, or otherwise disposed of as mutually agreed.
- 12.4.4 Within sixty (60) days of the effective termination date, the Contractor shall submit claims for additional costs actually incurred, not covered above or elsewhere in the Contract. Such claims may include reasonable mobilization costs, overhead expenses attributable to the Work performed, Subcontractor costs not otherwise paid for, actual idle labor costs if Work is stopped in advance of the termination date. The DPMC will not compensate the Contractor for costs prohibited under provisions of the Contract and/or anticipated profits on work not performed.
- 12.4.5 If the DPMC terminates the Contractor for cause as provided under Article 12.2 of the General Conditions, and if a court of law subsequently determines such termination for cause to have been undertaken without lawful justification, then such termination shall be deemed a termination for convenience governed by this Article 12.4. In that event, recovery by the Contractor and/or the Contractor's surety shall be limited to those costs which are recoverable following a termination for convenience under this Article 12.4.

ARTICLE 13 – OTHER REQUIREMENTS

13.1 PREVAILING WAGE

- 13.1.1 The Contractor shall comply with the New Jersey Prevailing Wage Act Laws of 1963, Chapter 150, (N.J.S.A. 34:11-56.25 et seq.) and all amendments thereto, and this act is hereby made a part of every Contract entered into on behalf of the State of New Jersey through the DPMC, except those Contracts which are not within the contemplation of the Act. Provisions of the Act include the following stipulations and requirements:
 - a. All workers employed in the performance of every Contract in which the Contract sum is in excess of \$2,000 and to which the DPMC is a party shall be paid not less than the prevailing wage rate as designated by the Commissioner, Division of Labor or his or her duly authorized representative.
 - (1) The Contractor performing public work for the DPMC and which is subject to the provisions of the Prevailing Wage Act, shall post the prevailing wage rates for each craft and classification involved as determined by the Commissioner, Division of Labor. This posting shall include the effective date of any changes thereof, and shall be displayed in prominent and easily accessible places at the Site of the Work or at such place or places as are used by the Contractor/Subcontractor to pay workers' wages.
 - (2) At the time of the bid due date, the Bidder and any Subcontractors identified by the Bidder must be registered in accordance with "The Public Works Contractor Registration Act" (N.J.S.A. 34:11-56.48 et seq.) All questions regarding registration shall be addressed to:

Contractor Registration Unit New Jersey Department of Labor Division of Wage & Hour Compliance P O Box 389 Trenton NJ 08625-0389 Telephone: 609-292-9464

FAX: 609-633-8591

- b. In the event it is found that any worker, employed by any Contractor covered by any Contract in excess of \$2,000 for any public work to which the DPMC is a party, has been paid a rate of wages less than the prevailing wage required by such Contract, DPMC may terminate the Contractor's right to proceed with the Work, or such part of the Work as to which there has been failure to pay required wages, and may otherwise execute the Work to completion.
- c. In the event that any Subcontractor retained by a Contractor on any Contract in excess of \$2,000 for any public work to which the DPMC is a party, has been paid a rate of wages less than the prevailing wage required by such Contract, DPMC may terminate the Contractor's right to proceed with the Work, or such part of the Work as to which there has been failure to pay required wages, and may

otherwise execute the Work to completion or may require that the Contractor immediately substitute a new Subcontractor at the costs set forth in the Contract.

- d Nothing contained in the Prevailing Wage Act shall prohibit the payment of more than the prevailing wage rate to any worker employed on a Project.
- e. The Contractor shall, as a condition of subcontract with any tier Subcontractor, require compliance with this section as a condition of Subcontract.
- f. The State may audit the Contractor's conformance with the Prevailing Wage Act. If the result of such audit determines that the Contractor has not complied with the Prevailing Wage Act then such Contractor shall be responsible for the cost of this audit.

13.2 PATENTS

- 13.2.1 The Contractor shall hold and save the State and its officers, agents, servants, and employees harmless from liability of any nature or kind, including cost and expenses for or on account of any patented or non-patented design, devise, invention, process, article or appliance manufactured or used in the performance of the Contract, including its use by the State, unless otherwise specifically stipulated in the Contract Documents.
- 13.2.2 License and/or royalty fees for the use design, devise, invention, process, article or appliance which is authorized by the State must be reasonable, and paid to the holder of the patent or his or her authorized licensee directly by the State and not by or through the Contractor.
- 13.2.3 If the Contractor uses any design, devise, invention, process, article or appliance covered by letters, patent or copyright, it shall provide for such use by suitable agreement with the State of such patented or copyrighted design, device or material. It is mutually agreed and understood that, without exception, the Contract prices shall include all royalties or costs arising from the use of such design, devise, invention, process, article or appliance in any way involved in the Work.
- 13.2.4 The Contractor and/or its surety shall indemnify and save harmless the State from any and all claims for infringement by reason of the use of such patented or copyrighted devise, invention, process, article or appliance, or any trademark or copyright in connection with Work performed under this Contract, and shall defend and indemnify the State for any cost, expense or damage which it may be obliged to pay by reason of such infringement at any time during the execution of the Work or after the completion of the Work. This section shall survive the termination of the Contract.

13.3 RIGHT TO AUDIT

13.3.1 The State reserves the right to audit the records of the Contractor in connection with all matters related to its Contract. The Contractor agrees to maintain its records in accordance with "Generally Accepted Accounting Principles," for a period of not less than five (5) years after receipt of final payment. All charges must be supported by appropriate documentation, including, but not limited to canceled checks. All records

shall be made available to the New Jersey Office of the State Comptroller or other State audit agency upon request and at no cost to the State.

- 13.3.2 The Contractor shall maintain all documentation related to products, transactions or services under this contract for a period of five years from the date of final payment. Such records shall be made available to the New Jersey Office of the State Comptroller or other State audit agency upon request and at no cost to the State.
- 13.3.2 The Contractor shall develop, maintain and make available to the DPMC on request such schedule of quantities and costs, progress schedules, payrolls, reports, estimates, Change Orders, all original estimates, takeoffs and other bidding documents, all Subcontractor and supplier Contracts and changes, all records showing all costs and liabilities incurred or to be incurred in connection with the Project (including all Subcontractor and supplier costs), all payment records and all records showing all costs incurred in labor and personnel of any kind, records and other data as the State may request concerning work performed or to be performed under this Contract.
- 13.3.3 The Contractor acknowledges and agrees that no claim for payment which is premised to any degree upon actual costs of the Contractor shall be recognized or payable by the State except and to the extent that such actual costs are substantiated by records required to be maintained under these provisions.
- 13.3.4 The Contractor acknowledges and agrees that its obligation to establish, maintain and make available records and the State's right to audit as delineated herein shall extend to actual costs incurred by Subcontractors in performing work required under the Contract Documents. The Contractor shall require in each subcontract that the Subcontractor establish, maintain and make available to the State all records as defined and delineated herein, relating to all work performed under the Subcontractor including work performed by a sub-Subcontractor.

13.4 INSURANCE

13.4.1 Insurance To Be Carried By The Contractor:

The Contractor shall obtain and maintain, at its expense and for the duration of the contract, minimum insurance coverage set forth below. By requiring such minimum insurance, the State of New Jersey shall not be deemed or construed to have assessed the risk that may be applicable to the Contractor under this contract. The Contractor shall assess its own risks and if it deems appropriate and/or prudent, maintain higher limits and/or broader coverage. The Contractor is not relieved of any liability or other obligations assumed or pursuant to the Contract by reason of its failure to obtain or maintain insurance in sufficient amounts, duration or types.

- a Commercial General Liability:
 - (1) Commercial General Liability (CGL)-ISO occurrence form CG001 or a substitute form providing a minimum coverage of \$2,000,000 per occurrence for bodily injury liability and \$2,000,000 per occurrence for property damage liability and shall cover liability arising from:
 - Premises/Operations

- Independent Contractors
- Products/Completed Operations
- Personal and Advertising Injury
- Liability assumed under an insured contract (including defense cost assumed)
- (2) The State of New Jersey shall be included as an additional insured under the CGL using ISO additional insured endorsement CG 20 10 and CG 20 37 or a substitute providing equivalent coverage, which endorsement shall include coverage for the State of New Jersey arising out of the completed operations of the contractor, and which coverage shall be maintained in effect for the benefit of the State of New Jersey for a period of three (3) years following the completion of the work specified in section 7.3 of this contract. Additional Insured coverage as required in this subparagraph shall apply as primary insurance with respect to any other insurance or self-insurance programs afforded to the State of New Jersey.
- (3) The CGL general aggregate shall apply separately to this project using ISO CG 2503 form designated construction projects(s) General Aggregate Limit.
- (4) There shall be no endorsement or modification of the CGL limiting the scope of coverage for liability arising from explosion, collapse or underground property damage.
- (5) If not included in the policy form the CGL policy must be endorsed with a separation of insureds (severability of interests) endorsement.
- (6) CGL policy must provide or be endorsed (ISO form CG 24 04) to provide for waiver of subrogation.

b Business Automobile Liability:

- (1) Contractor and subcontractors shall maintain business auto liability insurance and such insurance shall cover liability arising out of any auto (including owned, hired and non-owned autos).
- (2) The limits of liability shall be not less than \$1,000,000 per occurrence for both bodily injury and property damage liability.
- (3) Business Automobile coverage shall be written on ISO form CA 00 01 or a substitute form providing equivalent liability coverage. If necessary, the policy shall be endorsed to provide contractual liability coverage equivalent to that provided in the 1990 and later additions of CA 00 01.
- (4) If required by law, the business auto policy shall be endorsed to provide pollution liability coverage equivalent to that provided under the ISO pollution liability broadened coverage for covered autos form

- CA 99 48 and the Motor Carrier Act endorsement (MCS 90) shall be attached.
- (5) Waiver of Subrogation -- Contractor waives all rights against the State of New Jersey for recovery of damages to the extent these damages are covered by the business auto liability insurance obtained by Contractor pursuant to Paragraph 2.0 of this Agreement.
- c Workers Compensation: Workers Compensation Insurance applicable to the laws of the State of New Jersey and other State or Federal jurisdiction is required to protect the employees of the Contractor or any Subcontractor who will be engaged in the performance of this Contract. This insurance shall include employers' liability protection with a limit of liability not less than \$500,000.
- d Umbrella Liability: Contractor must maintain an Umbrella Liability Policy excess of the Commercial General Liability, Automobile Liability and Employer Liability coverage.
 - (1) The coverages of the umbrella policy must be as broad as the primary policies covered by this policy and include a "drop-down" provision if the primary coverage becomes impaired or exhausted.

13.4.2 Insurance To Be Carried By The State of New Jersey:


- a Builders Risk Insurance: Unless otherwise provided in this agreement the State of New Jersey shall provide and maintain, in a company or companies lawfully authorized to do business in the jurisdiction which this project is located, Builders Risk Insurance in the amount of the initial contract amount as well as subsequent modifications for the entire project at the site on a replacement cost basis.
 - (1) The Builders Risk coverage shall be on an "All Risk of direct physical loss or damage" or equivalent policy form and include theft, earthquake, flood, temporary structures, demolition and increased cost of construction, architects fees and expenses.
 - Also the insurance must include coverage for Equipment Breakdown Coverage (a.k.a. Boiler & Machinery) which shall cover insured Equipment during installation and testing. The Builders Risk insurance shall include the interest of the State of New Jersey, the general Contractor, subcontractors and sub-tier contractors in the project.
 - (2) The Builders Risk Policy shall cover all materials equipment and supplies, assemblies and furnishings intended for specific installation in the project while located at the site. The policy will cover portions of the work off site and portions of the work in transit subject to the policy sub-limits for these coverages.
 - (3) Waivers of Subrogation -- The State of New Jersey and Contractor waive all rights against (1) each other and any of their subcontractors, sub-subcontractors, agents and employees and (2) the

- Architect/Engineer, Architect/Engineer's Consultants, and any of their subcontractors, Sub-subcontractors, agents and employees for damages caused by fire or other causes of loss to the extent covered by the Builders Risk insurance or any other property insurance applicable to the work.
- (4) The Builders Risk policy will provide for a waiver of subrogation against all interested parties covered by the policy but only to the extent the loss is covered by the policy.
- (5) The above insurance shall apply only to the work described in this contract, and shall not apply to alterations, repairs, maintenance and installations of systems, equipment and other items of work which do not result in creating additional habitable space. This insurance shall not protect against damage or loss to any of the Contractor's or Subcontractor's tools, equipment, scaffolding, staging towers or forms and Contractor's materials stored on Site which are not part of the construction Project,. It is understood that the Contractor will, at its own expense, carry all insurance which may be required to provide the necessary protection against such loss or damage herein described which shall contain a waiver of any right of subrogation against the State of New Jersey.
- (6) Deductible Provisions -- The insurance protection described herein may contain a deductible clause. The State of New Jersey agrees to bear the cost of all deductibles of the Builders Risk Policy.
- (7) Loss Reporting and Loss Adjustment The Contractor will receive a Loss Reporting Form whenever Builders' Risk Insurance is written. This form includes appropriate loss reporting instructions. In the event of loss, the Contractor shall immediately notify the State of New Jersey, DPMC, in writing, and take any other appropriate steps as may be required under the standard builders' risk insurance policy in effect. Upon the occurrence of any loss or damage prior to the acceptance of the building by the State, the Contractor shall, at the State's option, replace and repair the damaged work as originally provided in the drawings and specifications at no additional compensation to that provided in the original Contract.
- (8) Status Trustee for Loss Adjustment -- All losses will be adjusted with, and payable to, the State of New Jersey, as trustee for the insured as their interests may appear. The Contractor shall be named jointly with the State in all policies of insurance, all of which shall be open to inspection by the State.
- (9) This provision shall not relieve the Contractor from its obligation to complete, according to plans and specifications, the Project covered by the Contract, and the Contractor and its surety shall be obligated to full performance of the Contractor's undertaking.

13.5 ASSIGNMENT OF ANTITRUST CLAIMS

- 13.5.1 The Contractor recognizes that in actual economic practice, overcharges resulting from antitrust violations are in fact usually borne by the ultimate purchaser. Therefore, and as consideration for executing this Contract, the Contractor, acting herein by and through its duly authorized agent, hereby conveys, sells, assigns, and transfers to the State of New Jersey, for itself and on behalf of its political subdivisions, instrumentalities, and public agencies, all right, title and interest to all claims and causes of action it may now or hereafter acquire under the antitrust laws of the United States or the State of New Jersey, relating to the particular goods or services purchased or acquired by the State of New Jersey or any of its political subdivisions or public agencies pursuant to this Contract.
- 13.5.2 In connection with this assignment, the following are the express obligations of the Contractor:
 - a. The Contractor will take no action which will in any way diminish the value of the rights conveyed or assigned hereunder.
 - b. The Contractor will advise the Attorney General of New Jersey and DPMC:
 - (1) in advance of its intention to commence any action on its own behalf regarding any such claim or cause(s) of action; and/or
 - (2) immediately upon becoming aware of the fact that an action has been commenced on its behalf by some other person(s) of the tendency of such action.
 - c. The Contractor will notify the defendants in any antitrust suit of the fact of the within assignment at the earliest practicable opportunity after the Contractor has initiated an action on its own behalf or becomes aware that such an action has been filed on its behalf by another person. A copy of such Notice will be sent to the Attorney General of New Jersey and the DPMC.
- 13.5.3 It is understood and agreed that in the event any payment under any such claim or cause of action is made to the Contractor, it shall promptly pay over to the State of New Jersey the allotted share thereof, if any, assigned to the State hereunder.

END, GENERAL CONDITIONS



SUMMARY

PART 1 - GENERAL

1.1 SCOPE OF WORK

- A. The Scope of this Project is for the demolition of abandoned buildings and includes:
 - 1. Vermin Control
 - 2. Soil Erosion Controls
 - 3. Site Protection
 - 4. Building Demolition
 - 5. Demolition of Site Improvements
 - 6. Excavation, Backfilling, and Grading
 - 7. Removal and Reuse / Recycle / Disposal of Site Debris
 - 8. Removal and Reuse / Recycle / Disposal of Demolition Debris
 - 9. ACM Abatement
 - 10. Termination and removal of water and sewer services

1.2 MARKOUT SERVICES

A. Prior to any onsite or off site activity contact New Jersey Dig (1-800-272-1000) for a buried utility markout survey. If the survey should expire, or markings become illegible, contractors requiring excavation as part of their work shall be responsible for arranging a new survey.

1.3 SITE PROTECTION

- A. Confine operations to those areas designated on the drawings.
- B. Do not interfere with, impair, or prevent the use, maintenance and operations of the adjoining roads, curbs, sidewalks, structures, lands, and public use areas.
- C. Repair all damage to the adjoining structures, roads, curbs, sidewalks, structures, lands, and public use areas as a result of operations under this contract. Clean adjacent structures and improvements of dust, dirt, and debris caused by the demolition operations.

1.4 WARRANTIES

A. The Contractor warrants to the State and Architect / Engineer that the new turf will be established within one year of Substantial Completion. If new turf is not established within the one year period, the Contractor shall replace any planting which have not established themselves with one year of acceptance of the planting.

PART 2 – MATERIALS (NOT USED)

PART 3 – EXECUTION (NOT USED)

END OF SECTION

SUMMARY 011100-1

ALLOWANCES

PART 1 - GENERAL

1.1 SUMMARY

A. This Section includes administrative and procedural requirements for Allowances.

1.2 DEFINITIONS

A. Allowances is an amount established in the contract documents for inclusion in the contract sum to cover the cost of prescribed items not specified in detail, with provisions for variations between such amount and the finally determined cost of the prescribed items.

1.3 PROCEDURES

- A. Allowances have been established and are described herein. Materials or equipment furnished or installed or provided for work done under an Allowance shall be at the direction and authorization of the Engineer. The amounts of the Allowances stipulated are estimates only; payments under Allowances will be the actual cost of furnishing or installing or providing the Work included in the Allowance.
- B. Include the amounts stipulated herein for the Allowances in the Lump Sum Price bid for the Contract. The Lump Sum Price bid for the Contract will be decreased by the amount that the actual cost of the Allowance differs from the Allowance stipulated.
- C. For each Allowance, submit a cost estimate for the Work based on a list of required work stipulated by the Engineer. The estimate shall detail the equipment or material cost of each item provided under the Allowance, the cost for installing the equipment or material, and the overhead and profit associated with this work. The estimate shall accurately reflect the material and labor costs required for installing the equipment or materials, and shall not include work required under the base bid.

PART 2 - MATERIALS (Not Used)

PART 3 - EXECUTION

3.1 LIST OF ALLOWANCES

A. Allowance #1 –None

END OF SECTION

ADMINISTRATIVE REQUIREMENTS

PART 1 – GENERAL

1.1 PROJECT MEETINGS

A. Construction Progress Meetings will be held at the Project site on a as needed basis.

PART 2 – MATERIALS (NOT USED)

PART 3 – EXECUTION (NOT USED)

END OF SECTION

CONSTRUCTION SEQUENCE

PART 1 – GENERAL

1.1 CONTRACT COMPLETION

A. The work under this Contract shall be completed within 65 calendar days from the date of the Notice to Proceed.

1.2 PROJECT SEQUENCE

A. Submit a project sequence for all the tasks, including hazardous building materials abatement, in the scope of work within four (4) calendar days of the Notice to Proceed for review and approval.

PART 2 – MATERIALS (NOT USED)

PART 3 – EXECUTION (NOT USED)

END OF SECTION

REGULATORY COMPLIANCE

PART 1 - GENERAL

1.1 REGULATORY COMPLIANCE

- A. The Contractor is solely responsible for all site safety.
- B. Inspect and assure compliance with all statutory requirements for worker protection and safety. Provide, inspect, and assure that all workers utilize appropriate worker protective and safety gear.
- C. Instruct workers and inspectors in the proper use of all protective and safety equipment.
- D. All safety equipment shall be OSHA approved.

1.2 CODES AND STANDARDS

A. New Jersey Uniform Construction Code: The work described by these Contract Documents shall be accomplished in strict accordance with the New Jersey Uniform Construction Code and in full compliance with the following Subcodes and Standards as applicable:

INTERNATIONAL BUILDING CODE, NEW JERSEY EDITION 2015 NATIONAL PLUMBING CODE NJAC 5:23-8 ASBESTOS HAZARD ABATEMENT SUBCODE

- B. Asbestos Abatement Standards: Accomplish the work described by these Contract Documents in strict accordance and in full compliance with the Federal and State Standards specified in Section 020590.
- Comply with applicable regulations and standards for traffic control and sewer and water terminations.

1.3 PERMITS

- A. Asbestos Abatement Permit: The Licensed Asbestos Abatement Contractor shall obtain and pay for all permits and pay all associated fees, including any bonds that may be required.
- B. U.C.C. Construction (Demolition) Permits will be issued after:
 - 1. All asbestos abatement work is completed and the abatement certification and final clearance air sampling results are submitted in accordance with Section 020590.
 - 2. Sewer and water terminations shall been completed under this Contract and termination letters shall be issued by the utility owner / operator.
 - 4. Vermin eradication is completed and a certification submitted.
 - 3. There will be no costs to the Contractor for U.C.C. Construction (Demolition) Permits.
- C. Sewer and Water Terminations: Pay all associated fees that may be required by the utility owner / operator.
- D. Soil Erosion and Sediment Control Permits will be obtained by the Owner.

1.4 INSPECTIONS

- A. Inspections: Construction demolition inspections will be provided by DCA Code Inspection Group and will be coordinated through the DPMC, Office of Construction Services Construction Manager. Conduct all testing required by the Inspectors and Code.
- B. Sewer and water terminations shall be inspected by the utility owner / operator.

PART 2 – MATERIALS (NOT USED)

PART 3 – EXECUTION (NOT USED)

TESTING AND INSPECTION SERVICES

PART 1 – GENERAL

- 1.1 TESTING AGENCY
 - A. Engage and pay for an independent testing agency(s), acceptable to the DPMC, to conduct all testing and inspection services listed below.
- 1.2 SPECIAL TESTING AND INSPECTIONS
 - A. Compaction testing as specified in Section 312300.
 - B. Environmental testing as specified in Sections 020590 and 020700.

PART 2 – MATERIALS (NOT USED)

PART 3 – EXECUTION (NOT USED)

TEMPORARY UTILITIES

PART 1 - GENERAL

1.1 SUMMARY

A. This section includes the requirements for temporary utilities. There are no active utilities available at the work locations. Installation and removal of and use charges for temporary utilities shall be included in the lump sum price bid unless otherwise indicated. Upon completion of the work, remove the temporary utilities. Arrange with utility company as necessary for any required temporary utilities.

1.2 PHONE SERVICE

A. Provide a working cellular telephone on site.

1.3 TEMPORARY WATER

A. Provide water service if water is required for the performance of the work. Provide connections and extensions of services as required for construction operations.

1.4 TEMPORARY ELECTRICAL POWER

A. Provide portable generators if power is required for the performance of the work. Comply with NECA, NEMA, and UL standards and regulations for temporary electric service.

1.5 TEMPORARY LIGHTING

A. Provide temporary lighting within the building work area that provides adequate illumination for construction operations, observations, inspections, and traffic conditions.

PART 2 – MATERIALS (NOT USED)

PART 3 – EXECUTION (NOT USED)

TRAFFIC CONTROLS

PART 1 – GENERAL

1.1 TRAFFIC CONTROL DEVICES

- A. Provide, install and maintain traffic control devices as required by the municipality, County, or State in accordance with Section 159 of the NJDOT Standard Specification. Obtain approvals from the municipality, County, or State for any required traffic control operations.
- B. Contractor is responsible for maintaining flow of traffic and shall direct traffic, as necessary.

1.2 VEHICLES

- A. Vehicle, truck, and equipment access:
 - 1. Avoid traffic conflicts with the public. Do not block the public roads.
 - 2. Protect adjacent building surfaces and the site from vehicles and equipment.
 - 3. Confine all vehicles and equipment to the paved road surfaces and stabilized soil surfaces.

PART 2 – MATERIALS (NOT USED)

PART 3 – EXECUTION (NOT USED)

TEMPORARY FENCING

PART 1 - GENERAL

1.1 PROTECTIVE BARRIERS AND SIGNAGE

- A. No public access shall be allowed on the site of work until the property is restored and accepted by the State. Enclose the site and maintain protective fencing and barriers during all work to prevent public access. Provide all specified and necessary signage to inform and restrict public access.
- B. Protective barriers to restrict access to the construction site shall be temporary 6' high chain link fencing properly supported on steel posts. Provide access as required for the construction operations. Secure all fencing at the end of each work day. Install all temporary fences on all properties before any work takes place. Fencing shall remain until all final backfilling and compaction is completed on each property.

1.2 DAMAGE TO PROPERTY

A. Without expense to the Owner, restore to its original condition any adjacent property that has been damaged due to the negligence and/or work of the Contractor's agents, employees or subcontractors. Complete all such repairs to the satisfaction of the Engineer.

PART 2 – MATERIALS (NOT USED)

PART 3 – EXECUTION (NOT USED)

PRODUCT REQUIREMENTS

PART 1 - GENERAL

1.1 SUBMITTAL PROCEDURES

- A. Make all submittals within four (4) calendar days of the Notice to Proceed in accordance with the attached submittal log. All submittals are to be made in electronic format.
- B. DPMC 12/13: This form is to be used for submission for approval of all subcontractor(s), materials to be utilized in the construction, manufacturers/suppliers and for Professional Services. Complete the Contractor Section as follows:
 - Submission Type: Place a check mark in the appropriate block(s) that applies to the submission.
 - 2. *Trade:* Place a check mark in the appropriate block that identifies the trade related to the submission.
 - 3. *Contractor Name:* The Prime Contractor submitting the form inserts his company name in the space indicated.
 - 4. **Description of Submittal:** Include a brief description of the submittal.
 - 5. *General Condition, Specification or Drawing section*: Identify the Article, Spec Section or Drawing that represents the submission type, i.e., Article 4.11.2 Sleeve & Opening Drawing, Spec Section 115575 Condensate Pump, Drawing FP2.2 Ames Backflow Preventer.
 - 6. **Vendor/Manufacturer/Supplier/Subcontractor:** Insert the name, address, and telephone number of the vendor/manufacturer/supplier or subcontractor for which he is requesting approval. (When required, insert the license number and registration number in the space provided, attach a copy of said license and certification.)

1.2 SUBSTITUTIONS

A. Submit proposed substitutions within four (4) calendar days from the Notice to Proceed; after that time has expired no substitutions will be considered by the State. Substitution submittals that are incomplete will be rejected.

PART 2 – MATERIALS (NOT USED)

PART 3 – EXECUTION (NOT USED)

CLOSEOUT SUBMITTALS

PART 1 – GENERAL

1.1 CLOSE-OUT DOCUMENTS

- A. At the completion of construction provide an electronic submittal containing the following documents, with the exception of the Consent of Surety for which an original copy with a raised seal must be submitted.
 - 1. Waste Manifests
 - 2. Recycling Receipts
 - 3. Test Reports
 - 4. Asbestos Abatement Closeout Documents
 - 5. DPMC-20, Final Contract Acceptance
 - 6. DPMC-11, DPMC Invoice (marked final)
 - 7. DPMC-11-2a, Certification of Prime Contractor
 - 8. DPMC-20r(2), Consent of Surety to Final Payment (ORIGINAL)
 - 9. DPMC-20d, Certificate of Substantial Completion
 - 10. Contractor Warranty Letter

PART 2 – MATERIALS (NOT USED)

PART 3 – EXECUTION (NOT USED)

REMOVAL OF ASBESTOS MATERIALS

PART 1 - GENERAL

1.1 SUMMARY

A. Applicable Properties:

ID	Address	Municipality	Lot	Block
1	640 Bamford Avenue	Woodbridge Twp.	503	563.03
2	576 Bamford Avenue	Woodbridge Twp.	633	563.08
3	88 Claire Avenue	Woodbridge Twp.	5	563.39
4	122 Harriot Street	Woodbridge Twp.	123	551.04
5	661 Lewis Street	Woodbridge Twp.	19	589
6	675 Lewis Street	Woodbridge Twp.	15	589
7	679 Lewis Street	Woodbridge Twp.	14	589
8	82 Port Reading Avenue	Woodbridge Twp.	505	563.03
9	88 Port Reading Avenue	Woodbridge Twp.	507	563.03
10	7 Wedgewood Avenue	Woodbridge Twp.	32.01	590

B. Scope of work: The applicable residential buildings listed above have been surveyed and tested for the presence of asbestos containing materials (ACM). ACM were found to be present at each of the above residences. Refer to Appendix B for asbestos testing and analysis data. ACM identified must be removed by a New Jersey Licensed Asbestos Abatement Contractor prior to demolition.

1.2 DESCRIPTION OF WORK

A. The Asbestos Abatement Contractor shall supply all labor, materials, services and equipment required to complete the work in accordance with all applicable federal, state, and local regulations and guidelines. The estimated location, materials, and quantities for asbestos abatement and disposal are included on the following tables:

Approximate Quantities and Locations Asbestos-Containing Materials (ACM)

640 Bamford Avenue - Residence					
Floor	Location	Material	Quantity		
1st Floor	Dining Room	Cream Mottled Sheet Flooring Under Luan ¹	176	SF	
1 st Floor	Entrance Vestibule (Under Carpet)	9"x9" Tan Floor tile with Grey and Red Mottled Pattern	40	SF	
2 nd Floor	Rear Sun Room	1'x1' Tan and Grey Stone Pattern Floor Tile and Backing	140	SF	
Basement	Basement Flue	Grey Flue Cement – Abandoned – Type 1	2	SF	

¹ Multi-layered flooring and subfloor(s)

_

640 Bamford Avenue - Residence					
Floor	Location	Material	Quantity	y	
Exterior	Chimney	Black Tar Flashing at Chimney	10	SF	
Exterior	Basement Window	Grey Exterior Window Caulk – Basement	1 (16 LF Per)	UN	
Exterior	Basement Window	White Exterior Window Glazing – Basement	1 (24 LF Per)	UN	
Exterior	Throughout	White Exterior Window Caulk Under Metal Casing	24 (16 LF Per)	UN	

640 Bamford Avenue - Garage					
Floor	Location	Material	Quantity	Y	
Exterior	Interface of Wall and Clapboard Siding	Grey Exterior Caulk at Interface of Wall and Clapboard	90	LF	

576 Bamford Avenue - Residence				
Floor	Location	Material	Quantity	
2 nd Floor	Left Bedroom	Brown Glue Dots Associated with 1'x1' White Ceiling Tile with Grey Mottled Pattern	182	SF
1 st Floor	Kitchen	Yellow Floor Tile (Unknown Size) Under Sheet Flooring (Middle Layer) ²	180	SF
1 st Floor	Kitchen	White Floor Tile (Unknown Size) Under Sheet Flooring (Middle Layer) ²	180	SF
1 st Floor	Kitchen	Off-White and Grey Mottled Pattern Sheet Flooring ²	180	SF
Exterior	Chimney	Black Tar Flashing at Chimney	10	SF

88 Claire Avenue - Residence					
Floor	Location	Material	Quantity	y	
1 st Floor	Dining Room	Black Mastic Associated with Grey Resilient Flooring ²	110	SF	
1 st Floor	Dining Room	Grey Resilient Flooring Under 9" Orange/Brown Floor Tile ²	110	SF	
1 st Floor 2 nd Floor	Dining Room Bathroom & Closets	9"x9" Orange/Brown Mottled Pattern Floor Tile ²	182	SF	

² Multi-layered flooring and subfloor(s)

_

88 Claire Avenue - Residence				
Floor	Location	Material	Quantity	V
Basement	Throughout	9"x9" Chocolate Floor Tile with Orange and Tan Streaks	525	SF
Basement	Throughout	Black Mastic Associated with 9" Chocolate Floor Tile	525	SF
Basement 1 st Floor 2 nd Floor	Throughout	Tan Paper Duct Insulation	150	LF
Basement	Right Bar Room	Grey Paper Light Pad Insulation	1	SF
2 nd Floor	Hallway, Left Bedroom, Right Bedroom	9"x9" Grey and Tan Mottled Pattern Floor Tile	350	SF
1 st Floor	Dining Room (Front Left Room)	Grey Adhesive Associated with Removed Ceramic Wall Tile – Under Wood Paneling	120	SF
Exterior	Vent and Chimney	Black Tar Flashing at Chimney and Vent (Bottom Layer)	10	SF

88 Claire Avenue - Garage					
Floor	Location	Material	Quantity	y	
1 st Floor	Behind Wall – Shop to Garage	Tan Exterior Window Glazing – Covered Window	1 (24 LF Per)	UN	
1 st Floor	Shop	9"x9" Chocolate Floor Tile with Orange and Tan Streaks	288	SF	

122 Harriot Street – Residence					
Floor	Location	Material	Quantity	у	
Stairwell	Stairwell Landing, Basement to First Floor	Tan Stone Pattern Sheet Flooring	36	SF	
Stairwell	Stairwell, Basement to First Floor	Cream Mottled Pattern Stair Tread/Riser	36	SF	
Exterior	Vent and Chimney	Black Tar Flashing at Vents and Chimney	10	SF	
Exterior	Siding (Under Vinyl)	Cementitious Siding Shingle (Transite)	1,550	SF	

661 Lewis Street– Residence					
Floor	Location	Material	Quantity		
1 st Floor	Kitchen	Tan Resilient Flooring Under Plywood Subfloor ³	130	SF	
1 st Floor	Bathroom	Yellow, Tan and Brown Geometric Pattern Sheet Flooring (Layer 3) ⁴	30	SF	
1 st Floor	Sun Room	9"x9" Pink Floor Tile with Red and Grey Specks ⁵	140	SF	
1 st Floor	Bathroom	Brown Adhesive Associated Wall Paneling	90	SF	
Exterior	Vents and Chimney	Black Tar Roof Flashing at Vents and Chimney	10	SF	
Exterior	Siding	Cementitious Siding Shingle (Transite)	1,500	SF	

675 Lewis Street– Residence					
Floor	Location	Material	Quantity	Y	
Exterior	Front Door Side Door	White Exterior Door Caulk at Interface of Brick and Metal Casing – Type 2	2 (21 LF Per)	UN	
Exterior	Driveway to Building Interface	Dark Grey Exterior Tar Sealant (Remnant) at 1st Course of Brick	30	LF	

679 Lewis Street– Residence					
Floor	Location	Material	Quantity		
1 st Floor	Kitchen (Multi-Layered Covered with Subfloor and Ceramic)	Off-White Sheet Flooring with Gold Flecks (Bottom Layer)	160	SF	
1 st Floor	Kitchen (Multi-Layered Covered with Subfloor and Ceramic)	Brown and Tan Square Pattern Sheet Flooring (Middle Layer)	160	SF	
1 st Floor	Kitchen (Multi-Layered Covered with Subfloor and Ceramic)	Off-White 1'x1' Pattern Sheet Flooring	160	SF	
1 st Floor	In Wall at Supply Diffusers	Grey Paper Duct Insulation	32	SF	
Basement	Boiler	Corrugated Paper Boiler / Furnace Lining	48	SF	
Basement	Basement Flue	White Flue Cement	8	SF	

Multi-layered flooring and subfloor(s) under ceramic
 Multi-layered flooring and subfloor(s)
 Under Carpet

679 Lewis Street- Residence				
Floor	Location	Material	Quantity	y
Exterior	Throughout	White Exterior Door/Window Caulk (Remnants) Under Metal Casing	18 (24 LF Per)	UN

82 Port Reading Avenue - Residence				
Floor	Location	Material	Quantity	У
Basement	Basement Flue	Grey Flue Cement – Off Boiler	2	SF
Basement	Basement Flue	Cementitious Boiler Rib Packing	25	SF
Exterior – Basement, 1st Floor, 2nd Floor	Windows	White Exterior Window Caulk – Original Construction	18 (16 LF Per)	UN
Exterior – Basement, 1st Floor, 2nd Floor	Windows	White Exterior Window Glazing – Original Construction	18 (24 LF Per)	UN
Exterior	Rear Addition Windows	White Exterior Window Glazing – Rear Addition	2 (24 LF Per)	UN
Exterior	Siding Gables, Dormers, Rear Porch	Multi-Colored Mineral Coat Siding Shingle	340	SF
Exterior	Vents & Chimney	Black Tar Flashing / Sealant at Roof Vents and Chimney	10	SF
Exterior	Foundation Wall	Black Tar Vapor Barrier Over Exterior Foundation (Below Grade)	570	SF
Exterior	Siding	Cementitious Siding Shingle (Transite)	140	SF
Basement	Basement (Accessible and	Corrugated Paper Pipe and Cementitious Fitting Insulation	15	LF

82 Port Reading Avenue - Garage				
Floor	Location	Material	Quantity	y
Exterior	Windows	White Exterior Window Glazing	2 (24 LF Per)	UN

88 Port Reading Avenue – Residence				
Floor Location Material Quantity				y
Exterior	Windows	White Exterior Window Caulk – Original	20 (16 LF Per)	UN

88 Port Reading Avenue – Residence				
Floor	Location	Material	Quantity	y
Lower Level	Throughout – Wall Behind Substrate	Black Tar Vapor Barrier on Interior Foundation Wall Behind Wood Paneling/Walls	480	SF

7 Wedgewood Avenue – Residence				
Floor	Location	Material	Quantity	y
1 st Floor	Entry Vestibule/Sun Room	Grey Floor Tile Under Plywood and Sheet Flooring ⁶	140	SF
1 st Floor	Mud Room, Rear Pantry, Stairwell To Basement	Light Tan Floor Tile Over Plywood Subfloor Under Sheet Flooring (Layer 3) 7	120	SF

7 Wedgewood Avenue – Garage				
Floor	Location	Material	Quantity	y
Exterior	Gables	White Sealant at Vinyl Siding to Stucco Façade Seams	30	LF

B. General Notes

- 1. SF Square Feet; LF Linear Feet; UN Number of Units
- 2. Erect critical barriers, as required, to seal each work area.
- 3. There are no utilities at the sites. Provide water and electricity and all lines, hoses and connections between source and work area to perform asbestos abatement in accordance with the requirements of this Specification.
- 4. Upon successful completion of post abatement air testing, the Asbestos Abatement Contractor shall remove all abatement materials and equipment.
- 5. In accordance with the EPA NESHAP Clarification on sampling of wallboard systems, in some instances the sample of the wallboard system (e.g. all components including the drywall, tape and joint compound) is analyzed as one composite sample. In these cases, there may be trace or low concentrations of asbestos below 1%. The material is considered non-ACM by EPA NESHAP, but OSHA worker protection compliance is required. Refer to the Demolition Section of the Specifications for additional information. The complete analytical data package is attached as Appendix B.

Properties with Composite Sample Analysis of Wallboard System (<1% Asbestos)		
Property	Building	
88 Port Reading Avenue	Residence	
679 Lewis Street	Residence	

1.3 DEFINITIONS

A. <u>ACM</u> - Asbestos Containing Materials. All materials and products that contain more than 1 percent asbestos.

⁶ Multi-layered flooring and subfloor(s) under ceramic

⁷ Multi-layered flooring and subfloor(s)

- B. <u>Amended Water</u> Water containing a wetting agent or surfactant with a maximum surface tension of 2.9 Pa (29 dynes per square centimeter) when tested according to ASTM D 1331.
- C. <u>Area Sampling</u> Sampling of asbestos fiber concentrations which approximates the concentrations of asbestos in the theoretical breathing zone but is not actually collected in the breathing zone of an employee.
- D. <u>Asbestos</u> The term asbestos includes Chrysotile, amosite, crocidolite, tremolite, asbestos, anthophyllite asbestos, and actinolite asbestos and any of these minerals that have been chemically treated or altered. Materials are considered to contain asbestos if the asbestos content of the material is determined to be at least one percent.
- E. <u>Asbestos Control Area</u> That area where asbestos removal operations are performed which is isolated by physical boundaries, which assist in the prevention of the uncontrolled release of asbestos dust, fibers, or debris
- F. <u>Asbestos Fibers</u> Those fibers having an aspect ratio of at least 3:1 and longer than 5 micrometers as determined by National Institute for Occupational Safety and Health (NIOSH) Method 7400.
- G. <u>Asbestos Permissible Exposure Limit (PEL)</u> 0.1 fibers per cubic centimeter of air as an 8-hour time weighted average measured in the breathing zone as defined by 29 CFR 1926.1101 or other Federal legislation having legal jurisdiction for the protection of workers health.
- H. <u>Background</u> The ambient airborne asbestos concentration in an uncontaminated area as measured before any asbestos hazard abatement efforts. Background concentrations for other (contaminated) areas are measured in similar but asbestos free locations
- I. <u>Contractor / Asbestos Abatement Contractor -</u> The Contractor is that individual, or entity under contract to the Department to perform the herein listed work.
- J. <u>Department</u> New Jersey Division of Property Management and Construction.
- K. <u>Encapsulation</u> The abatement of an asbestos hazard through the appropriate use of chemical encapsulants.
- L. <u>Encapsulants</u> Specific materials in various forms used to chemically or physically entrap asbestos fibers in various configurations to prevent these fibers from becoming airborne. There are four types of encapsulants as follows which must comply with performance requirements as specified herein.
 - 1. Removal Encapsulant (can be used as a wetting agent)
 - 2. Lock-Down Encapsulant (used to seal off or "lock-down" minute asbestos fibers left on surfaces from which asbestos containing material has been removed).
- M. <u>Friable Asbestos Material</u> Any material greater than one percent asbestos that, when dry, can be crumbled, pulverized, or reduced to powder by hand pressure when dry.
- N. <u>HEPA Filter Equipment</u> High efficiency particulate air (HEPA) filtered vacuum and/or exhaust ventilation equipment with a filter system capable of collecting and retaining asbestos fibers. Ensure filters retain 99.97 percent of particles 0.3 microns or larger as indicated in UL 586.
- O. <u>Negative Pressure Enclosure (NPE)</u> That engineering control technique described as a negative pressure enclosure in 29 CFR 1926.1101.

- P. <u>Non-friable Asbestos Material</u> Any material that contains more than one percent asbestos in which the fibers have been immobilized by a bonding agent, coating, binder, or other material so that the asbestos is well bound and will not normally release asbestos fibers during any appropriate use, handling, storage or transportation. Non-friable materials are defined as either:
 - 1. Category I means asbestos containing packing, gaskets, resilient floor coverings and asphalt roofing products.
 - 2. Category II any material, excluding Category I non-friable ACM, containing more than one percent asbestos such as transite, galbestos and window caulking.
- Q. <u>PACM</u> Presumed Asbestos Containing Material
- R. <u>Powered Air Purifying Respirator (PAPR)</u> A positive-pressure respirator which employs a portable, rechargeable battery pack and blower to force air from the work area through a HEPA filter cartridge, where the air is cleaned and supplied to the wearer's breathing zone.
- S. <u>Personal Sampling</u> Air sampling which is performed to determine asbestos fiber concentrations within the breathing zone of a specific employee, as performed according to 29 CFR 1926.1101.
- T. Qualified Person (QP) That qualified person hired by the Contractor to perform the required contractor's tasks, who has successfully completed training and is therefore accredited under a legitimate State Model Accreditation Plan as described in 40 CFR 763 as a Building Inspector, Contractor/Supervisor Abatement Worker, and Asbestos Project Designer; and has successfully completed the National Institute of Occupational Safety and Health (NIOSH) 582 course "Sampling and Evaluating Airborne Asbestos Dust" or equivalent. The QP must be qualified to perform visual inspections as indicated in ASTM E 1368. Ensure the QP is appropriately licensed in the State of New Jersey.
- U. <u>Regulated ACM</u> Friable asbestos containing material, category I non-friable ACM that has become friable, Category I non-friable ACM that will be or has been subject to sanding, grinding, cutting, or abrading, or Category II non-friable ACM that has a high probability of becoming or has become crumbled, pulverized, or reduced to powder by the forces expected to act on the material in the course of demolition or renovation operations regulated by NESHAP.
- V. <u>Time Weighted Average (TWA)</u> The TWA is an 8-hour time weighted average airborne concentration of asbestos fibers.
- W. Wetting Agent A chemical added to water to reduce the water's surface tension thereby increasing the water's ability to soak into the material to which it is applied. An equivalent wetting agent must have a surface tension of at most 2.9 Pa (29 dynes per square centimeter) when tested according to ASTM D 1331.

1.4 PERMITS AND FEES

A. Obtain any required project permits and pay all associated fees, including any bonds that may be required.

1.5 CODES AND REGULATIONS

- A. This sub section covers the governmental regulations and industry standards that shall be adhered to during this project. These regulations and standards are the minimal requirements for this project; therefore, if the contract documents indicate procedures that are stricter, the contract documents shall govern.
- B. It is the Contractor's full responsibility to comply with all applicable federal, state and local regulations governing asbestos abatement work practices, including hauling and disposal of waste

and protection of workers, visitors, and persons occupying project and adjacent areas. The Contractor is responsible for providing medical examinations and maintaining medical records of his personnel as required by the applicable federal, state, and local regulations.

- C. Federal Regulations that govern asbestos abatement work and/or the hauling and disposal of asbestos waste materials include, but are not limited to, the following:
 - 1. U.S. Department of Labor, Occupational Safety and Health Administration (OSHA) including, but not limited to:
 - a. Occupational Exposure to Asbestos, Tremolite, Anthophyllite, and Actinolite; 29 CFR, Part 1926.1101 (amended)
 - b. Respiratory Protection 29 CFR, Part 1910, Section 134
 - c. Asbestos in Construction Industry 29 CFR, Part 1926.1101 (amended)
 - d. Access to Employee Exposure and Medical Records 2 9 CFR, Part 1910, Section 2
 - e. Hazard Communication 29 CFR, Part 1910, Section 1200 and Part 1926.1101 (amended)
 - f. Specifications for Accident Prevention Signs and Tags 29 CFR, Part 1910, Section 145
 - 2. U.S. Environmental Protection Agency (EPA) including, but not limited to:
 - a. Asbestos Abatement Projects; Worker Protection Rule 40 CFR, Part 763, Sub part G
 - b. Asbestos Hazard Emergency Response Act (AHERA) Regulation
 - c. Asbestos-Containing Materials in Schools Final Rule & Notice 40 CFR, Part 763, Subpart E
 - d. National Emission Standard for Hazardous Air Pollutants (NESHAPS) 40 CFR, Part 61, Subpart A, and Subpart M (Revised Subpart B)
 - e. Asbestos Model Accreditation Plan 40 CFR Part 763 (amended), Appendix C to Subpart E
 - 3. U.S. Department of Transportation, including, but not limited to: Hazardous Substances 29 CFR Part 171 and 172
- D. Local Regulations that govern asbestos abatement work and/or hauling and disposal of asbestos waste materials include, but are not limited to:
 - 1. NJAC 5:23-8- Asbestos Hazard Abatement Subcode.
 - 2. New Jersey Department of Health regulation 8:60
 - 3. New Jersey Department of Labor regulation 12:120
 - 4. New Jersey Department of Environmental Protection regulation 7:26
- E. Standards that govern asbestos abatement work include but are not limited to the following:
 - National Standards Institute (ANSI)
 1430 Broadway
 New York, New York 10018
 - a. ANSI Standard Z9.2-79 applies specifically to the design and operation of local exhaust systems for maintaining negative pressure.
 - b. ANSI Standard Z288.2-80 applies to practices for respiratory protection.
 - American Society for Testing and Materials (ASTM) 100 Barr Harbor Drive West Conshohocken, PA 19428

- Specification for Encapsulants for Friable Asbestos Containing Building Materials Proposal P-189
- Safety and Health Requirements Relating to Occupational Exposure to Asbestos E 849-82

1.6 NOTICES

A. Send written notification, as required by U.S. EPA National Emission Standards for Hazardous Air Pollutants (NESHAPS) Asbestos Regulations (40 CFR, Part 61, Subpart M), to the regional Asbestos NESHAPS Contact prior to beginning any work on asbestos-containing materials. The project has been granted a waiver from the 10 day notification period, a copy of which is included in Appendix A. Send notification to the following address:

U.S. ENVIRONMENTAL PROTECTION AGENCY Asbestos NESHAPS Contact Air & Waste Management Division 26 Federal Plaza New York, New York 10007

Include the following with the written notification sent to NESHAPS contact:

- 1. Name and address of owner or operator.
- 2. Description of the facility being demolished or renovated, including the size, age, present and prior use of the facility.
- 3. Procedure, including analytical methods, employed to detect the presence of ACM and Category I and Category II non-friable ACM.
- 4. Estimate of the approximate amount of ACM to be removed from the facility is terms of length of pipe in linear meters (linear feet), surface area in square meters (square feet) on other facility components, or volume in cubic meters (cubic feet) if off the facility components. Also, estimate the approximate amount of Category I and Category II non-friable ACM in the affected part of the facility that will not be removed before demolition.
- 5. Location and street address (including building number or name and floor or room number, if appropriate), city, county, and state, of the facility being demolished or renovated.
- 6. Scheduled starting and completion dates of asbestos removal work (or any other activity, such as site preparation that would break up, dislodge, or similarly disturb asbestos material) in a demolition or renovation.
- 7. Scheduled starting and completion dates of demolition or renovation.
- 8. Description of planned demolition or renovation work to be performed and method(s) to be employed, including demolition or renovation techniques to be used and description of affected facility components.
- 9. Procedures to be used to comply with the requirements of US EPA National Emission Standards for Hazardous Air Pollutants (NESHAPS) Asbestos Regulations (40 CFR, Part 61 Sub part M), including asbestos removal and waste handling emission control procedures.
- 10. Name and location of the waste disposal site where the asbestos waste material will be deposited.
- 11. Description of procedures to be followed in the event that unexpected ACM is found or Category II non-friable ACM becomes crumbled, pulverized, or reduced to powder.
- 12. Name, address, and telephone number of the waste transporter.

- B. Send written notification to any other federal, state or local agencies as required. These agencies may include, but are not limited to the following:
 - 1. OSHA

Occupational Safety and Health Administration 201 Varick Street

Room 670

New York, New York 10014

2. NIOSH

National Institute for Occupation Safety and Health

Region II - Federal Building

26 Federal Plaza

New York, New York 10007

3. New Jersey Department of Health

Asbestos Control Program

Division of Occupational and Environmental Health

P.O. Box 360

Trenton, New Jersey 08625-0360

4. New Jersey Department of Labor

Office of Asbestos Control and Licensing

P.O. Box 054

Trenton, New Jersey 08625-0054

5. New Jersey Department of Environmental Protection

Division of Solid Waste Management

840 Bear Tavern Road

P.O. Box 414

Trenton, New Jersey 08625-0414

6. New Jersey Department of Community Affairs

Bureau of Code Services

P.O. Box 816

Trenton, New Jersey 08625-0816

1.7 SUBMITTALS

- A. It is the intent of this section to show all submittals required after award of the Contract.
- B. Submit an Asbestos Abatement Plan with the following information for review and approval prior to beginning asbestos abatement.
 - Copy of Project Notification and list of agencies notified including the General Contractor (if applicable), Fire Department (if applicable), Police Department (if applicable) and any other person, company and/or agency, in compliance with OSHA 1926.1101 {d}.
 - 2. A plan including safety precautions such as fall protection, first aid, and safety procedures and equipment and work procedures to be used in the removal and demolition of materials containing asbestos. Include in the plan the methods and abatement techniques to be used, personal protective equipment to be used including, but not limited to, respiratory protection, type of whole-body protection, disposal plan, type of wetting agent and asbestos sealer to be used, and a description of the method to be employed in order to control environmental pollution to the surrounding areas. Include in the plan both fire and medical emergency response plans and the location and use of fire extinguishers, including evacuation procedures, source of medical assistance and procedures to be used for access by medical personnel (examples: first aid squad and physician) with telephone numbers and locations of emergency response personnel.
 - 3. Documentation of fit testing program conducted by the Asbestos Abatement Contractor.

- 4. Explanation of the handling of asbestos contaminated waste including name, address and U.S. EPA and NJ DEP identification numbers of Waste Hauler and the landfill.
- 5. Testing Laboratory Submit the name, address, and telephone number of each testing laboratory selected for the analysis, and reporting of airborne concentrations of asbestos fibers along with evidence that each laboratory selected holds the appropriate New Jersey license and/or permits and certification that each laboratory is American Industrial Hygiene Association (AIHA) accredited and that persons counting the samples have been judged proficient by current inclusion on the AIHA Asbestos Analysis Registry (AAR) and successful participation of the laboratory in the Proficiency Analytical Testing (PAT) Program. Where analysis to determine asbestos content in bulk materials or transmission electron microscopy is required, submit evidence that the laboratory is accredited by the National Institute of Science and Technology (NIST) under National Voluntary Laboratory Accreditation Program (NVLAP) for asbestos analysis.
- 6. Delineation of responsibility for work site supervision with names and resumes of the responsible parties.
- 7. A list of personnel to be used on this project and licenses and training courses attended by the personnel including U.S. EPA, state, city, or other seminars, or any certifications obtained.
- 8. Report from medical examination conducted within last twelve months as part of compliance with OSHA medical surveillance requirements for each worker who is to enter the work area. Submit, for each worker, a written certification from the licensed health care provider including, at a minimum, the following:
 - a. The worker has met or exceeded all of the medical prerequisites of 29 CFR 1926.1101
 - b. The worker is able to wear and use the type of respiratory protection proposed for the project, and is able to work safely in an environment capable of producing heat stress in the worker.
- 9. Submit certification, signed by an officer of the asbestos abatement-contracting firm, that exposure measurement, medical surveillance, and worker-training records are being kept in conformance with 29 CFR 1926.1101.
- C. After the completion of the abatement at each site, submit asbestos abatement closeout documents. These documents shall include, but not be limited to, the following items:
 - 1. Air monitoring samples and results.
 - 2. Asbestos removal certification. See Appendix G for Certification of Asbestos Abatement.
 - 3. Disposal Manifest forms, including amount of material, waste hauler's signature, landfill operator's signature and location where material was removed.

PART 2 – PRODUCTS

2.1 MATERIALS

- A. Provide flame resistant polyethylene of the largest sheet size possible to minimize seams. Thickness shall be six-mils, and shall be clear, frosted, or black as required. Certify that all polyethylene conforms to NFPA Standard 701 "Standard Methods of Fire Tests for Flame Resistant Textiles and Films".
- B. Duct tape, in two or three-inch widths as indicated, with an adhesive which is formulated to aggressively stick to sheet polyethylene.

020590-12

- C. Asbestos warning signs, in English and Spanish, for posting at the perimeter of all work areas, as required by U.S. EPA, OSHA, and NJAC 5:23-8.
- D. Disposable full-body coveralls including foot and head covers. Require that they be worn by all workers in the work area. Provide a sufficient number for all required changes, for all workers in work area, authorized visitors, inspectors, and the Engineer.
- E. Provide gloves to all workers, authorized visitors, inspectors, and the Engineer. Require that they be worn by all workers inside the work area. Do not remove gloves from work area. Dispose of as asbestos- contaminated waste at the end of work.
- F. Half-face, at a minimum, or full-face type respirators for each worker. Equip full-face respirators with a nose cup or other anti-fogging device. Equip respirators with High Efficiency Particulate Air (HEPA) type filters, labeled with NIOSH and MSHA Certification for "Radionuclides, Radon Daughters, Dust, Fumes, Mists including Asbestos-Containing Dusts and Mists" and color-coded in accordance with ANSI Z228.2 (1980). Single use, disposable, or quarter-face respirators are strictly forbidden for asbestos abatement work.
- G. Disposal bags shall be six-mil thick, leak tight polyethylene bags, labeled in accordance with U.S. EPA NESHAPS regulations, OSHA 29 CFR, 1926 and the U.S. Department of Transportation Hazardous Waste Hauling Regulation.
- H. If waste components are wrapped with polyethylene, or if fiberboard drums are utilized, provide labels to be attached to each component in accordance with U.S. EPA NESHAPS regulations, OSHA 29 CFR, 1926.1101, and the U.S. Department of Transportation Hazardous Waste Hauling Regulation.

PART 3 – EXECUTION

3.1 AIR MONITORING - TESTING LABORATORY SERVICES

- A. Description: This section describes the air monitoring responsibilities of the Contractor throughout the project. The Contractor's air monitoring responsibilities shall be conducted by an independent firm.
 - 1. Air monitoring as required by OSHA is the direct responsibility of the Contractor.
 - 2. Air monitoring at the building exterior within the limits of construction.
 - 3. Air monitoring of the building interior.

B. Air monitoring

- 1. Pre-Tests: Conduct pre-tests in the work area prior to the start of any work, including work area preparation of any type.
- 2. Monitoring during Abatement: Conduct all monitoring as specified during the abatement and decontamination phases of the project.
- 3. Post Abatement Clearance Monitoring

C. Procedures

- 1. Sampling and analysis methods shall be per NIOSH Method 7400, PCM and / or TEM, as applicable for the quantities of ACM and methods of abatement.
- 2. Assemble filter cassettes and sampling train as specified in the applicable requirements.
- 3. Air monitoring shall be conducted by a trained technician.

- 4. Take employee personnel samples using pumps whose flow rates are calibrated for a rate of one to two and one-half liters per minute (LPM). Calibrate all air monitoring pumps before and after every sampling period, the results of which shall be recorded.
- 5. Air sample results shall be received verbally no later than twenty-four hours after the end of the shift during which the samples were taken.
- 6. Post written reports of air sampling results outside the decontamination chamber on a daily basis.
- D. Laboratory services: Laboratories shall meet the following: For Phase Contrast Microscopy (PCM) analysis, laboratories shall be enrolled in the American Industrial Hygiene Association Proficiency Analytical Testing Program (AIHA PAT) or equivalent recognized program.
- E. Reports: Submit a written report of the OSHA sampling to the Engineer at the completion of the project. The report shall contain all air sampling data and subsequent results, problems encountered and corrective actions, pump calibrations, and general observations.

3.2 FINAL CLEARANCE AIR MONITORING

- A. Collect final clearance air samples at the completion of interior abatement activities and after a satisfactory clean-up inspection.
- B. Engineering controls, critical barriers and the decontamination unit shall remain during final clearance air sampling.
- C. Take all final clearance air samples using aggressive sampling techniques as follows:
 - 1. Before sampling pumps are started, sweep the exhaust from forced air equipment (leaf blower with 1 HP electric motor) against all walls, ceilings, floors, ledges and other surfaces in the room. Continue this procedure for five (5) minutes per 10,000 cubic feet of air volume.
 - 2. Mount one 20" diameter fan per 10,000 cubic feet of room volume in a central location at approximately 2 meters above the floor, directed towards the ceiling and operated at low speed for the entire period of sample collection.
 - 3. Collect air samples in areas subject to normal air circulation away from room corners, obstructed locations, and sites near windows, doors or vents.
- D. Collect a minimum of five (5) samples from the work area and analyze them in accordance with the method set forth in the AHERA Regulation 40 CFR Part 763 Appendix A.
 - 1. For work area(s) where more than 160 SF or 260 LF of asbestos-containing materials have been removed, collect and analyze final clearance samples utilizing Transmission Electron Microscopy (TEM).
 - 2. For work area(s) where less than 160 SF or 260 LF of asbestos-containing materials have been removed, collect and analyze final clearance samples utilizing Phase Contrast Microscopy (PCM).
 - 3. Analyze TEM samples at a laboratory accredited by the American Industrial Hygiene Association, participating in the National Voluntary Laboratory Accreditation Program (NVLAP). Analyze PCM samples in accordance with the most recent revision to NIOSH method 7400.
 - 4. Acceptable Clearance Criteria for work area demobilization and re-occupancy are as follows:
 - a. TEM: Average of less than 70 structures per millimeter squared for all five (5) samples analyzed.
 - b. PCM: Less than 0.010 fibers per cubic centimeter.

3.3 SITE CONTROLS

- A. Warning signs: Supply and post caution signs meeting the requirements of OSHA 29 CFR, 1926 at any location, and approaches to a location, where airborne concentrations of asbestos may exceed ambient background levels. Post signs at a distance sufficiently far enough away from the work area to permit an employee to read the sign and take the necessary protective measures.
- B. Critical barriers: Completely isolate the work area from other portions of the project by installing warning tape, construction barriers and additional signs, as required.

3.4 WORKER TRAINING AND MEDICAL EXAMINATIONS

- A. Train workers, in accordance with 29 CFR, 1926.1101(k)(8), on the dangers inherent in handling asbestos and breathing asbestos dust and in proper work procedures and personal and area protective measures. Training for any Class I or II (OSHA designations) abatement work shall be in accordance with the U.S. EPA Model Accreditation Plan (MAP) for asbestos abatement worker training. Include, but do not limit, the topics covered in the course to the following:
 - 1. Methods of recognizing asbestos.
 - 2. Health effects associated with asbestos.
 - 3. Relationship between smoking and asbestos in producing lung cancer.
 - 4. Nature of operations that could result in exposure to asbestos.
 - 5. Importance of and instruction in the use of necessary protective controls, practices and procedures to minimize exposure including:
 - a) Engineering controls
 - b) Work Practices
 - c) Respirators
 - d) Housekeeping procedures
 - e) Hygiene facilities
 - f) Protective clothing
 - g) Decontamination procedures
 - h) Emergency procedures
 - i) Waste disposal procedures.
 - 6. Purpose, proper use, fitting, instructions, and limitations of respirators, as required by 29 CFR, 1910.134.
 - 7. Appropriate work practices for the work.
 - 8. Requirements of medical surveillance program.
 - 9. Review of 29 CFR, 1926.1101, including appendices.
 - 10. Negative air systems.
 - 11. Work practices including hands-on or on-job training.
 - 12. Personal decontamination procedures.
 - 13. Air monitoring, personal and area.
 - 14. Provide medical examinations for all workers in accordance with 29 CFR, 1926.1101(m). Provide an evaluation of the individual's ability to work with respiratory protection in environments capable of producing heat stress in the worker.

3.5 RESPIRATORY PROTECTION

A. Contractor shall have a respiratory protection program established in compliance with ANSI Z88.2 - 1980 "Practices for Respiratory Protection" and OSHA 29 CFR, 1910 and 1926. Post the written program at the job site.

- 1. Anyone entering the work area is required to wear a respirator at all times, regardless of activity, airborne fiber levels or amount of time inside the work area.
- 2. At no time shall single-use, disposable, or quarter-face respirators be used.
- 3. No one having a beard or other facial hair in the fit area will be permitted to don a respirator and enter the work area.
- B. Conduct a fit testing program as required by OSHA 29 CFR 1926 and submit documentation of fit testing program.
- C. Asbestos abatement workers shall perform positive and negative pressure fit checks each time a respirator is donned, whenever the respirator design so permits.
- D. Provide respirators to all workers as follows: During all abatement work, negative pressure airpurifying respirators equipped with high-efficiency (HEPA) filters shall be utilized, at a minimum.

3.6 PROJECT DECONTAMINATION

A. INITIAL CLEANING

Carry out initial cleaning of all surfaces which came into contact with the asbestoscontaining materials removed, including any tools, etc., by use of damp-cleaning and
mopping, and/or a HEPA filtered vacuum. Do not perform dry dusting or dry sweeping.
Use each surface of a cleaning cloth one time only, and then dispose of as contaminated
waste. Continue this cleaning until there is no visible debris from removed materials or
residue on substrate surfaces.

B. COMPLETION OF ABATEMENT WORK

1. Remove any small quantities of residual material found on-site with a HEPA filtered vacuum cleaner and local area protection. If significant quantities, as determined by the Engineer, are found then decontaminate the entire area affected as specified herein.

3.7 FINAL INSPECTION

- A. Perform a final inspection of the work area in accordance with New Jersey Department of Labor and Workforce Development requirements. If analytical results are obtained that are higher than the allowable threshold, re-clean the work area and the re-test the area. Repeat this sequence until the final test results are acceptable.
 - 1. Provide any additional cleaning, contractor services and final clearance air sampling and analysis at no cost to the Owner.
- B. Upon receipt of acceptable final air tests, demobilize all critical and separation barriers, decontamination unit and engineering controls from the abatement work areas. All waste containers shall be off-site and en-route to an USEPA ID #27 approved landfill for final disposal.
- C. Perform a final visual inspection of the abatement work area(s) to document the project has been completed in accordance with these specifications and all applicable Local, State and Federal regulations.
- D. Provide a letter certifying the following: The building referenced above was inspected and sampled for the presence of asbestos material(s), which may become friable during demolition.
 Those asbestos building materials identified have been properly removed utilizing appropriate personal protection, wet removal techniques, engineering controls and enclosures as required. The asbestos materials have been properly transported and disposed of in accordance with prescribed

regulations.

 Utilize this correspondence as part of the demolition permit submission for meeting the New Jersey Uniform Construction Code requirements of N.J.A.C. 5:23 2.4, 2.17 (d), as well as the United States Environmental Protection Agency (USEPA) National Emission Standards for Hazardous Air Pollutants (NESHAP) 40 CFR, Part 61, Subpart M requirements.

DEMOLITION

PART 1 - GENERAL

1.1 SUMMARY

- A. This Section includes:
 - 1. Vermin Control
 - 2. Building Demolition
 - 3. Perimeter Air Monitoring
 - 4. Dust Control
 - 5. Removal of Site Improvements and Below-Grade Construction
 - 6. Removal of Foundation Walls and Footings
 - 7. Removal of Curbs, Walks, Slabs, Decks and Miscellaneous Site Improvements.
 - 8. Removal of Pavements
 - 9. Disposal of Materials
 - 10. Recycling of Materials
 - 11. Recovery of Materials

1.2 RELATED WORK

- A. The work under this Section shall be coordinated with that specified under the following sections, whenever applicable:
 - 1. Section 020590 Removal of Asbestos Materials
 - 2. Section 220000 Plumbing
 - 3. Section 312300 Excavation, Backfilling, and Grading
 - 4. Section 312500 Erosion and Sedimentation Controls
 - 5. Section 329200 Turf and Grasses

1.3 PRIOR APPROVALS

- A. UCC Permits for the demolition of the dwellings shall not be released until all prior approvals have been obtained. The contractor is responsible to obtain the appropriate certifications after the following work is completed.
 - 1. ACM abatement.
 - 2. Sewer and water services are disconnected.
 - 3. Vermin eradication.
- B. Submit all certifications to the Engineer for processing.

1.4 REFERENCES

American National Standards Institute, Inc., ANSI A10.6, 1983 Demolition Operations – Safety Requirements

1.5 SUBMITTALS

- A. The following must be submitted and approved prior to beginning demolition operations:
 - 1. Demolition Plan: Submit proposed demolition and removal procedures for approval before work is started. Include procedures and detailed description of methods and

- equipment to be used for each operation and the sequence of operations.
- 2. Materials Salvage and Recycling Management Plan: Before the start of demolition, submit for approval a Materials Salvage and Recycling Management Plan for all materials to be salvaged or recycled. The Plan shall indicate how demolition waste will salvaged and recycled. Salvage, recycle, and recover at least 80% of demolition waste by volume. Include a list of salvage and recycling outlets, which indicates where salvageable materials will be sent. Identify materials that are not recyclable or otherwise not recoverable that must be disposed of in a landfill or other means acceptable under State and local regulations. List permitted landfills and/or other disposal means to be employed for building waste that cannot be recycled. Indicate any instances where compliance with requirements of this Specification does not appear to be possible and request resolution from the Engineer.
- 3. Health and Safety Plan: Submit a Health and Safety Plan (HASP), which shall be kept at the work site and available to employees, and shall include the following:
 - a. Summary of major activities and types of work to be performed.
 - b. General safety rules and procedures for the performance of the Work. Ensure that all applicable safety regulations are included in this section. Examples for inclusion in this section are: Hazcom Program; Hearing Conservation Program; Respiratory Protection Program; Confined Space Program; Control of Hazardous Energy Sources (Lock-out/Tag-out); Construction Equipment Safety; Personal Protective Equipment; Fire Prevention Requirements; Vehicle Safety.
 - c. A list of emergency phone numbers including those for fire, police, medical, and the release of contaminants into the environment.
 - d. List of personnel responsible for implementing the HASP.
 - e. A safety orientation plan for Contractor and subcontractor personnel.
- 4. Certificate of Pesticide Application.
- B. Provide the following submittals after or during the course of the demolition operations:
 - 1. Landfill-tipping receipts which provide volumes.
 - 2. Receipts for materials types, weight or volume, and revenues from salvage and recycling.
 - 3. An inventory of items or materials, which were salvaged and recycled.
 - 4. Pesticides: Submit SDS sheets and application instruction for each pesticide to be utilized.

1.6 QUALITY ASSURANCE

- A. Regulatory Requirements: Comply with all applicable requirements of the State of New Jersey and applicable County ordinances and regulations concerning management of demolition and disposal of debris.
- B. Implementation: Designate an on-site party responsible for instructing workers and implementing the Materials Salvage and Recycling Management Plan. Distribute copies of the Materials Salvage and Recycling Management Plan to the job site foreman and each appropriate subcontractor. Provide on-site instruction on appropriate salvaging, removing, recovering, and handling procedures to be used by all subcontractors at appropriate stages of the work at the site. Also include discussion of Materials Salvage and Recycling Management Plan in regular job meeting as long as it is appropriate to do so.

1.7 ASBESTOS MATERIAL AND LEAD BASED PAINT

- A. Wallboard Systems in the structures to be demolished may have trace amounts of asbestos. As such, during demolition and loading, all material is to be kept wet. The Contractor shall review the OSHA requirements to ensure compliance and protection of his workers. Contractor shall arrange for perimeter air monitoring.
- B. The Contractor shall anticipate the presence of materials which contain lead based paint (LBP) in

structures built prior to 1978. Refer to paragraph 3.10.E. regarding disposal of LBP.

1.8 REGULATORY AND SAFETY REQUIREMENTS

- A. Comply with Federal, State, and County hauling and disposal regulations. In addition to these requirements, demolition operations shall conform to ANSI A10.6 Demolition Operations Safety Requirements.
- B. In the performance of the work in this Section comply with NJAC 5:17.

1.9 DUST AND DEBRIS CONTROL

- A. Prevent the spread of dust and debris within adjacent public rights-of-way and adjacent properties. Avoid the creation of a nuisance or hazard in the surrounding area.
- B. Limit the use of water for dust control and terminate its use if it results in hazardous or objectionable conditions such as flooding or runoff.
- C. Utilize street cleaning procedures daily to remove debris from the access point to the property.
- D. Sweep pavement(s) as often as necessary to control the spread of debris that may result in foreign object damage potential to person or property.

1.10 PROTECTION

- A. Do not proceed with any work until all temporary fencing and soil erosion and sediment control procedures, as required elsewhere in these Specifications, are installed.
- B. Where pedestrian and driver safety is endangered in the area of removal work, use traffic barricades with flashing lights. Anchor barricades in a manner to prevent displacement.
- C. Protect existing infrastructure which is to remain after the work in this Section is completed. Repair items, which are to remain, and which were damaged during the performance of the work to their original condition, or replace with new.
- D. Undertake backfilling, compaction, and grading after demolition in accordance with the requirements of Section 312300.

1.11 UTILITY DISCONNECTS

- A. Telephone, cable, natural gas and electrical services serving the buildings to be demolished have been disconnected. Verify that all utilities have been disconnected before any demolition begins.
- B. Termination of water service and sewer connection is specified in Section 220000. This work must be completed prior to the demolition of the buildings.

1.12 DEFINITIONS

- A. Salvage is defined as the recovery or reapplication of a package or product for uses similar or identical to its originally intended application, without manufacturing or preparation processes that significantly alter the original package or product. Salvage refers to materials that are recovered for reuse off-site and sold or donated to a third party.
- B. Recycling is defined as the process of collecting and preparing recyclable materials and reusing them in their original form or in manufacturing processes that do not cause the destruction of

recyclable materials in a manner that precludes further use.

C. Recovery is defined as any process that reclaims materials, substances, energy, or other products contained within or derived from the waste. It includes waste-to-energy, composting, and other processes. It also includes materials, which if released into the atmosphere or disposed in landfills may cause environmental damage.

1.13 STORAGE

A. Site Storage: Remove all materials that are to be salvaged and recycled from the site.

PART 2 - PRODUCTS

2.1 PESTICIDES

A. All pesticides used for the eradication of vermin (rodent and insects) shall be EPA Registered.

PART 3 – EXECUTION

3.1 VERMIN (RODENT AND INSECT) ERADICATION

- A. Treat the buildings to be razed with pesticides to assure that they are free from all pests including rats, mice, roaches or other vermin present that may pose a risk of infesting adjacent properties following demolition.
- B. Application of pesticides shall be by a pest control operator licensed by the State of New Jersey, and be applied in accordance with the application instructions.
- C. Conduct an inspection of the buildings to be razed after they are treated and certify the pesticide treatment and that the buildings are vermin-free. Do not demolish any buildings until all buildings are certified vermin-free.
- D. Prior to beginning demolition, submit a Certificate of Pesticide Application listing:
 - 1. Pesticides used and quantities
 - 2. Method of application
 - 3. Target vermin
 - 4. Treatment inspection results

3.2 STRUCTURES

- A. Demolish structures completely including dwellings, porches, sheds, garages, patios, and decks unless otherwise noted on drawings.
- B. Proceed with demolition in a systemic manner from the top of the structure to the ground. Complete demolition work above each tier, or floor, before the supporting members on the lower levels are disturbed. Demolish concrete and masonry walls in small sections.
- C. Demolish structure by mechanical means. Do not use explosives or burning.
- D. Demolish and remove all below grade construction, including foundation walls, footings, grade slabs, piles, and other below grade construction.
- E. After demolition, backfill, compact, and grade the site in accordance with the requirements of Section 312300.

3.3 AIR MONITORING – TESTING LABORATORY SERVICES

- A. Description: This section describes the air monitoring responsibilities of the Contractor. The Contractor's air monitoring responsibilities shall be conducted by an independent firm.
 - 1. Air monitoring as required by OSHA is the direct responsibility of the Contractor.
 - 2. Air monitoring of the building exterior within the site boundary limits (perimeter).
 - 3. Air monitoring during asbestos abatement.

B. Air Monitoring

- Monitoring during demolition of the structure due to potential trace amounts of
 asbestos associated with wallboard systems which include wallboard, joint tape, and
 joint compound. Air monitoring is required during the demolition phase and loading of
 waste for transportation off-site.
- 2. During asbestos abatement See Section 020590.

C. Procedures

- 1. Sampling and analysis methods shall be per NIOSH Method 7400.
- 2. Assemble filter cassettes and sampling train as specified in the applicable requirements.
- 3. Air monitoring shall be conducted by a trained technician.
- 4. Take employee personnel samples (OSHA) using pumps whose flow rates are calibrated for a rate of one to two and one-half liters per minutes (LPM). Calibrate all air monitoring pumps before and after every sampling period, the results of which shall be recorded. Perimeter samples shall be performed using either low or high volume pumps with a minimum of 1,200 liter per sample. Sample cassettes shall be at stationary locations at the typical "breathing zone" (4 to 5 feet above ground level).
- 5. OSHA and Perimeter Air sample results shall be received verbally no later than twenty-four hours after the end of the shift during which the samples were taken. Post written reports of OSHA air sampling results and provide copies of perimeter sample results to the DPMC's representative on a daily basis.
- D. Laboratory Services: Laboratories shall meet the following: For Phase Contrast Microscopy (PCM) analysis, laboratories shall be enrolled in the American Industrial Hygiene Association Proficiency Analytical Testing Program (AIHA PAT) or equivalent recognized program.
- E. Reports: Submit a written report of the sampling to the Engineer at the completion of the project. The report shall contain all air sampling data and subsequent results, problems encountered and corrective actions, pump calibrations, and general observations.

3.4 SITE IMPROVEMENTS

- A. Remove secondary electrical distributions, including site lighting conduit and wiring, and after demolition, backfill, compact, and grade the site in accordance with the requirements of Section 312300. Remove all other underground pipes located within the limits of removals.
- B. Below grade excavation and removal is unclassified. Remove all below grade structures whether shown on the drawings or not.
- C. Remove fences and other site improvements where indicated on the drawings.

3.5 CURBS, PAVEMENTS, AND SLABS

A. Remove curbing, pavements and concrete slabs, stairs, ramps, footings, and walks where indicated on the drawings.

3.6 SWIMMING POOLS

A. Prior to demolition of above or below ground pools, notify the State prior to discharge of pool water to an adjacent storm drain.

3.7 REMOVAL OF UNCLASSIFIED DEBRIS

A. It is the intent of the work of this Section that all debris and materials on each property or site be removed and disposed. This material is unclassified and may include collapsed wood structures, furniture, appliances, containers, paint, clothing, toys, tires, propane tanks, pipes, metals, etc.

3.8 MATERIALS TO BE RECOVERED

- A. Materials to be recovered prior to demolition include, but are not limited to, the following. Take the materials to an approved reclamation center. Utilize licensed technicians where required by regulations to recover regulated materials.
 - 1. Ozone-depleting refrigerants from appliances and air conditioners
 - 2. Thermostats and switches containing mercury
 - 3. Fluorescent lamps
 - 4. Lighting ballasts
 - 5. Appliances and motors
 - 6. Smoke detectors

3.9 MATERIALS TO BE RECYCLED

- A. Recover the following materials during demolition and take them to an approved recycling center. Comply with the Materials Salvage and Recycling Management Plan for recycled materials.
 - 1. Wood products
 - 2. Metals including wire and piping
 - 3. Brick
 - 4. Concrete products
 - 5. Asphalt pavements
 - 6. Roofing products
 - 7. Porcelain plumbing fixtures
 - 8. Tires

3.10 DISPOSITION OF MATERIAL

- A. Immediately relocate, recycle, or dispose of all other demolished material away from site.
- B. Except where specified in other Sections, all materials and equipment removed and not reused, becomes property of the Contractor and shall be removed from the property. Title to materials, resulting from demolition, and materials and equipment to be removed, is vested in the Contractor.
- C. Disposal of Rubbish and Debris: Dispose of all rubbish and debris in accordance with the requirements specified herein and in accordance with applicable laws and ordinances.
- D. Except for materials scheduled for recycling, remove all debris and legally dispose of the debris at a licensed landfill.

E. Lead Hazard: In the performance of the work, remove and dispose of lead-based material in accordance with applicable DEP Regulations.

3.11 BACKFILLING AND GRADING

A. Conduct backfilling, compaction, and grading in accordance with Section 312300.

END OF SECTION

DEMOLITION 020700-7 Rev. 10/31/2016

PLUMBING

PART 1 – GENERAL

1.1 SUMMARY

- A. This Section includes the following:
 - 1. Locating and capping of sewer laterals as indicated on the drawings and removal of the sewer lateral from the cap to the dwelling.
 - 2. Locating and capping the water service at the curb valve, or other location as indicated on the drawings, and removal of the water service from the cap to the dwelling.

1.2 RELATED WORK

- A. The work under this Section shall be coordinated with that specified under the following sections, whenever applicable:
 - 1. Section 312300 Excavation, Backfilling, and Grading

1.3 CODES AND STANDARDS

- A. New Jersey Uniform Construction Code
- B. 2018 National Standard Plumbing Code
- C. Requirements of the utility owner / operator for termination and capping

1.4 DRAWINGS

A. Locations of the existing underground utilities are approximate. Locate the service lines and cap the services as specified.

PART 2 – PRODUCTS

2.1 SANITARY SEWER

- A. Cap for underground sewer pipe: Provide Fernco Quick Cap or equivalent product by Everflow Supplies, Wal-Rich, or approved equal consisting of a flexible PVC cap with stainless steel clamping ring, rated for underground installation; or provide a mechanical friction plug with natural rubber or flexible PVC bushing and stainless steel or galvanized steel pressure plates.
- B. Concrete thrust block: Utilize packaged dry concrete mix with a minimum 7-day compressive strength of 2,500 psi in conformance with ASTM C 387, or approved equal.

2.2 WATER PIPING

A. Copper pipe size 2 inches and under: Provide copper cap with soldered joints. Galvanized steel pipe: Provide galvanized steel cap. Plastic pipe: Provide plastic cap with solvent weld.

PART 3 – EXECUTION

3.1 GENERAL

PLUMBING 220000-1

- A. Do not start demolition work until utility disconnecting and sealing has been completed and all completion letters have been received and approved.
- B. Coordinate work with the utility owner / operator.
- C. Install caps in accordance with manufacturer's instructions, the Plumbing Code, and as shown on the drawings.

END OF SECTION

PLUMBING 220000-2

EXCAVATION, BACKFILLING, AND GRADING

PART 1 - GENERAL

1.1 SUMMARY

- A. The work under this Section includes the following:
 - 1. Excavation, filling, backfilling, and compaction
 - 2. Grading
 - 3. Disposition of excess excavated materials and debris
 - 4. Final cleanup

1.2 RELATED WORK

- A. The work under this Section shall be coordinated with that specified under the following sections, whenever applicable:
 - 1. Section 312500 Erosion Control
 - 2. Section 020700 Demolition
 - 3. Section 015526 Traffic Controls

1.3 STANDARDS

A. Perform work in accordance with the "NJDOT Standard Specifications for Road and Bridge Construction, 2007," as amended herein.

1.4 SUBMITTALS

- A. Submit documentation from a testing agency demonstrating that the fill material meets the Specification proctor and gradation requirements. Attach test results and submit with the Certification of Clean Fill Material. See Appendix H for Certification of Clean Fill Material letter.
- B. Submit daily to the DPMC a load ticket specifying the origin of the material for each load of fill delivered to the site.

PART 2 – PRODUCTS

2.1 MATERIALS

- A. Fill Material: Sand and gravel free of deleterious material including debris, waste, frozen materials, vegetation, and organic matter and containing no more than 20% fines (minus No. 200 sieve size), and free of rock or gravel larger than 3 inches in any dimension. Occasional boulders up to 12 inches in diameter will be acceptable provided they are buried a minimum of 12 inches below the topsoil layer. Excavated soil material from within the site may be permitted for use as fill material if in the opinion of the Engineer such material is free of deleterious materials. The use of Recycled Concrete Aggregate is not permitted.
- B. Provide documentation that the fill material is from a virgin source or meets the most stringent requirements of the New Jersey Residential, Non-Residential, and Impact to Groundwater Standards.

PART 3 - EXECUTION

3.1 DEWATERING

- A. No subsurface boring information is available. The Contractor is advised that high seasonal or perched groundwater should be expected during excavation operations.
- B. Provide dewatering for the proper execution of the work under this contract. This may include pumping of basements and or excavations.

3.2 EXCAVATION

- A. Excavation shall be carried to the limits required by the construction. Material shall be removed to the lines and depth to allow construction of the various portions of the project.
- B. All excavation shall be unclassified, and all material of whatever character encountered shall be removed, including bituminous and concrete pavements, footings and foundations, whether shown on the drawings, or as may be encountered during the course of construction.

3.3 BACKFILL

- A. Filling and backfilling shall consist of depositing, spreading, and compacting approved materials to the required elevations indicated. Completely fill below-grade areas and voids.
- B. Place fill material in 12" layers. Spread each layer evenly and thoroughly place and mix during the spreading to ensure uniformity of material in each layer. Keep the surface of the fill at a slight slope to facilitate drainage of any ground or surface water that enters the excavation. The moisture content of the fill material shall be at, or slightly below, the optimum moisture content for the soils being utilized during the entire compaction operation. If, in the opinion of the Engineer, the fill is too dry for proper compaction, uniformly moisten or aerate the subgrade and fill layers before compaction. Do not place, spread or compact fill material while the ground or fill is muddy, frozen or thawing or contains frost or ice. When work is interrupted by heavy rain, do not resume fill until the moisture content and density of the fill are as previously specified. Maintain ground water at a minimum of 2' below the surface of the fill during the backfilling operation. Compact the fill by suitable methods using roller and/or vibratory compactors of the proper size commensurate with the construction area. Utilize manual compactors within 5' of constructed or existing foundations, walls, and slabs.
- C. The minimum density to be obtained in the backfill is 90% of the maximum dry unit weight as defined in ASTM D-1557, Moisture Density Relations of Soil (Standard Proctor Compaction Test Method).

3.4 GRADING

- A. Rough grading: Grade to meet the elevations of adjacent areas to create a smooth surface, free from irregular surface changes. Uniformly rough grade the area of demolished construction.
- B. Bring subgrades, after final compaction, to the grades and sections for preparation of the final grading operations.
- C. Final Grading: Mound the final grade within the backfilled area to 3"-6" above the adjacent grade. Provide a smooth transition between adjacent existing grades and new grades.

3.5 TESTING

A. Engage and pay for a testing agency approved by DPMC to conduct material and compaction testing. For each on-site and borrow material intended for use in the backfilling operations, submit the results of a Modified Proctor Density (ASTM D1557) analysis and results of a sieve analysis (ASTM D422 (2007) or ASTM D6913). The maximum dry density and optimum moisture content of all compacted fills shall be determined by the Modified Proctor Density Test (ASTM D 1557).

The placement of compacted fill shall be observed and tested by either the Sand Cone Method (ASTM D 1556) or Nuclear Density Gauge Method (ASTM D 6938 and D 3012) at the following minimum frequency: 1 test per every 2500 SF, per lift. Remove, replace, and compact fill not meeting the required density until additional tests indicate compliance with Specifications.

3.6 FINAL CLEANUP

- A. Repair and reestablish grades to the required tolerances where completed or partially completed surfaces become eroded, rutted, settled, or where they lose compaction due to subsequent construction operations or weather conditions.
- B. Clean all areas occupied in connection with the project of all rubbish; excess materials, temporary structures and equipment, and leave all parts of the site in an acceptable condition.

END OF SECTION

SECTION 312500

EROSION AND SEDIMENTATION CONTROLS

PART 1 - GENERAL

1.1 SUMMARY

- A. This Section includes the following:
 - 1. Construction of temporary and permanent measures to control soil erosion and sedimentation including, but not limited to, vegetative cover, mulching, silt fence, tree protection, grading, diversions, slope protection, siltation barriers, dust control, and other such methods and materials necessary or directed by the Engineer to control soil erosion and sedimentation during construction.
 - 2. Install erosion and sedimentation control measures prior to any clearing, grubbing, grading operations or demolition and maintain the measures until construction is complete and the construction area is stabilized. After restoration is complete, remove temporary control measures and dispose of properly.
 - 3. Construct and maintain all erosion and sedimentation control measures in accordance with the Standards for Soil Erosion and Sediment Control in New Jersey, incorporated herein by reference, as amended and supplemented.

1.2 RELATED WORK

- A. The work under this Section shall be coordinated with that specified under the following sections, whenever applicable:
 - 1. Section 31225 Excavation, Backfilling, and Grading
 - 2. Section 32920 Turf and Grasses

1.3 REFERENCES

- A. The publications listed below form a part of this Specification to the extent referenced.
 - 1. Soil Conservation District Permit Requirements.
 - 2. Standards for Soil Erosion and Sediment Control in New Jersey, 2014, incorporated herein by reference, as amended and supplemented.
 - 3. NJDOT Standard Specification Section 158, Soil Erosion and Sediment Control and Water Quality Control.

PART 2 - PRODUCTS

2.1 GENERAL

- A. Materials shall conform to the following:
 - 1. Seed: Seed mixtures as indicated on the drawings.
 - 2. Mulch: Hay or straw as indicated on the drawings.
 - 3. Haybales: NJDOT Standard Specification Section 919.03, Hay and Straw.
 - 4. Silt Barrier Fence: 24-inch height above ground, installed, as per the drawings.
 - a. Geotextile fabric section shall have a width of at least three feet (3'). The total exposed silt fence height shall be two feet (2') high after one foot (1') of fabric is buried in the existing soil.

b. Join geotextile sections in such a manner that, when in operation, the sections work effectively as a continuous fence. Install fence posts at a slight angle toward the anticipated runoff source.

5. Inlet Filters

- a. Install inlet filters, consisting of geotextile fabric, to control sedimentation at inlet drainage structures.
- b. For existing inlet structures, place geotextile fabric under the grates, over the curb and extend beyond a minimum of six inches (6"). Place coarse aggregate size No. 8 shall behind each curb piece and on the geotextile fabric to secure the fabric in place.
- B. Any other materials required shall conform to the Standards for Soil Erosion and Sediment Control in New Jersey.

PART 3 – EXECUTION

3.1 INSTALLATION

- A. Install soil erosion and sediment control devices in accordance with the sequence of construction shown on the Soil Erosion and Sediment Control Notes.
- B. Install soil erosion and sediment control devices in accordance with the Standards for Soil Erosion and Sediment Control in New Jersey.

3.2 DUST CONTROL

- A. Employ construction methods and means that keep flying dust to the minimum, including sprinklering the site.
- B. The use of calcium chloride or petroleum products or other chemicals for dust control is prohibited.
- C. Wet sweep the public streets adjacent to the site as needed to maintain dust control and in order to eliminate obstructions to street drainage.

3.3 DIRT CONTROL

- A. Provide for prompt removal from existing roadways of all dirt and other materials that have been spilled, washed, tracked or otherwise deposited thereon. Haul off-site or use any other methods to dispose of whenever the accumulation is sufficient to cause the formation of mud, interfere with drainage, damage pavements or create a traffic hazard.
- B. In order to minimize tracking of dirt and other materials onto roadways, construct a stabilized construction entrance at locations where vehicles exit a work site, as indicated on the drawings. Maintain the driveways by top dressing with additional stone as directed.

3.4 DEWATERING

- A. Perform dewatering operations in accordance with the Standards for Soil Erosion and Sediment Control in New Jersey.
- B. When dewatering will occur and a dewatering permit is not required, monitor for adverse effects to structures or wells due to dewatering and remedy the same to the satisfaction of the Engineer. Discharges from dewatering activities which contain silt are subject to the following controls:

1. All discharges from dewatering activities to surface waters, wetlands, vernal habitats, or storm sewers shall be free of sediment. Exercise care to not damage or kill vegetation by excessive watering or by damaging silt accumulation in the discharge area. If discharges are sediment laden, employ techniques to remove sediment prior to discharge. Unfiltered dewatering is not permitted A sedimentation basin shall be constructed and used where necessary to protect vegetation and to achieve environmental objectives.

3.5 PROHIBITED CONSTRUCTION PROCEDURES

- A. Prohibited construction procedures include, but are not limited to, the following:
 - 1. Dumping of spoil material into any stream corridor, any wetlands, any vernal habitats, any surface waters, any sites listed or eligible for listing on the New Jersey or National Registers of Historic Places, or at unspecified locations;
 - 2. Indiscriminate, arbitrary or capricious operation of equipment in any stream corridors, wetlands, vernal habitats or surface waters;
 - 3. Pumping of silt laden water from trenches or other excavations into any surface waters, stream corridors, wetlands, or vernal habitats;
 - 4. Damaging vegetation adjacent to or outside of the limit of disturbance;
 - 5. Disposal of trees, brush and other debris in any stream corridors, wetlands, vernal habitats, surface waters, or at unspecified locations;
 - 6. Permanent or unspecified alteration of the flow line of any drainage feature;
 - 7. Open burning of project debris;
 - 8. Use of calcium chloride, petroleum products or other chemicals for dust control;
 - 9. Use of asphaltic mulch binders; and
 - 10. Any unpermitted discharge of sewage.

3.6 STOCKPILES

- A. Staging and stockpile areas not located within the limit of disturbance may require certification of a soil erosion and sediment control plan. Certification of a soil erosion and sediment control plan may be required for these activities if an area greater than 5,000 square feet is disturbed at each site.
- B. Temporarily stabilize all soil stockpiles.

3.7 SOIL EROSION AND SEDIMENT CONTROL MAINTENANCE

- A. Maintain soil erosion and sediment control measures throughout the life of the project to ensure that the measures function properly. Inspect soil erosion and sediment controls immediately after each rain and perform any corrective work immediately to return the soil erosion and sediment control measures to proper function, as directed. Riprap stones, coarse aggregate, silt fence, or hay bales damaged due to washouts or siltation shall be replaced as directed. When directed, remove and replace measures not functioning, due to clogging, damage, or deterioration.
- B. Remove sediment from silt fences, stone outlet structures, inlet filter, dams, and haybales when the sediment reaches fifty percent (50%) of the height of the soil erosion and sediment control measure.

END OF SECTION

SECTION 329200

TURF AND GRASSES

PART 1 - GENERAL

1.1 SUMMARY

- A. This Section includes the following:
 - 1. Topsoil
 - 2. Soil conditioning
 - 3. Seeding
 - 4. Mulch and Mulch Stabilization

1.2 RELATED WORK

- A. The work under this Section shall be coordinated with that specified under the following sections, whenever applicable:
 - 1. Section 312500 Erosion and Sedimentation Controls

1.2 REFERENCES

- A. The publications listed below form a part of this Specification to the extent referenced.
 - U.S. Department of Agriculture (DOA)
 DOA FSA: Federal Seed Act Rules and regulations of the Secretary of Agriculture (latest edition)
 - 2. New Jersey Department of Transportation (NJDOT) 2007Standard Specifications for Road and Bridge Construction
 - 3. New Jersey Standards for Soil Erosion and Sediment Control, latest edition.

1.3 PLANTING DATES

A. Refer to the dates in the Soil Erosion and Sediment Control Notes for temporary and permanent planting dates. If the season prevents establishment of temporary or permanent cover, treat disturbed areas by mulching as specified on the drawings.

1.4 SUBMITTALS

- A. Certification of Imported Topsoil Material. See Appendix I for Certification of Imported Topsoil Material letter.
- B. Seed mixtures product data indicating conformance to project requirements.

PART 2 – PRODUCTS

2.1 SEED

A. State certified of the latest season's crop delivered in original sealed packages, bearing producer's guaranteed analysis for percentages of mixtures, purity, germination, weed seed content, and inert material. Label in conformance with DOA FSA. Seed which has become wet, moldy, or otherwise damaged in transit or storage will not be accepted. Refer to the drawings for the required seed mixtures.

2.2 TOPSOIL

TURF AND GRASSES 329200-1 Rev. 08/08/2019

- A. Reusable surface soil stripped and stockpiled on site may be used if in compliance with the Specifications for composition.
- B. Off-site topsoil shall conform to the Specifications for composition.

C. Composition:

- 1. Topsoil shall be obtained from naturally drained areas and shall be fertile, friable loam suitable for plant growth. Topsoil shall be subject to inspection and approval at the source of supply and upon delivery.
- 2. The topsoil shall be of uniform quality, free from subsoil stiff or lump clay, hard clods, hardpan, rocks, disintegrated debris, plants, roots, seeds, and any other materials that would be toxic or harmful to plant growth. Topsoil shall contain no noxious weeds or noxious weed seeds.
- 3. The topsoil shall contain at least 2.75 percent organic matter as determined by loss of weight after ignition of dried (moisture-free) samples in accordance with current methods of the Association of Official Agricultural Chemists.
- 4. The acidity range of the topsoil shall be pH 5.5 to 7.5. The salinity level shall be less than 1 millimhos/cm.

2.3 pH ADJUSTERS

- A. The following shall be used to adjust soil pH properties:
 - Raw ground limestone conforming to NJDOT Standard Specifications Section 917.04, Pulverized Limestone.

2.4 FERTILIZER

A. Fertilizer must meet the requirements of NJDOT Standard Specification Section 806, Fertilizing and Seeding and the requirements included on the drawings.

2.5 MULCHES

- A. Mulches for seeded areas meet the requirements of NJDOT Standard Specification Section 917.06, Mulch, and shall be one, or a combination of, the following:
 - 1. Wood Chips: Ground redwood or fir tree bark, 3/16-inch maximum particle size.
 - 2. Straw: Stalks from oats, wheat, rye, barley, or rice. Furnish in air-dry condition and of proper consistency for placing with commercial mulch blowing equipment.
 - 3. Hay: Air-dry condition and of proper consistency for placing with commercial mulch blowing equipment. Provide only marsh hay for lawn areas.
 - 4. Wood Cellulose Fiber: Processed to contain no growth or germination-inhibiting substances and dyed an appropriate color to facilitate visual metering of materials application. Composition on air-dry weight basis: 9 to 15 percent moisture, pH range from 3.5 to 5.0. Use with hydraulic application of grass seed and fertilizer.

PART 3 – EXECUTION

3.1 PREPARATION OF SUBGRADE

- A. "Hard pan" or heavy shale:
 - 1. Plow to a minimum depth of 6".
 - 2. Loosen and grade by harrowing, discing, or dragging.

TURF AND GRASSES 329200-2 Rev. 08/08/2019

- 3. Handrake subgrade. Remove stones over 2" in diameter and other debris.
- B. Loose loam, sandy loam, or light clay:
 - 1. Loosen and grade by harrowing, discing, or dragging.
 - 2. Handrake subgrade. Remove rocks over 2" in diameter and other debris.

3.2 PLACING TOPSOIL

- A. Strip and stockpile topsoil from areas of disturbance for reuse.
- B. After demolition and filling operations are complete, spread stockpiled topsoil and add additional topsoil from offsite sources to establish minimum depth.
- C. Place 6" of topsoil and spread over the prepared subgrade to obtain the required depth and grade elevation
- D. Handrake topsoil and remove all materials unsuitable or harmful to plant growth.
- E. Do not place topsoil when the subgrade is frozen, excessively wet, or extremely dry.
- F. Do not handle topsoil when frozen or muddy.

3.3 TILLAGE


- A. After seed bed areas have been brought to proper compacted elevation, thoroughly loosen to a minimum depth of 5" by discing, harrowing, or other approved methods. Do not work topsoiled areas when frozen or excessively wet.
 - Incorporate liming and fertilizer as part of tillage operation at the rates indicated on the drawings.

3.4 MULCHING

- A. Mulch within 48 hours of seeding.
- B. Place straw mulch in a continuous blanket at a minimum rate as indicated on the drawings and secure as indicated on the drawings.
- C. Apply wood cellulose fiber hydraulically at the rates indicated on the drawings.
 - 1. Incorporate as an integral part of the slurry after seed and soil supplements have been thoroughly mixed.
- D. When mulch is applied to grass areas by blowing equipment, the use of cutters in the equipment will be permitted to the extent that a minimum of 95% of the mulch is 6" or more in length. For cut mulches applied by the blowing method, achieve a loose depth in place of not less than 2".

END OF SECTION

TURF AND GRASSES 329200-3 Rev. 08/08/2019



THIS PROJECT ARE NOT REPRINTED HERE DUE TO SIZE


Appendix B:

Asbestos and Hazardous Waste Tables

And

Laboratory Test Results

ASBESTOS TEST REPORTS FOR THIS HERE DUE	



Appendix D:	
Submittal Log	

TRACKING #	SECTION #	DESCRIPTION	ADDRESS	DATE REC'D	REVIEW CODE	DATE APPROVED	NOTES
1	020700	Health & Safety Plan					
2	GC	Subcontractor (Compaction Testing)					
3	GC	Subcontractor (ACM Sampling)					
4	GC	Subcontractor (ACM Testing)					
5	GC	Subcontractor (DOL/OSHA Air Sampling)					
6	GC	Other Subcontractors					
7	220000	Sewer Cap					
8	220000	Water Cap					
9	015626	Temporary Fence					
10	312500	Silt Fence					
11	312500	Inlet Filter					
12	312500	Tracking Pad Material					
13	020590	Asbestos Abatement Plan					
14	020700	Demolition Plan					
15	020700	Materials Salvage & Recycling Management Plan					
16	GC	Construction Sequence					
17	GC	Schedule of Values					
18	020700	Rodent and Insect Pesticides SDS (MSDS)					
19	312300	Clean Fill Material Proctor and Gradation Analysis and Certification Letter					
20	329200	Imported Topsoil Material Certification Letter					
21	329200	Hydroseed Mix (Seed Type, etc.)					
	323200	UCC Tech Sheets, Certificate of Pesticide Application, Water & Sewer Disconnect					
22.01	020700	Letters and ACM All Clear Letter	576 Bamford Avenue				
	020700	UCC Tech Sheets, Certificate of Pesticide Application, Water & Sewer Disconnect					
22.02	020700	Letters and ACM All Clear Letter	640 Bamford Avenue				
	020700	UCC Tech Sheets, Certificate of Pesticide Application, Water & Sewer Disconnect					
22.03	020700	Letters and ACM All Clear Letter	88 Claire Avenue				
	020700	UCC Tech Sheets, Certificate of Pesticide Application, Water & Sewer Disconnect					
22.04	020700	Letters and ACM All Clear Letter	122 Harriot Street				
	020.00	UCC Tech Sheets, Certificate of Pesticide Application, Water & Sewer Disconnect					
22.05	020700	Letters and ACM All Clear Letter	661 Lewis Street				
		UCC Tech Sheets, Certificate of Pesticide Application, Water & Sewer Disconnect					
22.06	020700	Letters and ACM All Clear Letter	675 Lewis Street				
00.07		UCC Tech Sheets, Certificate of Pesticide Application, Water & Sewer Disconnect	070.1 . 0				
22.07	020700	Letters and ACM All Clear Letter	679 Lewis Street				
00.00		UCC Tech Sheets, Certificate of Pesticide Application, Water & Sewer Disconnect	OO Deet Deeding Assessed				
22.08	020700	Letters and ACM All Clear Letter	82 Port Reading Avenue				
22.00		UCC Tech Sheets, Certificate of Pesticide Application, Water & Sewer Disconnect	00 Dort Dooding Avenue				
22.09	020700	Letters and ACM All Clear Letter	88 Port Reading Avenue				
22.10		UCC Tech Sheets, Certificate of Pesticide Application, Water & Sewer Disconnect	7 Wedgewood Avenue				
22.10	020700	Letters and ACM All Clear Letter	7 Wedgewood Avenue				
23.01	020590	ACM Waste Manifests, ACM Removal Letter (RACM)	576 Bamford Avenue				
23.02	020590	ACM Waste Manifests, ACM Removal Letter (RACM)	640 Bamford Avenue				
23.03	020590	ACM Waste Manifests, ACM Removal Letter (RACM)	88 Claire Avenue				
23.04	020590	ACM Waste Manifests, ACM Removal Letter (RACM)	122 Harriot Street				
23.05	020590	ACM Waste Manifests, ACM Removal Letter (RACM)	661 Lewis Street				
23.06	020590	ACM Waste Manifests, ACM Removal Letter (RACM)	675 Lewis Street				
23.07	020590	ACM Waste Manifests, ACM Removal Letter (RACM)	679 Lewis Street				
23.08	020590	ACM Waste Manifests, ACM Removal Letter (RACM)	82 Port Reading Avenue				
23.09	020590	ACM Waste Manifests, ACM Removal Letter (RACM)	88 Port Reading Avenue				
23.10	020590	ACM Waste Manifests, ACM Removal Letter (RACM)	7 Wedgewood Avenue				
24.01	020700	Landfill Receipts For General Demolition	576 Bamford Avenue				
24.02	020700	Landfill Receipts For General Demolition	640 Bamford Avenue				
24.03	020700	Landfill Receipts For General Demolition	88 Claire Avenue				
24.04	020700	Landfill Receipts For General Demolition	122 Harriot Street				
24.05	020700	Landfill Receipts For General Demolition	661 Lewis Street				
2	020100		001 E01110 Olloot	I			

TRACKING #	SECTION #	DESCRIPTION	ADDRESS	DATE REC'D	REVIEW CODE	DATE APPROVED	NOTES
24.06	020700	Landfill Receipts For General Demolition	675 Lewis Street				
24.07	020700	Landfill Receipts For General Demolition	679 Lewis Street				
24.08	020700	Landfill Receipts For General Demolition	82 Port Reading Avenue				
24.09	020700	Landfill Receipts For General Demolition	88 Port Reading Avenue				
24.10	020700	Landfill Receipts For General Demolition	7 Wedgewood Avenue				
25.01	020700	Salvage & Recycling Receipts	576 Bamford Avenue				
25.02	020700	Salvage & Recycling Receipts	640 Bamford Avenue				
25.03	020700	Salvage & Recycling Receipts	88 Claire Avenue				
25.04	020700	Salvage & Recycling Receipts	122 Harriot Street				
25.05	020700	Salvage & Recycling Receipts	661 Lewis Street				
25.06	020700	Salvage & Recycling Receipts	675 Lewis Street				
25.07	020700	Salvage & Recycling Receipts	679 Lewis Street				
25.08	020700	Salvage & Recycling Receipts	82 Port Reading Avenue				
25.09	020700	Salvage & Recycling Receipts	88 Port Reading Avenue				
25.10	020700	Salvage & Recycling Receipts	7 Wedgewood Avenue				
26.01	020700	DOL/OSHA Sampling Results	576 Bamford Avenue	NA	NA	NA	
26.02	020700	DOL/OSHA Sampling Results	640 Bamford Avenue	NA	NA	NA	
26.03	020700	DOL/OSHA Sampling Results	88 Claire Avenue	NA	NA	NA	
26.04	020700	DOL/OSHA Sampling Results	122 Harriot Street	NA	NA	NA	
26.05	020700	DOL/OSHA Sampling Results	661 Lewis Street	NA	NA	NA	
26.06	020700	DOL/OSHA Sampling Results	675 Lewis Street	NA	NA	NA	
26.07	020700	DOL/OSHA Sampling Results	679 Lewis Street				
26.08	020700	DOL/OSHA Sampling Results	82 Port Reading Avenue	NA	NA	NA	
26.09	020700	DOL/OSHA Sampling Results	88 Port Reading Avenue				
26.10	020700	DOL/OSHA Sampling Results	7 Wedgewood Avenue	NA	NA	NA	
27.01	312300	Compaction Testing Results	576 Bamford Avenue				
27.02	312300	Compaction Testing Results	640 Bamford Avenue				
27.03	312300	Compaction Testing Results	88 Claire Avenue				
27.04	312300	Compaction Testing Results	122 Harriot Street				
27.05	312300	Compaction Testing Results	661 Lewis Street				
27.06	312300	Compaction Testing Results	675 Lewis Street				
27.07	312300	Compaction Testing Results	679 Lewis Street				
27.08	312300	Compaction Testing Results	82 Port Reading Avenue				
27.09	312300	Compaction Testing Results	88 Port Reading Avenue				
27.10	312300	Compaction Testing Results	7 Wedgewood Avenue				
28	GC	HUD/CDBG-DR - Contractor Information Form					
29	GC	HUD/CDBG-DR - Business Contact Log					
30	GC	HUD/CDBG-DR - Community Outreach Log					
31	GC	HUD/CDBG-DR - Section 3 Business Certification					
32	GC	HUD/CDBG-DR - Section 3 Resident Certification					
33	017800	Closeout Submittal DPMC 11(Final Invoice), 11.2 (SOV) & 11.2a (Cert Prime)					
34	017800	Closeout Submittal DPMC 20 Final Contract Acceptance					
35	017800	Closeout Submittal DPMC 20r(2) ORIGINAL Consent of Surety w/raised seal (cannot be emailed)					
36	017800	Closeout Submittal DPMC 20d Certificate of Substantial Completion					
37	017800	Closeout Submittal One (1) Year Performance Warranty					


REVIEW CODE KEY:

APP = APPROVED REJ = REJECTED

AAN = APPROVED AS NOTED NR = NOT REVIEWED

R = REVIEWED NA = NOT APPLICABLE

RFR = RETURNED FOR RESUBMISSION RR = RECEIVED FOR RECORD



[CONTRACTOR LETTERHEAD]

[DATE]

William Byster
NJ Department of Treasury
Division of Property Management & Construction (DPMC)
Bureau of Design and Construction
33 West State Street, 9th Floor
Trenton, NJ 08625-0235

Re: Contractor Warranty

Demolition of Dwellings: DPMC Project No. P1121-12

640 Bamford Avenue, 576 Bamford Avenue, 88 Claire Avenue, 122 Harriot Street, 661 Lewis Street, 676 Lewis Street, 679 Lewis Street, 82 Port Reading, 88 Port Reading, 7 Wedgewood Avenue (Woodbridge Township, Middlesex County, NJ)

By this letter, the undersigned Contractor guarantees and warrants the Work performed and all materials furnished under the above-referenced Contract against defects in materials and/or workmanship, and agrees to be responsible for the value or repair of any damage to other Work or to the building premises resulting from the performance of the Contract, for a period of one (1) year from the date of Substantial Completion for Beneficial Use established in 7.2.2 of the Contract General Conditions, or from the time of completion and acceptance of the equipment, work or materials in question, whichever is later.


This written guarantee and warranty is provided in addition to, and not in place of, any and all other guarantees and warranties established under the Contract documents and/or applicable law.

<u> </u>	
Signature	
Name	

Sincerely,

Title

Contractor Company Name



Contractor Information Form

ckground Informa	tion	-	
1. Company			
Name		_	4. Date Submitted
2. Contact Name			5. Reporting Period
3. Contact Number			
	6. Are you a Section 3		1
	Business?		
rt I: Listing of Pro	jects Contractor is Working On		
A	В	C	_
Project Name	Contract Value	HUD-60002 Type of Work	
		WOIK	
			1
			1
			1
			-
			J
rt II: Employee In			
A	В	С	7
Number of New	Number of New Hires that are	Number of Section 3	
Hires	Section 3	Employees and Trainees	

Part III: Subcontractors

(leave blank if no subcontractors have been hired)

A	D	C	D
Subcontractor Name	Is the subcontractor working on construction or non-construction work?	Is the subcontractor a Section 3 Business?	Contract Value

R

Part IV: Summary of Outreach Efforts

Indicate the efforts made to direct the employment and other economic opportunities generated by HUD financial assistance for housing and community development programs, to the greatest extent feasible low- and very-low income persons, particularly those who are recipients of government assistance for housing. Check all that apply.

- Attempted to recruit low-income residents through: local advertising media, signs prominently displayed at the project site, contracts with the community organizations and public or private agencies operating within the metropolitan area (or Nonmetropolitan County) in which the Section 3 covered program or project is located or similar methods.
- Participated in HUD program or other program which promotes the training or employment of Section 3 residents.
- Participated in HUD program or other program which promotes the award of contracts to business concerns which meet the definition of D Section 3 business concerns.
- Coordinated with Youthbuild Program administered in the metropolitan area in which the Section 3 covered project is located.
- D Other; describe below

SECTION 3 BUSINESS CONTACT LOG

Project Name:			Project Number:					
Company Name	Company Name:							
construction to raffix documents	ecord contact wit	ch businesses. Red n efforts (e.g. proo	iod of the solicitat cord all efforts use of of mailing, fax t	ed to meet Section	3 obligations and			
Date / Time	Company	Method of Contact	Contact Person	Other Efforts	Results of Communication			
	•							

SECTION 3 COMMUNITY OUTREACH CONTACT LOG

Project Name:				Project Nun	nber:
Company Nam	e:				
construction to and affix docum	ecord communit	y outreach efforts such efforts (e.g.	s. Record all effe	itation phase and ent orts used to meet Sec g, fax transmittal, e-r	etion 3 obligations
Date / Time	Company	Method of Contact	Contact Person	Other Efforts	Results of Communication

CERTIFICATION FOR BUSINESS CONCERNS SEEKING SECTION 3 PREFERENCE IN CONTRACTING AND DEMONSTRATION OF CAPABILITY

Name of Business			
Address of Business			
Type of Business: D Corporation	O Partnership	D Sole Proprietorship	D Joint Venture
Attached is the following documentation	on as evidence of	f status:	
For Business claiming status as a Sec	tion 3 resident-	owned enterprise:	
D Copy of resident lease	D Copy of re	ceipt of public assistance	
D Copy of evidence of participation in	a public assistar	nce program	
D Other evidence			
For business entity as applicable:			
D Copy of Articles of Incorporation			
D Certificate of Good Standing			
D Assumed Business Name Certificate	;		
D Partnership Agreement			
D List of owners/stockholders and % o	wnership of eac	h	
D Corporation Annual Report			
D Latest Board minutes appointing off	icers		
D Organization chart with names and t	itles and brief fu	nction statement	
D Additional documentation			
For business claiming Section 3 statu qualified Section 3 business:	s by subcontrac	cting 25 percent of the do	llar awarded to
D List of subcontracted Section 3 busin if a relationship has already been establimentioned.	` '	_	•

SECTION 3 BUSINESS CONCERN CERTIFICATION PAGE 2

For business claiming Section 3 status, claiming at least 30 percent of their workforce are currently Section 3 residents or were Section 3 eligible residents within 3 years of date of first employment with the business:
D List of all current full-time employees
D List of employees claiming Section 3 status
D PHA/IHA Residential lease less than 3 years from date of first employment
D Other evidence of Section 3 status less than 3 years from date of first employment
Evidence of ability to perform successfully under the terms and conditions of the proposed contract:
D Current financial statement
D Statement of ability to comply with public policy
D List of owned equipment
D List of all contracts for the past two years
(Corporate Seal) (Authorizing Name and Signature)
Attested by:

SECTION 3 RESIDENT CERTIFICATION FORM

Eligibility for Preference

A Section 3 resident seeking the preference in training and employment provided by this part shall certify, or submit evidence to the recipient contractor or subcontractor, if requested, that the person is a Section 3 resident, as defined in 24 CFR Part 135.5. (An example of evidence of eligibility for the preference is evidence of receipt of public assistance, or evidence of participation in a public assistance program. Additional documentation supporting eligibility will be submitted upon request.)

Certification for Resident Seeking Section 3 Preference in Training and Employment

Ι,	, am a legal resident of the
	and meet HUD's income eligibility
guidelines for a low- or very low-income person.	
I am currently employed by:	
My date of first employment with this company v	was: (month/year)
My permanent address is:	
I have attached the following documentation as e	
D Copy of lease	D Copy of receipt of public assistance
D Copy of Evidence of participation	D Other evidence
Signature)	(Date)
Printed name)	

SECTION 3 RESIDENT CERTIFICATION PAGE 2

SECTION 3 INCOME LIMITS			
All residents of public housing developments of the			
	Housing Au	thority qualify as Section 3	
residents.			
Additionally, individuals residing in the(City/County) of who meet the income limits set forth below can also qualify for Section 3 status.			
A picture identification card an	nd proof of current residency is	required.	
Eligibility Guideline			
Number in Household	Very Low Income	Low Income	
1 Individual			
2 Individuals			
3 Individuals			
4 Individuals			
5 Individuals			
6 Individuals			
7 Individuals			
8 Individuals			

The HUD income limits can be found at http://www.huduser.org/portal/datasets/il.html

SAMPLE / FOR CONTRACTOR'S USE

SECTION 3 COMPLIANCE CHECKLIST


For recommended use by Contractors and Sub-contractors.

Creation of Action Plan	Yes / No	Date Complete
1. Contractor has designated a Section 3 compliance officer/contact for the project		
2. Contractor attended the project's pre-bid meeting		
3. Contractor attended the project's pre-construction meeting		
4. The Contractor's Section 3 Plan was approved by the State.		
5. Sub-contractors with contracts in excess of \$100,000 have each submitted a		
complete Section 3 Action Plan		

Soliciting Bids / Contracting	Yes / No	Date Complete
1. A list of certified Section 3 business concerns from the metropolitan Housing		
Authority has been obtained		
2. Solicited bids from the list of Section 3 businesses for each service that requires		
sub-contracts (ensure adequate time for the business to respond and/or submit a		
proposal or bid)		
3. Provided plans and specifications or information regarding the location of plans		
and specifications to Section 3 business concerns		
4. Efforts to sub-contract Section 3 business concerns have been recorded.		
5. Efforts and their results have been included with the project's bid packet		

Compliance	Yes / No	Date Complete
1. Quarterly Section 3 compliance reports have been submitted to the State		
2. Section 3 businesses utilized for the project were identified		
3. All contractors and new hires utilized for the project were identified		
4. The existing core workforce list or a certified payroll has been submitted to the		
State's Section 3 Coordinator		

Impediments, Concerns, Enforcement	Yes / No	Date Complete
1. Efforts taken and the impediments encountered in trying to satisfy Section 3		
requirements have been documented		



Asbestos Abatement Contractor Letterhead

Date

William Byster
NJ Department of Treasury
Division of Property Management and Construction (DPMC)
Bureau of Design and Construction
33 West State Street, 9th Floor
Trenton, NJ 08625-0235

Re: Certification of Asbestos Abatement (property address)

Demolition of Dwellings: DPMC Project No. P1121-12

Dear Mr. Byster,


This letter hereby certifies that all required asbestos hazard abatement work has been performed in accordance with Specification Section 020590 Removal of Asbestos Materials within the Contract Documents. All work was completed in accordance with all Federal, State and Local regulations; air monitoring requirements were successfully completed and passed in accordance with N.J.A.C. 12:120 Asbestos Licenses and Permits; and all asbestos waste material has been properly disposed of per all Federal, State and Local regulations.

I am fully authorized to make these certifications and warranties.

Asbestos Abatement Contractor

New Jersey Asbestos Contractor License Number:

Name: _	Title/Company:_
Address: _	Phone: _
Signature:	Date:



Prime Contractor Letterhead

William Byster
NJ Department of Treasury
Division of Property Management and Construction (DPMC)
Bureau of Design and Construction
33 West State Street, 9th Floor
Trenton, NJ 08625-0235


Re: Certification of Clean Fill Material

Demolition of Dwellings Middlesex County, NJ DPMC Project No. P1121-12

Dear Mr. Byster,

This letter hereby certifies and warrants the imported fill material to be utilized for DPMC Project No. P1121-12 meets the requirements of "Fill Material" and is from a virgin source or meets the most stringent requirements of the New Jersey Residential, Non-Residential, and Impact to Groundwater Standards in accordance with Specification Section 312300 Excavation, Backfilling, and Grading within the Contract Documents. Samples of the imported fill material were collected in accordance with the NJDEP Regulations, including Technical Regulations (NJAC 7:26E-2), and that sample collection has been performed in accordance with the NJDEP's Field Sampling Procedures Manual. Results of sampling shall be made available upon request.

Address of Su	upply Location:		
I am fully aut	horized to make these certific	cations and warranties.	
<u>Prime Contra</u>	<u>actor</u>		
Name:	-	Title/Company: _	
Address:	-		Phone: _
Signature:	-	Date:	
Fill Material S	<u>Supplier</u>		
Name:	-	Title/Company: _	
Address:	-		Phone: _
Signature:	-	Date:	
<u>Licensed Site</u>	Remediation Professional (L	SRP)	
Name:	-	Title/Company: _	
Address:	-		Phone: _
Signature:	_	Date:	



Prime Contractor Letterhead

William Byster NJ Department of Treasury Division of Property Management and Construction (DPMC) Bureau of Design and Construction 33 West State Street, 9th Floor Trenton, NJ 08625-0235


Re: Certification of Imported Topsoil Material


Demolition of Dwellings Middlesex County, NJ DPMC Project No. P1121-12

Dear Mr. Byster,

This letter hereby certifies and warrants the imported topsoil material to be utilized for DPMC Project No. P1121-12 meets the requirements of "Composition" in accordance with Specification Section 329200 Turf and Grasses within the Contract Documents.

Address of Supply Location:			
I am fully authorized to make these co	ertifications and warranties.		
<u>Prime Contractor</u>			
Name:	Title/Company:		
Address:		Phone:	
Signature:	Date:		
Topsoil Material Supplier			
Name:	Title/Company:		
Address:		Phone:	
Signature:	Date:		





Mr. Byster,

The Office of Asbestos Control and Licensing has approved your office's waiver request for asbestos abatement work performed during demolition of private residences under the Blue Acres program. The asbestos abatement contractors performing the work should submit a copy of your letter when notifying each project to our office. If I can be of any further assistance, please do not hesitate to contact me.

Regards,

Thomas P. Voorhees
New Jersey Department of Labor and Workforce Development
Occupational Health & Safety, Inspection & Enforcement
1 John Fitch Plaza 3rd Floor
P.0. Box 949
Trenton, New Jersey 08625
Phone 609-633-2159
Fax 609-633-0664



State of New Jersey
DEPARTMENT OF TREASURY
DIVISION OF PROPERTY MANAGEMENT & CONSTRUCTION
P O Box 034
TRENTON NJ 08625-0034

ELIZABETH MAHER MUOIO State Treasurer

CHRISTOPHER CHIANESE Director

SHEILA Y. OLIVER Lt. Governor

PHILIP D. MURPHY

Governor

November 16th, 2018

Mr. Thomas Voorhees Asbestos Control and Licensing New Jersey Department of Labor John Fitch Plaza, 3rd Floor P.O. Box 949 Trenton, NJ 08625-0949

Re: Blue Acres - Superstorm Sandy Demolition Project

Dear Mr. Voorhees:


I am writing on behalf of the New Jersey Division of Property Management and Construction (DPMC) to request a waiver of the requirement to provide ten days advance notice of asbestos abatement work performed during demolition of private residences under the Blue Acres program. Blue Acres is a federally-funded (FEMA) and (HUD) program whereby the New Jersey Department of Environmental Protection (DEP) has been acquiring title to houses to be demolished in flood-prone areas of the State ravaged by Hurricane Sandy. We currently anticipate that the program will eventually require demolition of upwards of 2,000 houses throughout the State. DPMC has been tasked with managing and overseeing the demolition.

FEMA and HUD have imposed tight deadlines upon this program, requiring the demolition of each structure to be completed within 90 days after DEP closes on the properties. Within this brief 90 day period we must award a professional service contract for design of the demolition plan along with a construction contract for the actual demolition work while obtaining all local and county approvals, arrange for utility disconnects and complete the actual demolition. The requirement to build an additional ten days advanced notice into this current schedule substantially jeopardizes our ability to complete this work within this time period in order to continue to qualify for federal funding.

Please accept our request to waive the ten day notification requirement for the demolition of dwellings under this program.

Respectfully,
William Byster
Program Manager
Department of Property Management & Construction

Cc: Richard Flodmand, Deputy Director; James Langsdorf, Deputy Director; Wayne Martorelli, Assistant Deputy Director



BID PROPOSAL FORM

STATE OF NEW JERSEY
DEPARTMENT OF TREASURY
DIVISION OF PROPERTY MANAGEMENT & CONSTRUCTION
P O BOX 034
TRENTON NEW JERSEY 08625-0034

The bid proposal is to be returned in the pre-addressed envelope and will be accepted no later than 2:00 p.m., October 29, 2019 after which time the bid proposals will be publicly opened and read. FIRM NAME: (Please Type or Print) (Business Street Address ONLY - No P O Box) PROJECT NO P1121-12 PROJECT: Demolition of Residential Dwellings LOCATION: 576 Bamford Ave., 640 Bamford Ave., 88 Claire Ave., 122 Harriot St., 661 Lewis St., 675 Lewis St., 679 Lewis St., 82 Port Reading Ave., 88 Port Reading Ave., 7 Wedgewood Ave., Woodbridge, NJ COUNTY: Middlesex The undersigned Single Prime Contractor proposes to be responsible for all work shown in the contract plans and specifications. X Single Bid lump sum all trades (Numerical Figures Only) In accordance with N.J.S.A. 52:35-1 et seq., the Contractor will be classified with the Division of Property Management and Construction (DPMC) in one of the following trades: General Construction (C008) or General Construction/ Alterations and Additions (C009) or Demolition (C021) The proposal is based upon the bid documents listed below. 1. General Conditions revised: December 2015 2. Specifications dated: September 2019 3. Drawing(s)#: Included in the Specifications Dated: Included in the Specifications This project will be fully completed and ready for occupancy within 65 Calendar days. Liquidated damages will be assessed at 1/20 of one percent (.05%) of the value of this contract (minimum of \$250.00). The above price is good through sixty (60) days after the bid opening date. Submit only one bid proposal and bid bond form. A bid bond in the amount of fifty percent (50%) of the TOTAL bid, including alternates if applicable, must accompany this proposal form.

PROJECT NO.: <u>P1121-12</u>

The Contractor must include prices for the base bid and all alternates and unit prices when requested, otherwise the bid may be considered non-responsive.

Having examined the bid documents and the site of the proposed work and being familiar with all of the conditions surrounding the construction of the proposed project including the availability of materials and labor, the Contractor hereby proposes to furnish all labor, materials and supplies, and to construct the project as submitted, within the time set forth therein, and at the price stated. This price is to cover all expenses incurred in performing the work required, of which this proposal is a part.

The Contractor acknowledges and affirms that it has personal knowledge of or has obtained and reviewed a copy of the valid prevailing wage rates for all trades involved in the project for the geographical location of the project as issued by the Commissioner of the Department of Labor, P O Box 389, Trenton, New Jersey, 08625 (609) 292-2259.

The Contractor acknowledges receipt of the following Bulletins:

BULLETIN NUMBER	DATE OF BULLETIN
A	September 26, 2019

The names and addresses of each Subcontractor included in this Single Bid proposal are listed below and are classified with DPMC in accordance with N.J.S.A. 52:35-1 et seq. at the time of the bid due date. If the Single Prime contractor intends to perform the work described under any of the listed trades sections of this bid proposal form, that Single Prime Contractor must be classified in that trade and listed in the appropriate Subcontractor section of this bid proposal. The Contractor acknowledges the failure to list classified Subcontractors as part of Single Bid proposals shall constitute a non-waivable material deviation resulting in a rejection of the bid.

DEMOLITIO	ON (C021)
NAME:	
ADDRESS:	
PLUMBING	G (C030)
NAME:	
ADDRESS:	
ASBESTOS I	REMOVAL/TREATMENT (C092)
NAME:	
ADDRESS:	

ALLOWANCES

There are NO allowances in this bid.

EXECUTION OF CONTRACT

Upon receipt of written notice of the acceptance of this bid, the Contractor shall execute the formal contract within 10 calendar days and deliver a Performance and Payment Bond as well as other information as required in the bid solicitation.

COMMENCEMENT OF WORK

Contractor acknowledges that the work is to commence upon receipt of the Notice to Proceed with the exception of permit activities.

BID SECURITY

Bid Bond is fifty percent (50%) of the TOTAL bid, including alternates if applicable, and is to become the property of the State in the event the contract and bond are not executed within the time set forth as liquidated damages for the delay and additional expense incurred by the Owner.

CERTI	FI	CAT	TO	N

approved amount of	S	for (trade)		unti	1
	(expiration date).				
consideration of uncon	nis firm's bid for this project doe inpleted construction work (plea ct work is discounted 85% for pr	se refer to N I A (' 1'	7.10 2 12 mbia	la dassail - 1	4.70
		Respectfully su	bmitted,		
Seal-if Bid proposal i	s by a corporation)				
		By:			
			(Name of	f Firm)	
) 	(Signat	ture)	
		Ş	(Titl	e)	
		(Business	Street Address	ONLY – No P O Ba	ox)
		(City	State	County	Zip)
		Phone No.			
		Fax No.			
ederal Identification N	Jo				
ederal identification i					
any change in ownersh	ip information since filing your	Request for Classifica	ntion (Form DP	MC 27)	
Yes					
☐ No					

PROPOSAL PAGE 4 OF 8

PROJECT: Demolition of Residential Dwellings

STATE OF NEW JERSEY DEPARTMENT OF TREASURY DIVISION OF PROPERTY MANAGEMENT & CONSTRUCTION

NON-COLLUSION AFFIDAVIT

576 Bamford Ave 679 Lewis St., 82 Middlesex Count	Port Reading	rd Ave., 88 Claire Ave., 122 H Ave., 88 Port Reading Ave., 7	arriot St., 661 Lewis S Wedgewood Ave., Wo	t., 675 Lewis St., oodbridge,
		Bid Due Date	October 29, 2019	2:00 PM
STATE OF NEW JERSEY	1		1	
	[SS.			
COUNTY OF	1			
I,		of the City of		
in the County of		and the State of		
of full age, being duly sworn acc	cording to law	on my oath depose and say tha	t:	
I am				
of the firm of				
the Contractor making the Bid Prauthority so to do; that said Cont collusion, or otherwise taken any project; and that all statements cofull knowledge that the State of Nother statements contained in this a	ractor has not, action in restr ontained in said New Jersey reli	directly or indirectly, entered is aint of free, competitive biddired bid proposal and in this affidations are the statement ties upon the truth of the statement	nto any agreement, par ng in connection with the avit are true and correct ents contained in said I	ticipated in any
		SIG	NATURE OF PRINC	CIPAL
Subscribed and sworn to before r	ne this	day		
of 20 ,				
AL . B. C.				
Notary Public				
My Commission expires				

Bidder:

Public Law 2005, Chapter 92

Formerly: Executive Order 129

In accordance with Public Law 2005, Chapter 92 (N.J.S.A. 52:34-13.2 et seq., superseding Executive Order 129 (2004)) all bidders submitting a proposal shall be required to submit a Source Disclosure Certification that all services will be performed in the United States. The bidder shall disclose the location by country where services under the contract will be performed and any subcontracting of services under the contract and the location by country where any subcontracted services will be performed.

SOURCE DISCLOSURE CERTIFICATION FORM

I hereby certify and say:		
I have personal knowledge of t. Bidder.	he facts set forth herein and am au	horized to make this Certification on behalf of the
State of New Jersey, Departm	ent of Treasury. Division of Pror	esponse to the referenced solicitation issued by the perty Management and Construction (DPMC), in (N.J.S.A. 52:34-13.2 et seq., superseding Executive
The following is a list of every	location where services will be per	formed by the bidder and all subcontractors.
Bidder or Subcontractor	Description of Services	Performance Location(s) by Country
Department of Treasury, State of I understand that, after award of above to be provided within the the Director, Division of Proper of services or that the failure to Bidder shall be deemed in breach with DPMC. I further understand that this Ce	f New-Jersey, PO Box 034, Trento f New-Jersey, PO Box 034, Trento a contract to the Bidder, it is determined States to sources outside the ty Management and Construction, shift the services would result in ear of contract, which contract will be retification is submitted on behalf or	mined that the Bidder has shifted services declared a United States, prior to a written determination by that extraordinary circumstances require the shift conomic hardship to the State of New Jersey, the subject to termination for cause under its contract
contained north.	nat the State of New Jersey and Di	f the Bidder in order to induce DPMC to accept a PMC are relying upon the truth of the statements
	nat the State of New Jersey and Dl	PMC are relying upon the truth of the statements
I certify that, to the best of my k of the statements are willfully fa	nat the State of New Jersey and Dl nowledge and belief, the foregoing lse, I am subject to punishment.	PMC are relying upon the truth of the statements
I certify that, to the best of my k of the statements are willfully fa	nat the State of New Jersey and Dl nowledge and belief, the foregoing lse, I am subject to punishment.	PMC are relying upon the truth of the statements
I certify that, to the best of my k of the statements are willfully fa	nowledge and belief, the foregoing lse, I am subject to punishment. zation or Entity]	f the Bidder in order to induce DPMC to accept a PMC are relying upon the truth of the statements statements by me are true. I am aware that if any Title:

STATE OF NEW JERSEY DIVISION OF PROPERTY MANAGEMENT AND CONSTRUCTION DISCLOSURE OF INVESTMENT ACTIVITIES IN IRAN

Pursuant to Public Law 2012, c. 25, any person or entity that submits a bid or proposal or otherwise proposes to enter into or renew a contract must complete the certification below to attess penalty of perjury, that neither the person or entity, nor any of its parents, subsidiaries, or affiliates, identified on the Department of Treasury's Chapter 25 list as a person or entity engaging in investing activities in Iran. The Chapter 25 list is found on the Division of Purchase and Property's website a http://www.state.ni.us/treasury/purchase/pdf/Chapter25List.pdf. Bidders must review this list prior completing the below certification. Failure to complete the certification may render a bidder's proposal non-responsive. If the Director finds a person or entity to be in violation of law, s/he she action as may be appropriate and provided by law, rule or contract, including but not limited to, imposanctions, seeking compliance, recovering damages, declaring the party in default and seeking debarment or suspension of the party. PLEASE CHECK THE APPROPRIATE BOX: I certify, pursuant to Public Law 2012, c. 25, that neither the bidder listed above nor any of bidder's parents, subsidiaries, or affiliates is listed on the N.J. Department of the Treasury's list of edetermined to be engaged in prohibited activities in Iran pursuant to P.L. 2012, C. 25 ("Chapter 25 I further certify that I am the person listed above, or I am an officer or representative of the entity list above and am authorized to make this certification on its behalf. I will skip Part 2 and sign and complete the Certification below. OR I am unable to certify as above because the bidder and/or one or more of its parents, subsidiaries, or affiliates is listed on the Department's Chapter 25 list. I will provide a detailed, accurant precise description of the activities in Part 2 below and sign and complete the Certification beloef aliure to provide such will result in the proposal being rendered as non-responsive and appropriate penalties, fines and/or sanc	
I certify, pursuant to Public Law 2012, c. 25, that neither the bidder listed above nor any of bidder's parents, subsidiaries, or affiliates is listed on the N.J. Department of the Treasury's list of edetermined to be engaged in prohibited activities in Iran pursuant to P.L. 2012, C. 25 ("Chapter 25 I further certify that I am the person listed above, or I am an officer or representative of the entity lis above and am authorized to make this certification on its behalf. I will skip Part 2 and sign and complete Certification below. OR I am unable to certify as above because the bidder and/or one or more of its parents, subsidiaries, or affiliates is listed on the Department's Chapter 25 list. I will provide a detailed, accurant precise description of the activities in Part 2 below and sign and complete the Certification below. Failure to provide such will result in the proposal being rendered as non-responsive and appropriate penalties, fines and/or sanctions will be assessed as provided by law. Part 2: PLEASE PROVIDE FURTHER INFORMATION RELATED TO INVESTMENT ACTIVITIES I	is ent o II take
bidder's parents, subsidiaries, or affiliates is listed on the N.J. Department of the Treasury's list of edetermined to be engaged in prohibited activities in Iran pursuant to P.L. 2012, C. 25 ("Chapter 25 I further certify that I am the person listed above, or I am an officer or representative of the entity lis above and am authorized to make this certification on its behalf. I will skip Part 2 and sign and complete the Certification below. OR I am unable to certify as above because the bidder and/or one or more of its parents, subsidiaries, or affiliates is listed on the Department's Chapter 25 list. I will provide a detailed, account and precise description of the activities in Part 2 below and sign and complete the Certification belowallure to provide such will result in the proposal being rendered as non-responsive and appropriate penalties, fines and/or sanctions will be assessed as provided by law. Part 2: PLEASE PROVIDE FURTHER INFORMATION RELATED TO INVESTMENT ACTIVITIES I	
I am unable to certify as above because the bidder and/or one or more of its parents, subsidiaries, or affiliates is listed on the Department's Chapter 25 list. I will provide a detailed, accurant precise description of the activities in Part 2 below and sign and complete the Certification below Failure to provide such will result in the proposal being rendered as non-responsive and appropriate penalties, fines and/or sanctions will be assessed as provided by law. Part 2: PLEASE PROVIDE FURTHER INFORMATION RELATED TO INVESTMENT ACTIVITIES I	ntities ist"). ed
subsidiaries, or affiliates is listed on the Department's Chapter 25 list. I will provide a detailed, accurant precise description of the activities in Part 2 below and sign and complete the Certification below Failure to provide such will result in the proposal being rendered as non-responsive and appropriate penalties, fines and/or sanctions will be assessed as provided by law. Part 2: PLEASE PROVIDE FURTHER INFORMATION RELATED TO INVESTMENT ACTIVITIES I	
Part 2: PLEASE PROVIDE FURTHER INFORMATION RELATED TO INVESTMENT ACTIVITIES I	ate /.
IRAN	1
You must provide a detailed, accurate and precise description of the activities of the bidding person/entity, or one of its parents, subsidiaries or affiliates, engaging in the investment activities in butlined above by completing the box(es) below.	an ·
Name Relationship to Bidder/Offeror	
Description of Activities	
Duration of Engagement Anticipated Cessation Date	
Bidder/Offeror Contract Name Contact Phone Number	

List Additional Activities on Separate Sheet

P.L. 2012 c. 25

CERTIFICATION: I, being duly sworn upon my oath, hereby represent and state that the foregoing information and any attachments thereto to the best of my knowledge are true and complete. I attest that I am authorized to execute this certification on behalf of the above-referenced person or entity. I acknowledge that the State of New Jersey is relying on the information contained herein and thereby acknowledge that I am under a continuing obligation from the date of this certification through the completion of any contracts with the State to notify the State in writing of any changes to the answers of information contained herein. I acknowledge that I am aware that it is a criminal offense to make a false statement or misrepresentation in this certification, and if I do so, I recognize that I am subject to criminal prosecution under the law and that it will also constitute a material breach of my agreement(s) with the State of New Jersey and that the State at its option may declare any contract(s) resulting from this certification void and unenforceable.

Full Name (Print):	Signature;	
Title:	Date:	

CONTRACT

THIS AGREEM!	NT, made this	day c	of	_, 2018
			herein c	alled "owner," acting herein through its
(Corpo	orate Name of Own	ier)		
	Division of Prope	rty Management (Title of Autl		ction, Deputy Director and (ial)
(a corporation)				
of	City of ID#XXXXXXXX	X00) County o	ſ	, and State of New Jersey hereinafter
	OWNER, the CO			and agreements hereinafter mentioned, to be made with the OWNER to commence and complete the
CONTRACT PROJEC	XXX XXX	XX-XX-CC01 XXXXXXXXX XXXXXXXXXXXXXXX XXXXX, COUN	X	XXXXX, NEW JERSEY
LUMP SUM BID			****************	
SPECIFICATIONS:	Dated XX-XX	-XX included as	part of this o	contract
UNIT PRICES:	Unit prices sul contract	omitted on XXX.	XXXX of the	2 Bid Proposal Form, included as part of this
BULLETINS:	XXXXXXXX	X have been ack	nowledged b	y the bidder and included as part of this contract
GEN.CONDITIONS:	Instructions to of this contrac		eral Condition	ns revised December 2015, included as part
DRAWINGS:	See Cover She	eet and Drawing	Index dated I	XX-XX-XX, included as part of this contract
POST BID REVIEW CERTIFICATION:	Dated XX-XX	-XX, included a	s part of this	contract
*Refer to Page 3.				
Specifications, and at equipment, tools, superproject in accordance General Conditions an prints, and other draw therefore as prepared and collectively evider. The contractor hereby	his (its or their) of crintendent, labor, with the condition of Special Condition ings and printed of special constitute the agrees to commer	win proper cost insurance, and cons and prices stands of the Contract written explanation herein entitly he contract.	and expense other accessorated in the I of Specificat dory matter led the Archi	Dollars (\$000,000.00) and all extra General and Special Conditions of the Contract to furnish all the materials, supplies, machinery, pries and services necessary to complete the said Proposal, the General Conditions, Supplementary tons, the plans, which include all maps, plats, blue thereof, the specifications and contract documents teet/Engineer, all of which are made a part hereof ton (See Notice to Proceed) and to fully complete of the essence for the completion of this contract.
	agrees to pay, as	liquidated dama	ages, the sur	n of \$000.00, for each consecutive calendar day
	ns, as provided in	the General Con-	ditions of the	s for the performance of the contract, subject to Contract Specification, and to make payments on

Only domestic materials shall be acquired or used for any public work unless the head of the department, or other public officer charged with the duty by law, shall determine it to be inconsistent with the public interest, or the cost to be unreasonable, or domestic materials of the class or kind to be used are not mined, produced or manufactured, as the case may be, in the United States in commercial quantities and of a satisfactory quality.

The Contractor shall conform to all provisions of "Law Against Discrimination" (P.L.1975,e.,127; N.J.S.A. 10:5-1 et seq.).

IN WITNESS WHEREOF, the parties to these presents have executed this contract in four (4) counterparts, each of which shall be deemed an original, in the year and day first above mentioned.

ATTEST:		DIVISION OF PROPERTY MANAGEMENT AND CONSTRUCTION
(Witness)	By	
(Tribless)		(Title)
(Affix Corporate Seal)		
		(Contractor)
(Witness)	Ву	
V. M.		PRESIDENT (Title)
		(Address)

WARRANTY:

It is hereby certified and warranted by the undersigned contractor and by the undersigned principals or officers thereof, for said Contractor and for themselves, personally and individually, that no person has been employed to solicit or secure this Contract in violation of the provisions of Section 10. Chapter 48 of the Laws of 1954, N.J.S.A. 52:34-15, or in violation of any other laws of the State of New Jersey; and it is further warranted that all applicable laws and regulations shall be complied within the performance of this contract.

Please be advised that pursuant to N.J.S.A. 54:49-19 et seq. and notwithstanding any provision of the law to the contrary, whenever any taxpayer, partnership or S corporation under contract to provide goods or services or construction projects to the State of New Jersey or its agencies or instrumentalities, including the legislative and judicial branches of State government, is entitled to payment for those goods or services at the same time the taxpayer, partner or shareholder of that entity is indebted for any State tax, the Director of the Division of Taxation shall seek to set off so much of that payment as shall be necessary to satisfy the indebtedness. The amount set-off shall not allow for the deduction of any expense or other deductions which might be attributable to the taxpayer, partner, or shareholder subject to set-off under this Act.

The Director of the Division of Taxation shall give notice of the set-off to the taxpayer, partner or shareholder and provide an opportunity for a hearing within 30 days of such notice under the procedures for protests established under N.J.S.A. 54:49-18. No request for conference, protest, or subsequent appeal to the Tax Court from any protest shall stay the collection of the indebtedness. Interest that may be payable by the State, pursuant to P.L. 1987, c 184 (c. 52:32-32 et. seq. to the taxpayer shall be stayed.

By signing this contract, I certify, pursuant to N.J.S.A. 52:34-12.2, that the entity for which I am authorized to bid:

has no ongoing business activities in Northern Ireland and does not maintain a physical presence therein through the operation of offices, plants, factories, or similar facilities, either directly or indirectly, through intermediaries, subsidiaries or affiliated companies over which it maintains effective control; or

will take lawful steps in good faith to conduct any business operations it has in Northern Ireland in accordance with the McBride principles of nondiscrimination in employment as set forth in N.J.S.A. 52:18A-89.5 and in conformance with the United Kingdom's Fair Employment (Northern Ireland) Act of 1989, and permit independent monitoring of their compliance with those principles.

I certify that the foregoing statements made by me are true. I am aware that if any of the foregoing statements made by me are willfully false, I am subject to punishment.

Affix Corporate Scal)		
		(Contractor)
	13 y	
(Witness)		PRESIDENT
		(Title)
		(Address)

This contract conforms to the standard form approved by the Attorney General.

GURBIR S. GREWAL ATTORNEY GENERALOF NEW JERSEY

* Current Wage Rates dated XX-XX-XX and are included as part of this contract.

"THE MINORITY PERCENTAGE GOAL REQUIREMENT FOR THIS CONTRACT IS $\underline{XX\%}$ PER SKILLED CRAFT."

"THE FEMALE PERCENTAGE GOAL REQUIREMENT FOR THIS CONTRACT IS $\underline{6.9\%}$ PER SKILLED CRAFT."

"(The contract partner) shall maintain all documentation related to products, transactions or services under this contract for a period of five years from the date of final payment. Such records shall be made available to the New Jersey Office of the State Comptroller upon request."

EXHIBIT B

(Revised December 2010) MANDATORY EQUAL EMPLOYMENT OPPORTUNITY LANGUAGE N.J.S.A. 10:5-31 et. seg. (P.L. 1975, C. 127) N.J.A.C. 17:27-7.2

CONSTRUCTION CONTRACTS

During the performance of this contract, the contractor agrees as follows:

- a. The contractor or subcontractor, where applicable will not discriminate against any employee or applicant for employment because of age, race, creed, color, national origin, ancestry, marital status, affectional or sexual orientation, gender identity or expression, disability, nationality or sex. Except with respect to affectional or sexual orientation and gender identity or expression, the contractor will ensure that equal employment opportunity is afforded to such applicants in recruitment and employment, and that employees are treated during employment, without regard to their age, race, creed, color, national origin, ancestry, marital status, affectional or sexual orientation, gender identity or expression, disability, nationality or sex. Such equal employment opportunity shall include, but not be limited to the following; employment, up-grading, demotion, or transfer; recruitment or recruitment advertising; layoff or termination; rates of pay or other forms of compensation; and selection for training, including apprenticeship. The contractor agrees to post in conspicuous places, available to employees and applicants for employment, notices to be provided by the Public Agency Compliance Officer setting forth provisions of this nondiscrimination clause.
- b. The contractor or subcontractor, where applicable will, in all solicitations or advertisements for employees placed by or on behalf of the contractor, state that all qualified applicants will receive consideration for employment without regard to age, race, creed, color, national origin, ancestry, marital status, affectional or sexual orientation, gender identity or expression, disability, nationality or sex.
- c. The contractor or subcontractor will send to each labor union, with which he has a collective bargaining agreement a notice, to be provided by the agency contracting officer, advising the labor union or workers' representative of the contractor's commitments under this act and shall post copies of the notice in conspicuous places available to employees and applicants for employment.
- d. The contractor or subcontractor, where applicable, agrees to comply with any regulations promulgated by the Treasurer pursuant to N.J.S.A. 10:5-31 et. seq., as amended and supplemented from time to time and the Americans with Disabilities Act.
- e. When hiring or scheduling workers in each construction trade, the contractor or subcontractor agrees to make good faith efforts to employ minority and women workers in each construction trade consistent with the targeted employment goal prescribed by N.J.A.C. 17:27-7.2, provided however, that the Dept. of LWD, Construction EEO Monitoring Program may, in its discretion, exempt a contractor or subcontractor from compliance with the good faith procedures prescribed by the following provisions, A, B, and C, as long as the Dept. of LWD. Construction EEO Monitoring Program is satisfied that the contractor or subcontractor is employing workers provided by a union which provides evidence, in accordance with standards prescribed by the Dept. of LWD, Construction EEO Monitoring Program, that its percentage of active "card carrying" members who are minority and women workers is equal to or greater than the applicable employment goal established in accordance with N.J.A.C. 17:27-7.2. The contractor or subcontractor agrees that a good faith effort shall include compliance with the following procedures:
 - (A) If the contractor or subcontractor has a referral agreement or arrangement with a union for a construction trade, the contractor or subcontractor shall, within three business days of the contract award, seek assurances from the union that it will cooperate with the contractor or subcontractor as it fulfills its affirmative action obligations under this contract and in accordance with the rules promulgated by the Treasurer pursuant to N.J.S.A. 10.5-31 et seq., as supplemented and amended from time to time and the Americans with Disabilities Act. If the contractor or subcontractor is unable to obtain said assurances from the construction trade union at least five business days prior to the commencement of construction work, the contractor or subcontractor agrees to afford equal employment opportunities minority and women workers directly, consistent with this chapter. If the contractor's or subcontractor's prior experience with a construction trade union, regardless of whether the union has provided said assurances indicates a significant possibility that the trade union will not refer sufficient minority and women workers consistent with affording equal employment opportunities as specified in this chapter, the contractor or subcontractor agrees to be prepared to provide such opportunities to minority and women workers directly consistent with this chapter,

by complying with the hiring or scheduling procedures prescribed under (B) below; and the contractor or subcontractor further agrees to take said action immediately if it determines that the union is not referring minority and women workers consistent with the equal employment opportunity goals set forth in this chapter.

- (B) If good faith efforts to meet targeted employment goals have not or cannot be met for each construction trade by adhering to the procedures of (A) above, or if the contractor does not have a referral agreement or arrangement with a union for construction trade, the contractor or subcontractor agrees to take the following actions:
 - (1) To notify the public agency compliance officer, the Dept. of LWD, Construction EEO Monitoring Program, and minority and women referral organizations listed by the Division pursuant to N.J.A.C. 17:27-5.3, of its workforce needs, and request referral of minority and women workers;
 - (2) To notify any minority and women workers who have been listed with it as awaiting available vacancies;
 - (3) Prior to commencement of work, to request the local construction trade union refer minority and women workers to fill job openings, provided the contractor or subcontractor has a referral agreement, or arrangement with a union for the construction trade;
 - (4) To leave standing requests for additional referral of minority and women workers with the local construction trade union, provided the contractor or subcontractor has a referral agreement or arrangement with a union for the construction trade. The State Training and Employment Service and other approved referral sources in the area;
 - (5) If it is necessary to layoff some of the workers in a given trade on the construction site, layoffs shall be conducted in compliance with the equal employment opportunity and non-discrimination standards set forth in this regulation, as well as with applicable Federal and State court decisions;
 - (6) To adhere to the following procedure when minority and women workers apply or are referred to the contractor or subcontractor:
 - (i) The contractor or subcontractor shall interview the referred minority or women worker.
 - (ii) If said individuals have never previously received any document or certification signifying a level of qualification lower than that required in order to perform the work of the construction trade, the contractor or subcontractor shall in good faith determine the qualifications of such individuals. The contractor or subcontractor shall hire or schedule those individuals who satisfy appropriate qualification standards, in conformity with the equal employment opportunity and non-discrimination principles set forth in this chapter. However, a contractor or subcontractor shall determine that the individual at least possesses the requisite skills, and experience recognized by a union, apprentice program or a referral agency, provided the referral agency is acceptable to the Dept, of LWD, Construction EEO Monitoring Program. If necessary, the contractor or subcontractor shall hire minority and women workers who qualify as trainees pursuant to these rules. All of the requirements; however, are limited by the provisions of (C) below.
 - (iii) The name of any interested women or minority individual shall be maintained on a waiting list, and shall be considered for employment as described in (i) above, whenever vacancies occur. At the request of the Dept. of LWD, Construction EEO Monitoring Program, the contractor or subcontractors shall provide evidence of its good faith efforts to employ women and minorities from the list to fill vacancies.
 - (iv) If, for any reason, said contractor or subcontractor determines that a minority individual or a women is not qualified or if the individual qualifies as an advanced trainee or apprentice, the contractor or subcontractor shall inform the individual in writing with the reasons for the determination and maintain a copy of the determination in its files, and send a copy to the public agency compliance officer and to the Dept. of LWD, Construction EEO Monitoring Program.
 - (7) To keep a complete and accurate record of all requests made for the referral of workers in any trade covered by the contract, and on forms made available by the Dept. of LWD, Construction EEO Monitoring Program upon request.

The contractor or subcontractor agrees that nothing contained in (B) above shall preclude the ((') contractor or subcontractor from complying with the union hiring hall or apprenticeship policies in any applicable collective bargaining agreement or union hiring hall arrangement, and, where required by custom or agreement, it shall send journeymen and trainees to the union for referral, or to the apprenticeship program for admission, pursuant to such agreement or arrangement. However, where the practices of a union or apprenticeship program will result in the exclusion of minorities and women or the failure to refer minorities and women consistent with the targeted county employment goal, the contractor or subcontractor shall consider for employment persons referred pursuant to (B) above without regard to such agreement or arrangement; provided further, however, that the contractor or subcontractor shall not be required to employ minority and women advanced trainees and trainees in numbers which result in the employment of advanced trainees as a percentage of the total workforce for the construction trade, which percentage significantly exceeds the apprentice to journey worker ratio specified in the applicable collective bargaining agreement, or in the absence of a collective bargaining agreement, exceeds the ratio established by practice in the area for said construction trade. Also the contractor or subcontractor agrees that, in implementing the procedures of (B) above, it shall, where applicable, employ minority and women workers residing within the geographical jurisdiction of the union.

After notification of award, but prior to signing a construction contract, the contractor shall submit to the public agency compliance officer and the Dept. of LWD, Construction EEO Monitoring Program an initial project workforce report (Form AA-201) electronically provided to the public agency by the Dept. of LWD, Construction EEO Monitoring Program, through its website, for distribution to and completion by the contractor, in accordance with N.J.A.C. 17:27-7. The contractor also agrees to submit a copy of the Monthly Project Workforce Report once a month thereafter for the duration of this contract to the Division and to the public agency compliance officer.

The contractor agrees to cooperate with the public agency in the payment of budgeted funds, as is necessary, for on-the-job and/or off-the-job programs for outreach and training of minorities and women.

(D) The contractor and its subcontractors shall furnish such reports or other documents to the Dept, of LWD, Construction EEO Monitoring Program as may be requested by the Dept. of LWD, Construction EEO Monitoring Program from time to time in order to carry out the purposes of these regulations, and public agencies shall furnish such information as may be requested by the Dept. of LWD, Construction EEO Monitoring Program for conducting a compliance investigation pursuant to Subchapter 10 of the Administrative Code (NJAC 17:27)

ANTIDISCRIMATION PROVISIONS

Mandatory Language

N.J.S.A. 10:2-1 (2014)

The contractor agrees that:

Antidiscrimination provisions. Every contract for or on behalf of the State or any country or municipality or other political subdivision of the State, or any agency of or authority created by any of the foregoing, for the construction, alteration or repair of any public building or public work or for the acquisition of materials, equipment, supplies or services shall contain provisions by which the contractor agrees that:

- a. In the hiring of persons for the performance of work under this contract or any subcontract hereunder, or for the procurement, manufacture, assembling or furnishing of any such materials, equipment, supplies, or services to be acquired under this contract, no contractor, nor any person acting on behalf of such contractor or subcontractor, shall, by reason of race, creed, color, national origin, ancestry, marital status, gender identity or expression, affectional or sexual orientation or sex, discriminate against any person who is qualified and available to perform the work to which the employment relates;
- b. No contractor, subcontractor, nor any person on his behalf shall, in any manner, discriminate against or intimidate any employee engaged in the performance of work under this contract or any subcontract hereunder, or engaged in the procurement, manufacture, assembling or furnishing of any such materials, equipment, supplies or services to be acquired under such contract, on account of race, creed, color, national origin, ancestry, marital status, gender identity or expression, affectional or sexual orientation or sex;
- c. There may be deducted from the amount payable to the contractor by the contracting public agency, under this contract, a penalty of \$50.00 for each person for each calendar day during which such person is discriminated against or intimidated in violation of the provisions of the contract; and
- d. This contract may be canceled or terminated by the contracting public agency, and all money due or to become due hereunder may be forfeited, for any violation of this section of the contract occurring after notice to the contractor from the contracting public agency of any prior violation of this section of the contract.

No provision in this section shall be construed to prevent a board of education from designating that a contract, subcontract or other means of procurement of goods, services, equipment or construction shall be awarded to a small business enterprise, minority business enterprise or a women's business enterprise pursuant to P.L. 1985, c.490 (C.18A:18A-51 et seq.).

ADDITIONAL MANDA FORY CONSTRUCTION CONFRACT LANGUAGE

It is the policy of the State of NJ Department of the Treasury, Division of Property Management & Construction (DPMC), that its contracts should create a workforce that reflects the diversity of the State of New Jersey. Therefore, contractors engaged by the DPMC, to perform under a construction contract shall put forth a good faith effort to engage in recruitment and employment practices that further the goal of fostering equal opportunities to minorities and women.

The contractor must demonstrate to the DPMC's satisfaction that a good faith effort was made to ensure that minorities and women have been afforded equal opportunity to gain employment under the DPMC's contract with the contractor. Payment may be withheld from a contractor's contract for failure to comply with these provisions.

Evidence of a "good faith effort" includes, but is not limited to:

- 1. The Contractor shall recruit prospective employees through the State Job bank website, managed by the Department of Labor and Workforce Development, available online at http://NJ.gov/JobCentralNJ;
- 2. The Contractor shall keep specific records of its efforts, including records of all individuals interviewed and hired, including the specific numbers of minorities and women;
- 3. The Contractor shall actively solicit and shall provide the DPMC with proof of solicitations for employment, including but not limited to advertisements in general circulation media, professional service publications and electronic media; and
- 4. The Contractor shall provide evidence of efforts described at 2 above to the DPMC no less frequently than once every 12 months.
- 5. The Contractor shall comply with the requirements set forth at N.J.A.C. 17:27.

AMERICANS WITH DISABILITIES ACTS State Contract Language

Equal Opportunity for Individuals with Disabilities

The CONTRACTORS and the STATE do hereby agree that the provision of Title II of the Americans With Disabilities Act of 1990 (the "Act") (42 U.S.C. S12101 et. seq.), which prohibits discrimination on the basis of disability by public entities in all services, programs and activities provided or made available by public entities, and the rules and regulations promulgated pursuant thereunto, are made a part of this contract. In providing any aid, benefit, or service on behalf of the STATE pursuant to this contract, the CONTRACTOR agrees that the performance shall be in strict compliance with the Act. In the event that the CONTRACTOR, its agents, servants, employees, or subcontractors violate or are alleged to have violated the Act during the performance of this contract, the CONTRACTOR shall defend the STATE in any action or administrative proceeding commenced pursuant to this Act. The CONTRACTOR shall indemnify, protect, and save harmless the STATE, its agents, servants, and employees from and against any and all suits, claims, losses, demands, or damages of whatever kind or nature arising out of or claimed to arise out of the alleged violation. The CONTRACTOR shall, at its own expense, appear, defend, and pay any and all charges for legal services and any and all costs and other expenses arising from such action or administrative proceeding or incurred in connection therewith. In any and all complaints brought pursuant to the STATE's grievance procedure, the CONTRACTOR agrees to abide by any decision of the STATE which is rendered pursuant to said grievance procedure. If any action or administrative proceeding results in an award of damages against the STATE or if the STATE incurs any expense to cure a violation of the ADA which has been brought pursuant to its grievance procedure, the CONTRACTOR shall satisfy and discharge the same at its own expense.

The STATE shall, as soon as practicable after a claim has been made against it, give written notice thereof to the CONTRACTOR along with full and complete particulars of the claim. If any action or administrative proceeding is brought against the STATE or any of its agents, servants, and employees, the STATE shall expeditiously forward or have forwarded to the CONTRACTOR every demand, complaint, notice, summons, pleading, or other process received by the STATE of its representatives.

It is expressly agreed and understood that any approval by the STATE of the services provided by the CONTRACTOR pursuant to this contract will not relieve the CONTRACTOR of the obligation to comply with the Act and to defend, indemnify, protect, and save harmless the STATE pursuant to this paragraph.

It is further agreed and understood that the STATE assumes no obligation to indemnify or save harmless the CONTRACTOR, its agents, servants, employees and subcontractors for any claim which may arise out of their performance of this Agreement. Furthermore, the CONTRACTOR expressly understands and agrees that the provisions of this indemnification clause shall in no way limit the CONTRACTOR's obligations assumed in this Agreement, nor shall they be construed to relieve the CONTRACTOR from any liability, nor preclude the STATE from taking any other actions available to it under any other provisions of the Agreement or otherwise at law.

(Revised 4/10)

EXHIBIT A

MANDATORY EQUAL EMPLOYMENT OPPORTUNITY LANGUAGE N.J.S.A. 10:5-31 et seq. (P.L. 1975, C. 127)