

FINAL ENVIRONMENTAL IMPACT STATEMENT**NEW MEADOWLANDS STADIUM PROJECT****TABLE OF CONTENTS**

	<u>Page No.</u>
EXECUTIVE SUMMARY	ES-1
1.0 INTRODUCTION	1-1
2.0 PROJECT DESCRIPTION	2-1
2.1 Project Setting	2-1
2.2 Project Description	2-9
2.3 Project Sponsor	2-19
2.4 Project Location, Type and Character	2-20
2.5 Project Schedule and Construction Phasing	2-22
3.0 PURPOSE AND NEED	3-1
3.1 NJSEA Public Purpose and Mission	3-1
3.2 Project Purpose and Mission	3-1
4.0 ENVIRONMENTAL CONDITIONS, IMPACTS, AND MITIGATION.....	4-1
4.1 Land Form	4-1
4.1.1 Existing Conditions	4-1
4.1.2 Impacts and Mitigation	4-2
4.2 Geology and Soils	4-8
4.2.1 Existing Conditions	4-8
4.2.2 Impacts and Mitigation	4-16
4.3 Water Resources	4-17
4.3.1 Existing Conditions	4-17
4.3.1.1 Wetlands.....	4-17
4.3.1.2 Surface Water.....	4-20
4.3.1.2.1 Surface Drainage Characteristics	4-20
4.3.1.2.2 Surface Water Quality.....	4-24
4.3.1.3 Groundwater.....	4-31
4.3.2 Impacts and Mitigation	4-31
4.3.2.1 Wetlands.....	4-31

4.3.2.2	Surface Water	4-31
4.3.2.2.1	Surface Drainage Characteristics	4-31
4.3.2.2.2	Surface Water Quality	4-32
4.3.2.3	Groundwater	4-33
4.4	Floodplains	4-34
4.4.1	Existing Conditions	4-34
4.4.2	Impacts and Mitigation	4-36
4.5	Tidelands	4-37
4.5.1	Existing Conditions	4-37
4.5.2	Impacts and Mitigation	4-37
4.6	Vegetation	4-37
4.6.1	Existing Conditions	4-37
4.6.2	Impacts and Mitigation	4-39
4.7	Wildlife	4-41
4.7.1	Existing Conditions	4-41
4.7.2	Impacts and Mitigation	4-43
4.8	Resource Contamination	4-45
4.8.1	Existing Conditions	4-45
4.8.2	Impacts and Mitigation	4-50
4.9	Solid Waste and Recycling	4-54
4.9.1	Existing Conditions	4-54
4.9.2	Impacts and Mitigation	4-55
4.10	Utilities and Infrastructure	4-58
4.10.1	Existing Conditions	4-58
4.10.1.1	Stormwater Management	4-58
4.10.1.1.1	Stormwater Conveyance System	4-58
4.10.1.1.2	Existing Drainage Characteristics	4-60
4.10.1.1.3	Existing Hydrology	4-62
4.10.1.2	Sanitary Sewer Service	4-63
4.10.1.3	Potable Water Service	4-67
4.10.1.4	Natural Gas Service	4-68
4.10.1.5	Electric Service	4-68
4.10.1.6	Telecommunication Service	4-69
4.10.2	Impacts and Mitigation	4-69
4.10.2.1	Stormwater Management	4-69
4.10.2.1.1	Stormwater Conveyance System	4-69
4.10.2.1.2	Proposed Drainage Characteristics	4-72
4.10.2.1.3	Proposed Hydrology	4-74
4.10.2.2	Sanitary Sewer Service	4-74
4.10.2.3	Potable Water Service	4-77
4.10.2.4	Natural Gas Service	4-77

4.10.2.5	Electric Service	4-78
4.10.2.6	Telecommunication Service.....	4-79
4.11	Traffic and Transportation	4-81
4.11.1	Existing Conditions	4-83
4.11.1.1	Roadway Network	4-83
4.11.1.2	Traffic	4-84
4.11.1.3	Parking	4-85
4.11.1.4	Public Transportation	4-86
4.11.1.5	Pedestrian Circulation	4-88
4.11.1.6	Air Navigation.....	4-88
4.11.2	Impacts and Mitigation	4-89
4.11.2.1	Traffic Study Methodologies.....	4-89
4.11.2.1.1	Traffic Modeling Methodology	4-89
4.11.2.1.2	Study Locations	4-91
4.11.2.1.3	Peak Period Determination	4-95
4.11.2.1.4	Capacity Analysis Methodology	4-96
4.11.2.2	Traffic Impacts	4-96
4.11.2.2.1	Trip Generation	4-97
4.11.2.2.2	Trip Distribution.....	4-102
4.11.2.2.3	Traffic Volume and Capacity	4-102
4.11.2.3	Parking and Transportation Management.....	4-116
4.11.2.4	Public Transportation	4-122
4.11.2.5	Pedestrian Circulation	4-123
4.11.2.6	Air Navigation.....	4-124
4.12	Air Quality	4-125
4.12.1	Existing Conditions	4-125
4.12.1.1	Criteria and Standards.....	4-125
4.12.1.2	Existing Air Quality.....	4-129
4.12.2	Impacts and Mitigation	4-133
4.12.2.1	Construction Source Emissions.....	4-133
4.12.2.2	Stationary Source Emissions	4-134
4.12.2.3	Mobile Source Emissions	4-134
4.13	Noise.....	4-142
4.13.1	Existing Conditions	4-142
4.13.1.1	Background.....	4-142
4.13.1.2	Noise Standards, Criteria, and Guidelines.....	4-142
4.13.1.3	Existing Noise Levels and Sensitive Receptors.....	4-143
4.13.2	Impacts and Mitigation	4-147
4.13.2.1	Construction Noise	4-147
4.13.2.2	Operational Noise	4-152
4.13.2.3	Mobile Source Noise	4-152

4.14	Socioeconomics	4-153
4.14.1	Existing Conditions	4-155
4.14.1.1	Demographic and Socioeconomic Conditions	4-155
4.14.1.2	Community Facilities	4-155
4.14.1.2.1	Overview.....	4-155
4.14.1.2.2	Police Protection.....	4-155
4.14.1.2.3	Fire Protection.....	4-156
4.14.1.2.4	Hospitals and Emergency Medical Services	4-157
4.14.1.2.5	Schools	4-157
4.14.1.3	Economic and Fiscal Impact Estimates from Current Operations of Giants Stadium and Training Facilities.....	4-157
4.14.2	Incremental Construction and Operations Impacts: Stadium and Training Facilities	4-160
4.14.2.1	Overview	4-160
4.14.2.2	Population	4-161
4.14.2.3	Construction Economic Fiscal Impacts: New Stadium and Training Facilities.....	4-161
4.14.2.4	Operational Economic and Fiscal Impacts	4-162
4.14.3	Incremental Construction and Operations Impacts: Ancillary Development.....	4-166
4.14.4	Impacts on Community Facilities.....	4-167
4.14.4.1	Public Services.....	4-167
4.14.4.1.1	Police	4-168
4.14.4.1.2	Fire Protection.....	4-168
4.14.4.1.3	Emergency Medical Services.....	4-168
4.14.4.1.4	Impacts	4-169
4.14.4.2	Schools	4-169
4.14.4.3	Environmental Justice	4-169
4.15	Land Use and Zoning	4-170
4.15.1	Existing Conditions	4-170
4.15.1.1	Land Use.....	4-170
4.15.1.2	Zoning.....	4-175
4.15.2	Impacts and Mitigation	4-177
4.16	Cultural, Historic, and Archaeological Resources	4-178
4.16.1	Existing Conditions	4-178
4.16.1.1	Historical Background	4-178
4.16.1.2	Archaeological Resources.....	4-180
4.16.1.3	Historic Architectural Resources	4-183
4.16.2	Impacts and Mitigation	4-184
4.17	Parks and Recreational Facilities	4-184
4.17.1	Existing Conditions	4-184
4.17.2	Impacts and Mitigation	4-188

4.18	Visual and Landscape Aesthetics	4-188
4.18.1	Existing Conditions	4-188
4.18.2	Impacts and Mitigation	4-191
4.19	Avoidance of Adverse Environmental Impacts	4-202
4.20	Indirect and Cumulative Impacts	4-203
5.0	ALTERNATIVES FOR THE PROPOSED PROJECT	5-1
5.1	No-Action Alternative	5-1
5.2	Location Alternative to the Project Site	5-2
6.0	PERMITS AND APPROVALS REQUIRED	6-1
6.1	Overview	6-1
6.2	Required Regulatory Approvals	6-2
6.2.1	FAA Notification for Air Navigation Obstructions.....	6-2
6.2.2	Army Corps of Engineers Section 10/404 Jurisdictional Determination	6-2
6.2.3	NJDEP Land Use Permits.....	6-3
6.2.4	NJDEP Water Quality Management Plan Consistency Determination	6-4
6.2.5	New Jersey Pollutant Discharge Elimination System Permits	6-4
6.2.6	NJDEP Treatment Works Approval	6-4
6.2.7	NJDEP Well Permits.....	6-5
6.2.8	NJDEP Water Main Extension Certification.....	6-5
6.2.9	NJDEP Remedial Action Workplan Approval	6-5
6.2.10	New Jersey Uniform Construction Code Plan Approval	6-6
6.2.11	Bergen County Soil Conservation District Approvals.....	6-6
6.2.12	NJDOT Major Access Permit.....	6-6
6.2.13	NJDEP Air Permits.....	6-7
7.0	PUBLIC PARTICIPATION AND STATUTORY CONSULTATION	7-1
7.1	Statutory Consultation Requirement/Executive Order No. 215.....	7-1
7.2	Permits	7-2
7.3	Consultation Schedule.....	7-3
7.4	Availability of EIS	7-4
8.0	REFERENCES	8-1
9.0	LIST OF PREPARERS	9-1

FIGURES

		<u>Page No.</u>
 Section 1		
1-1	New Meadowlands Stadium Project Master Plan.....	1-2
 Section 2		
2-1	Project Location within the Hackensack Meadowlands District.....	2-2
2-2	Project Area Vicinity Map	2-3
2-3	General Map of Meadowlands Sports Complex.....	2-4
2-4	Project Area Location Map	2-5
2-5	Aerial Photograph of Project Area	2-6
2-6	Map of Regional Projects	2-8
2-7	Aerial Photograph with Proposed Stadium Project Components	2-10
2-8	Rendering of Proposed Stadium and Ancillary Development.....	2-11
2-9	Land Use Diagram.....	2-12
2-10	Rendering of Giants Training Facility	2-15
 Section 4		
4-1A	Topographic Survey of Project Area	4-3
4-1B	Topographic Survey of Project Area	4-4
4-1C	Topographic Survey of Project Area	4-5
4-1D	Topographic Survey of Project Area	4-6
4-1E	Topographic Survey of Project Area	4-7
4-2	USGS Bedrock Geologic Map.....	4-9
4-3	Bergen County Soil Survey Map.....	4-11
4-4	Geotechnical Investigation Soil Sample Location Map.....	4-12
4-5	Subsurface Profile A-A	4-14
4-6	Subsurface Profile B-B	4-15
4-7	National Wetlands Inventory Map	4-19
4-8	Drainage Basins within the Hackensack Meadowlands	4-22
4-9	New Jersey Meadowlands Commission Water Sampling Location Map ...	4-27
4-10	FEMA Flood Insurance Rate Map.....	4-35
4-11	Tidelands Composite Map.....	4-38
4-12	A View from the South Connector Road Bridge Over Rt. 120 Looking North at Project Area	4-40
4-13	A View Looking at a Typical Landscaped Traffic Island Next to Giants Stadium	4-40
4-14	NJDEP Landscape Project Map.....	4-44
4-15	Historic Fill of the Weehawken Quadrangle	4-47
4-16	Existing Drainage Area Map	4-59
4-17	BCUA Service Area Map	4-64
4-18	Stadium Utility Plan.....	4-70
4-19	Giants Training Facility Utility Plan.....	4-71

4-20	Proposed Drainage Area Map	4-73
4-21	Proposed Sanitary Sewer Map	4-76
4-22	Traffic Study Locations	4-94
4-23	Location of NJDEP Ambient Air Monitoring Stations	4-127
4-24	Air Pollution Trends in New Jersey 1969 - 2003	4-130
4-25	Air Quality Hot Spot Analysis Location Map	4-138
4-26	Noise Monitoring and Analysis Locations.....	4-145
4-27	Existing Land Use in the Hackensack Meadowlands District.....	4-171
4-28	Hackensack Meadowlands District Land Use Plan	4-174
4-29	Hackensack Meadowlands District Official Zoning Map	4-176
4-30	Cultural Resources in the Vicinity of the Project Area	4-181
4-31	Parks and Recreational Facilities in the Hackensack Meadowlands.....	4-185
4-32	Site Section Stadium/NJ Transit Rail Facility – East	4-192
4-33	Ancillary Development Stadium Section South	4-193
4-34	Example Material Selections for New Meadowlands Stadium	4-194
4-35	Ancillary Development Rendering	4-196
4-36	Pedestrian Zone Section Landscape Rendering	4-197
4-37	Stadium Plaza Area Landscape Plan.....	4-198
4-38	West Plaza to Middle Loop Road Section Landscape Rendering.....	4-199
4-39	East Plaza to Transit Station Section Landscape Rendering.....	4-200
4-40	Giants Training Facility Landscape Plan.....	4-201

TABLES

	<u>Page No.</u>
Executive Summary	
ES-1 Stadium Project Required Permits and Approvals.....	ES-11
Section 2	
2-1 Project Components of the New Meadowlands Stadium Project.....	2-17
2-2 Existing and Proposed Stadium Comparison	2-18
Section 4	
4-1 Flow Characteristics of the Tidal Water Bodies in Vicinity of the Meadowlands Sports Complex	4-23
4-2 Surface Water Classifications of the Hackensack River and Berry's Creek.	4-25
4-3 Water Quality Data from Station 3 in Hackensack River from 1994 to 2006	4-28
4-4 Water Quality Data from Station 8 in Berry's Creek from 1994 to 2006.....	4-29
4-5 Water Quality Data from Meadowlands Sports Complex Lagoon System Surface Water Discharge to Berry's Creek	4-30
4-6 Projected Solid Waste Production for Operation of the Project	4-57
4-7 Existing and Proposed Drainage Area Land Coverage	4-61
4-8 Existing Drainage Area Peak Flows	4-63
4-9 Existing and Proposed Sanitary Design Flows by Facility and Event	4-66
4-10 Proposed Drainage Area Peak Flows	4-74
4-11 Study Locations for the New Meadowlands Stadium Project Traffic Study	4-92
4-12 Trip Generation Estimates – Total Trips	4-100
4-13 Trip Generation Estimates – New Trips	4-101
4-14 Overall Trip Distribution.....	4-102
4-15 Weekday PM Highway Peak Hour Baseline (No Build) and Build Conditions for 2010 and 2013	4-105
4-16 Weekday PM Continental Airlines Arena Event Peak Hour Baseline (No Build) and Build Conditions for 2010 and 2013	4-108
4-17 Saturday Peak Continental Airlines Arena Event Hour Baseline (No Build) and Build Conditions for 2010 and 2013.....	4-112
4-18 Future Supply and Demand Summary of NFL Parking Spaces	4-120
4-19 Peak Day Parking Demand.....	4-122
4-20 New Jersey and National Ambient Air Quality Standards and Regional Monitoring Data	4-128
4-21 2013 Microscale Hot-Spot Analysis Results for 1-Hour Maximum CO Concentrations	4-139
4-22 2013 Microscale Hot-Spot Analysis Results for 8-Hour Maximum CO Concentrations.....	4-140
4-23 Community Response to Increases in Noise Levels.....	4-143
4-24 Distance of Noise Monitoring Locations from Project Area	4-144

4-25 Measured Ambient Noise Levels During Monitoring Periods 4-146

4-26 Measured Hourly L_{eq} Levels 4-146

4-27 Noise Levels of Major Construction Equipment..... 4-148

4-28 Typical Site Average Noise Levels at 50 Feet From the Construction Activity 4-149

4-29 Projected Combined Background Noise and Construction Noise Levels at
Receptor Locations 4-151

4-30 Summary of Economic and Fiscal Impacts to New Jersey Due to Current
Operation of Giants Stadium and Training Facilities..... 4-159

4-31 Summary of Economic and Fiscal Impacts to New Jersey From Construction
of New Meadowlands Stadium and Training Complex 4-162

4-32 Summary of Annual Economic Impacts to New Jersey from Operations of
New Meadowlands Stadium and Training Complex 4-163

4-33 Summary of Annual Fiscal and Other Revenue Impacts to New Jersey From
Operations of New Meadowlands Stadium and Training Complex..... 4-165

Section 6

6-1 List of Required Permits and Approvals 6-8

APPENDICES

Appendix A Agency Correspondence

Appendix B Preliminary Environmental Impact Statement on CD

Appendix C Revised Traffic Study

Appendix D Response to Comments on PEIS

LIST OF ACRONYMS

Ac – Acre
ACM – Asbestos Containing Materials
AED – Automated External Defibrillator
AOC – Area of Concern
APE – Area of Potential Effect
BCE – Before Common Era
BCUA – Bergen County Utilities Authority
BCSCD – Bergen County Soil Conservation District
BEE – Baseline Ecological Evaluation
BMP – Best Management Practices
BOD – Biological Oxygen Demand
CAA – Clean Air Act
CE – Common Era
CEA – Classification Exemption Area
cfs – cubic feet per second
CIWMB – California Integrated Waste Management Board
cms – cubic meters per second
CN – Curve Number
CO – Carbon Monoxide
COPEC – Contaminants Of Potential Ecological Concern
CZMCD – Coastal Zone Management Consistency Determination
dB – Decibel
dBA – A-weight Decibel Scale
DDC – Direct Digital Control
DO – Dissolved Oxygen
EA – Environmental Assessment
EFH – Essential Fish Habitat
EIS – Environmental Impact Statement
el – elevation
EMS – Emergency Medical Services
EO 215 – Executive Order No. 215
EO 53 – Executive Order No. 53
ERPD – East Rutherford Police Department
ERPWUC – East Rutherford Public Works Utility Commission
ERVFD – East Rutherford Volunteer Fire Department
FAA – Federal Aviation Administration
FEMA – Federal Emergency Management Agency
FHWA – Federal Highway Administration
FEIS – Final Environmental Impact Statement
FIRM – Flood Insurance Rate Map
FIS – Flood Insurance Study
ft – feet
GBA – Gross Building Area
gpd – gallons per day
gpm – gallons per minute

GLA – Gross Leasable Area
HAPS – Highway Access Permit System
HASP – Health and Safety Plan
HVAC – Heating, Ventilating, and Air Conditioning
HMD – Hackensack Meadowlands District
HMDC – Hackensack Meadowlands Development Commission
ISO – International Standards Organization
ITE – Institute of Transportation Engineers
Km² – square kilometer
Kv – Kilovolt
LBP – Lead Based Paint
LOS – Level of Service
JD – Jurisdictional Determination
LURP – Land Use Regulation Program
MERI – Meadowlands Environmental Research Institute
mgd – million gallons per day
mg/L – milligrams per liter
mi² – square mile
ml – milliliters
MOA – Memorandum of Agreement
MVA - Megavolts
NAAQS – National Ambient Air Quality Standards
NCAA – National Collegiate Athletic Association
NFL – National Football League
NGVD – National Geodetic Vertical Datum
NHP – Natural Heritage Program
NJ – New Jersey
NJAAQS -New Jersey Ambient Air Quality Standards
NJAS – New Jersey Audubon Society
NJDCA - New Jersey Department of Community Affairs
NJDEP – New Jersey Department of Environmental Protection
NJDOH – New Jersey Department of Health
NJDOL – New Jersey Department of Labor
NJDOT – New Jersey Department of Transportation
NJMC – New Jersey Meadowlands Commission
NJPDES – New Jersey Pollutant Discharge Elimination System
NJSEA – New Jersey Sports and Exposition Authority
NJSM – New Jersey State Museum
NJSP – New Jersey State Police
NJTA – New Jersey Turnpike Authority
NJTPA – North Jersey Transportation Planning Authority
NMFS – National Marine Fisheries Service
NM Stadco – New Meadowlands Stadium Company, LLC
NO – nitric oxide
NO₂ – nitrogen dioxide
NO_x – nitrogen oxides
NRCS – Natural Resources Conservation Service
NRHP – National Register of Historic Places

NWI – National Wetlands Inventory
O₃ – ozone
PA – Preliminary Assessment
PABT – Port Authority Bus Terminal
PAHs – Polycyclic Aromatic Hydrocarbons
PATH – Port Authority Trans-Hudson Corporation
Pb – lead
PCB – Polychlorinated Biphenyls
pc/mil/ln – passenger cars per mile per lane
PEIS – Preliminary Environmental Impact Statement
PILOT – Payments In Lieu Of Taxes
PM_{2.5} – particulate matter with an aerodynamic diameter less than or equal to 2.5 micrometers
PM₁₀ – particulate matter with an aerodynamic diameter less than or equal to 10 micrometers
POP – Project Operating Plan
ppm – parts per million
ppt – parts per thousand
PSE&G – Public Service Electric and Gas Company
PSEG – Public Service Enterprise Group
psi – pounds per square inch
PVC – polyvinyl chloride
RAWP – Remedial Action Work Plan
RFA – Request for Authorization
SAMP DEIS – Special Area Management Plan Draft Environmental Impact Statement
SCC – Soil Cleanup Criteria
SCS – Soil Conservation Service
SESCP – Soil Erosion and Sedimentation Control Plan
SF – square feet
SHPO – State Historic Preservation Office
SI – Site Investigation
SO₂ – sulfur dioxide
SPPP – Stormwater Pollution Prevention Plan
SRP – Soil Reuse Plan
SU – Standard Units
SVOC – Semi-Volatile Organic Compound
TWA – Treatment Works Approval
µg/m³ – micrograms per square meter
UdoB – Udorthents Organic Substratum
UR – Urban Land
USACE – United States Army Corps of Engineers
USEPA – United States Environmental Protection Agency
USFWS – United States Fish & Wildlife Service
USGS – United States Geological Survey
UWNJ – United Water New Jersey
VOC – Volatile Organic Compounds
WMA – Watershed Management Area