New Jersey Department of Transportation
CONSTRUCTION ADVISORY

NUMBER: 4	Temporary Striping and Markings	07/11/11
CATEGORY: Payment		

The Contractor is responsible for placing the Traffic Stripes and Traffic Markings (Traffic Stripes, Long-Life Epoxy Resin and Traffic Markings, Thermoplastic) and coordinating this with the other work prior to opening a roadway to traffic.

If the Contractor is unable to place the final Traffic Stripes and final Traffic Markings, it is permissible to allow the Contractor to place temporary traffic stripes and temporary traffic markings so that the roadway can be opened to traffic. However, this temporary work is to be considered as done for the Contractor's convenience, and REs are not to make payment to the Contractor for the temporary striping and temporary markings when permanent traffic stripes and permanent markings could have been installed.

Additionally, if the Contractor installs temporary traffic stripes and temporary markings as described above, the permanent traffic stripes and permanent markings must be placed within 3 days.

Kiran Patel, PE, PMP, CPM
Director, Construction Services & Materials