


# ***New Jersey Department of Transportation***

1035 Parkway Avenue, PO Box 600, Trenton, New Jersey 08625-0600



## ***Baseline Document Change Announcement***

**Spacer Bar for Steel U-Post  
BDC03D-02**

**November 29, 2004**

**SUBJECT: Revision to Construction Detail Sheet CD-619-5 of the 2001 Standard Roadway Construction-Details (Metric and English Units)-BDC03D-02**

Construction Detail Sheet CD-619-5 has been revised to correct use of spacer bars for the lap-spliced or nested Steel U-Post Sign Supports. The current Construction details permit only one size bar that will not properly address all possible splicing configuration found in the field. The use of a second bar will correct this problem and ensure proper function of the breakaway mechanism in all possible base-post/support splices.

The revision to 2001 Standard Roadway Construction Details sheet CD-619-5 is per following:

<u>Subsection</u>	<u>Changes</u>
CD-619-5.1	Addition of notes number 4 and 5
CD-619-5.2	Addition of second spacer bar

### **Implementation Code R (ROUTINE)**

Changes must be implemented in all applicable Department projects scheduled for Final Design Submission at least one month after the date of the BDC announcement. This will allow designers to make necessary plan, specifications, and estimate/proposal changes without requiring the need for an addenda or postponement of advertisement or receipt of bids.

Recommended By:

*ORIGINAL SIGNED BY LYNN D. RICH*

Lynn D. Rich  
Director,  
Quality Management Services

Approved By:

*ORIGINAL SIGNED BY F. HOWARD ZAHN*

F. Howard Zahn  
Assistant Commissioner,  
Capital Program Management

LDR: KS: FA

Attachments: Sheets CD-619-5 of the 2001 Standard Roadway Construction Details  
(Metric and English Units)