

406.07 MEASUREMENT

[Include for contracts involving removal of existing sign structures.]

The following is added:

Removal of overhead sign structures will be measured on a lump sum basis for each span, cantilever or butterfly type sign structure, and shall also include the removal of the existing footings and the delivery of all salvageable components as described in Section 406.05.

[Include for Authority furnished sign structures.]

Installation of new overhead sign structures will be measured on a lump sum basis for each span, cantilever or butterfly type sign structure, and shall include the pickup, delivery and complete installation as described in Section 406.05.

[Include appropriate pay items.]

406.08 PAYMENT

The following is added:

<i>PAY ITEM</i>	<i>PAY UNIT</i>
Remove Existing Span Sign Structure No. _____	Lump Sum
Remove Existing Cantilever Sign Structure No. _____	Lump Sum
Remove Existing Butterfly Sign Structure No. _____	Lump Sum
Install Overhead Span Sign Structure No. _____	Lump Sum
Install Overhead Cantilever Sign Structure No. _____	Lump Sum
Install Overhead Butterfly Sign Structure No. _____	Lump Sum

[Include the following if elastomeric bearing pads are included:]

SECTION 408 – ELASTOMATIC BEARING

408.03 METHODS OF CONSTRUCTION

(A) Fabrication

The first sentence is changed to the following:

Laminated Elastomeric Bearing Pads shall be vulcanized to the sole plate and base or masonry plate during the fabrication process unless otherwise noted on the plans.

(D) Testing

Regardless of the results of the test reports furnished by the contractor, the contractor shall furnish one additional full size laminated elastomeric bearing (including sole plate, base plate,