

SCOPE OF WORK

STOWE COTTAGE EDNA MAHAN CORRECTIONAL FACILITY EMC-226

- Remove and legally dispose of existing roofing to the steel deck.
- 2" LSO Insulation mechanically attached.
- PT 2 x 6 lumber mechanically fastened at perimeter.
- Versico EPDM .060" black fully adhered roofing system with all flashings and tie in to existing
- Aluminum drip edge, gutter and downspouts.
- Remove and replace up to 60sf of deteriorated steel deck Deck will be mechanically attached. Any quantity over this will be replaced at the unit price.
- One year warranty on labor and material.