

MARK WOSZCZAK
MECHANICAL CONTRACTORS
SITEWORK AND UTILITY CONSTRUCTION

1700 W. ATLANTIC AVE
MANASQUAN, NJ. 08736
Phone 732-223-3030 Fax 732-223-1563

UTILITY PROPOSAL



DATE: 4/20/2013
PROPOSAL: # 42013042
REVISED PROPOSAL

SEND TO:
New Jersey National Guard Training Center
P.O. Box 251
Sea Girt, NJ. 08750
Attn: Mr. Gary Schmitz

PROJECT SITE ADDRESS:
Bath House Building
Sea Girt Post
Sea Girt, NJ

UTILITY PROPOSAL

The following proposal is for the upgrade to the existing 1¼" HDPE water service from the existing 1" galvanized main supply to the rear of the building concrete vault assembly. The upgrade proposed will be a 2" HDPE main supply off the existing 8" ductile water main. The main will feed directly to a new concrete vault 48" x 48". The new vault will house the east trailer feeds, the west trailer feeds, and the current bath house. The current vault is too small for access. Also installed inside the vault will be winterizing blow downs with air fittings and ball valves. All areas are to be sectioned off using 2" ball valves and drain ports. The vault will include a 36" aluminum Bilco door for access. The following items are included within the proposal items; all excavation, backfill and compaction, all HDPE pipe and adaptors, brass ball valves and brass connections, brass fittings, concrete vault and Bilco door, concrete seals, and all permits required by DCA.

Utility Proposal

Description	Item	Unit	Total
HDPE Pipeline Complete As Described	395 Lf	\$ 25.00	\$ 9875.00
Connection and Wet Cut to Existing 8" Main	1 Un	\$ 600.00	\$ 600.00
Concrete Vault with Associated Piping and Manifold	1 Un	\$ 5800.00	\$ 5800.00
DCA Permits	1 Ls	\$ 500.00	\$ 500.00
<u>PROPOSAL TOTAL</u>			<u>\$ 16,775.00</u>

Submitted By:
Mark Woszczak

Mark L. Woszczak

Mark Woszczak Mechanical Contractors Inc.

MARK WOSZCZAK
MECHANICAL CONTRACTORS
SITEWORK AND UTILITY CONSTRUCTION

1700 W. ATLANTIC AVE
MANASQUAN, NJ. 08736
Phone 732-223-3030 Fax 732-223-1563

UTILITY PROPOSAL



DATE: 4/20/2013
PROPOSAL: # 42013042

SEND TO:

New Jersey National Guard Training Center
P.O. Box 251
Sea Girt, NJ. 08750
Attn: Mr. Gary Schmitz

PROJECT SITE ADDRESS:

Bath House Building
Sea Girt Post
Sea Girt, NJ

UTILITY PROPOSAL

The following proposal is for the removal of the existing damaged shower decks. The decks were damaged from Storm Sandy and it racked from water damage. The wood shower decks will be removed and disposed from the site. The wood decks will be replaced with new 4500 Psi concrete floors with trough drains. All drain assemblies will be equipped with new 4" Pvc pipe and fittings. The units will be piped to the existing sewer laterals in front of the buildings. Each slab unit will be piped to a sand separator located under the ground adjacent to the sewer lateral. The sand separator will have a removable top for sand removal from the unit. Two units are to be installed at the site. All interior wood walls and privacy doors are to remain at the site. No alteration of walls, benches, or doors are to be included under this proposal.

Utility Proposal

Description	Item	Unit	Total
Concrete Shower Floor Assemblies 20' x 10' x 6" thick	2 Un	\$ 3000.00	\$ 6000.00
Floor Channel Drain Assembly	2 Un	\$ 3200.00	\$ 6400.00
Sand Separator Units	2 Un	\$ 2500.00	\$ 5000.00
<u>PROPOSAL TOTAL</u>			<u>\$ 17,400.00</u>

Submitted By:

Mark Woszczak

Mark L. Woszczak

Mark Woszczak Mechanical Contractors Inc.

MARK WOSZCZAK
MECHANICAL CONTRACTORS
SITEWORK AND UTILITY CONSTRUCTION

1700 W. ATLANTIC AVE
MANASQUAN, NJ. 08736
Phone 732-223-3030 Fax 732-223-1563

UTILITY PROPOSAL



DATE: 4/20/13
PROPOSAL: # 4201306

SEND TO:
New Jersey National Guard Training Center
P.O. Box 251
Sea Girt, NJ. 08750
Attn: Mr. Gary Schmitz

PROJECT SITE ADDRESS:
Beach Shower Unit Repipe
Sea Girt Post
Sea Girt, NJ

UTILITY PROPOSAL

The following proposal is for the repiping of the beachfront shower unit damaged from Storm Sandy. The shower unit will have the feed assembly repiped to the fixture valves, hose bibb, and new yard hydrant. New single pull shower valves are to be installed for the shower unit. The existing hose bibbs adjacent to the parking lot that were damaged from Storm Sandy will be replaced with a new yard hydrant assembly.

Utility Proposal

Description	Item	Unit	Total
Plumbing Alterations to Exterior Shower Units as Described in the Proposal Above.	1 Un	\$ 2875.00	\$ 2875.00
<u>PROPOSAL TOTAL</u>			<u>\$ 2875.00</u>

Submitted By:
Mark Woszczak

Mark L. Woszczak

Mark Woszczak Mechanical Contractors Inc.