

State/County/Facility	Municipality	Begin MP ¹	End MP ¹	Agricultural ²		Commercial / Industrial ³		Forest/ Woodland ⁴		Open Land ⁵		Open Water ⁶		Residential ⁷		Total ¹¹		
				Temp. ROW ⁹	Perm. ROW ¹⁰	Temp. ROW ⁹	Perm. ROW ¹⁰	Temp. ROW ⁹	Perm. ROW ^{8,10}	Temp. ROW ⁹	Perm. ROW ¹⁰	Temp. ROW ⁹	Perm. ROW ¹⁰	Temp. ROW ⁹	Perm. ROW ¹⁰	Temp. ROW ⁹	Perm. ROW ¹⁰	
Hellertown Launcher & Mainline Launcher/Receiver / MLV-8	Lower Saucon Twp	71.6	-	0.0	0.0	0.3	0.1	0.2	0.8	0.1	1.7	0.0	0.0	0.0	0.0	0.6	2.6	
			Subtotal	0.0	0.0	0.3	0.1	0.2	1.0	0.1	1.7	0.0	0.0	0.0	0.0	0.6	2.8	
Contractor Yards, Pipe Yards and Staging Areas																		
Northampton County		-	Subtotal	119.9	0.0	83.3	0.0	7.2	0.0	10.2	0.0	0.0	0.0	0.0	0.0	220.6	0.0	
Hellertown 24-inch Lateral																		
Northampton County	Lower Saucon Twp	HL- 0.0	HL- 2.1R2	4.8	3.5	0.2	0.2	9.2	5.9	2.4	2.4	0.0	0.0	0.8	0.4	17.4	12.4	
			Subtotal	4.8	3.5	0.2	0.2	9.2	5.9	2.4	2.4	0.0	0.0	0.8	0.4	17.4	12.4	
Aboveground Facilities (for Hellertown Lateral)																		
TCO & UGI-LEH Interconnects	Lower Saucon Twp	HL- 2.1R2	-	0.0	0.0	0.0	0.5	0.0	1.4	0.0	2.1	0.0	0.0	0.0	0.0	0.0	4.0	
			Subtotal	0.0	0.0	0.0	0.5	0.0	1.4	0.0	2.1	0.0	0.0	0.0	0.0	0.0	4.0	
Access Roads																		
Northampton County		-	Subtotal	4.3	0.0	5.3	0.0	2.4	0.0	0.4	0.0	0.0	0.0	2.2	0.0	14.6	0.0	
			Northampton County Subtotal	256.1	79.7	99.0	8.6	81.1	60.0	26.7	15.2	0.0	0.4	11.8	6.3	474.7	170.2	
Bucks County																		
PennEast Mainline																		
	Durham Twp	75.9	77.7	13.1	6.9	0.1	0.2	1.6	1.6	0.1	0.2	0.0	0.3	0.2	0.2	15.1	9.4	
	Riegelsville Boro	76.7	76.9R2	2.3	1.4	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	2.3	1.4	
			Subtotal	15.4	8.3	0.1	0.2	1.6	1.6	0.1	0.2	0.0	0.3	0.2	0.2	17.4	10.8	
Access Roads																		
Bucks County		-	Subtotal	0.8	0.0	0.9	0.0	0.8	0.0	0.0	0.0	0.0	0.0	0.2	0.0	2.7	0.0	
			Bucks County Subtotal	16.2	8.3	1.0	0.2	2.4	1.6	0.1	0.2	0.0	0.3	0.4	0.2	20.1	10.8	
New Jersey																		
Hunterdon County																		
PennEast Mainline																		
	Holland Twp	77.7	85.4R1	32.8	19.6	0.7	0.7	23.7	21.7	4.9	5.6	0.0	0.3	2.0	1.1	64.1	49.0	
	Alexandria Twp	85.4R1	87.7	17.0	9.2	0.1	0.0	7.0	7.0	2.5	1.3	0.0	0.1	0.4	0.4	27.0	18.0	
	Kingwood Twp	87.7	94.5R2	28.6	16.5	2.8	3.6	12.4	16.4	1.7	2.3	0.0	0.2	0.9	1.0	46.4	40.0	
	Delaware Twp	94.5R2	100.4R2	27.5	17.5	0.1	0.7	8.6	15.6	0.1	0.4	0.0	0.2	1.0	1.9	37.3	36.3	
	West Amwell Twp	100.4R2	104.4R2	16.8	9.0	0.2	0.3	12.9	11.5	2.5	2.6	0.0	0.0	0.5	0.5	32.9	23.9	
			Subtotal	122.7	71.8	3.9	5.3	64.6	72.2	11.7	12.2	0.0	0.8	4.8	4.9	207.7	167.2	
Aboveground Facilities (for PennEast Mainline)																		
Gilbert Lateral Tap Site / MLV-9	Holland Twp	79.7R2	-	0.0	0.3	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.3	
MLV-10	Kingwood Twp	90.4R2	-	0.0	0.0	0.0	0.1	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.1	
			Subtotal	0.0	0.3	0.0	0.1	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.4	
Contractor Yards, Pipe Yards and Staging Areas																		
Hunterdon County		-	Subtotal	34.0	0.0	0.0	0.0	2.2	0.0	0.0	0.0	0.0	0.0	0.2	0.0	36.4	0.0	
Lambertville 36-inch Lateral																		
Hunterdon County	West Amwell Twp	LL- 0.0R2	LL- 1.4	5.0	3.1	0.0	0.0	8.6	5.3	0.8	0.3	0.0	0.0	0.0	0.0	14.4	8.7	
			Subtotal	5.0	3.1	0.0	0.0	8.6	5.3	0.8	0.3	0.0	0.0	0.0	0.0	14.4	8.7	
Aboveground Facilities (for Lambertville Lateral)																		
Lambertville Launcher Site / MLV-11	West Amwell Twp	ML- 101.0R2	-	0.0	0.0	0.0	0.0	0.0	2.2	0.0	0.0	0.0	0.0	0.0	0.0	0.0	2.2	
Algonquin and TETCO Interconnects	West Amwell Twp	LL-1.4	-	0.1	2.5	2.0	3.5	0.6	1.7	0.4	2.0	0.0	0.0	0.0	0.0	3.1	9.7	
			Subtotal	0.1	2.5	2.0	3.5	0.6	3.9	0.4	2.0	0.0	0.0	0.0	0.0	3.1	11.9	
Gilbert 12-inch Lateral																		
Hunterdon County	Holland Twp	GL- 0.0R2	GL- 0.6R2	0.4	0.9	0.0	0.1	0.3	1.0	0.3	0.6	0.0	0.0	0.0	0.0	1.0	2.6	

State/County/Facility	Municipality	Begin MP ¹	End MP ¹	Agricultural ²		Commercial / Industrial ³		Forest/ Woodland ⁴		Open Land ⁵		Open Water ⁶		Residential ⁷		Total ¹¹		
				Temp. ROW ⁹	Perm. ROW ¹⁰	Temp. ROW ⁹	Perm. ROW ¹⁰	Temp. ROW ⁹	Perm. ROW ^{8,10}	Temp. ROW ⁹	Perm. ROW ¹⁰	Temp. ROW ⁹	Perm. ROW ¹⁰	Temp. ROW ⁹	Perm. ROW ¹⁰	Temp. ROW ⁹	Perm. ROW ¹⁰	
Subtotal				0.4	0.9	0.0	0.1	0.3	1.0	0.3	0.6	0.0	0.0	0.0	0.0	1.0	2.6	
Aboveground Facilities (for Gilbert Lateral)																		
Etown and Gilbert Interconnects	Holland Twp	GL- 0.6R2	-	0.0	0.0	0.0	0.1	0.0	0.0	0.0	1.3	0.0	0.0	0.0	0.0	0.0	1.4	
Subtotal				0.0	0.0	0.0	0.1	0.0	0.0	0.0	1.3	0.0	0.0	0.0	0.0	0.0	1.4	
Access Roads																		
Hunterdon County		-	Subtotal	7.7	0.4	4.7	0.6	4.3	0.5	3.2	0.0	0.0	0.0	1.7	0.4	21.6	1.9	
Hunterdon County Subtotal				169.9	79.0	10.6	9.7	80.6	82.9	16.4	16.4	0.0	0.8	6.7	5.3	284.2	194.1	
Mercer County																		
PennEast Mainline																		
	Hopewell Twp	104.4R2	112.3R2	33.2	17.7	0.3	1.1	33.5	23.0	4.6	3.0	0.1	0.4	0.9	0.7	72.6	45.9	
Subtotal				33.2	17.7	0.3	1.1	33.5	23.0	4.6	3.0	0.1	0.4	0.9	0.7	72.6	45.9	
Aboveground Facilities																		
Subtotal				0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Contractor Yards, Pipe Yards and Staging Areas																		
Mercer County		-	Subtotal	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	
Access Roads																		
Mercer County		-	Subtotal	3.1	0.0	0.8	0.0	1.4	0.0	0.5	0.0	0.1	0.0	0.0	0.0	5.9	0.0	
Mercer County Subtotal				36.3	17.7	1.1	1.1	34.9	23.0	5.1	3.0	0.2	0.4	0.9	0.7	78.5	45.9	
Project Total				509.3	196.4	153.4	28.2	451.0	372.7	133.2	57.3	0.7	3.1	23.0	14.1	1270.6	671.8	

Notes:

1. All route deviations implemented after the September 2015 FERC Filing are denoted with an "R" and indicate a milepost equation. Mileposts with an "R1" indicate route deviations implemented and provided to FERC prior to the issuance of the Draft Environmental Impact Statement. Mileposts with an "R2" indicate route deviations implemented as part of this September 2016 Supplemental Filing. All mileposts without an "R" indicate that the route has not changed since the September 2015 Application.
2. Agricultural Land - Active cropland, pasture, orchards, vineyards, and/or hay fields;
3. Industrial Or Commercial Land - Electric power or gas utility stations, manufacturing or industrial plants, landfills, mines, quarries, commercial or retail facilities, and roads;
4. Forest/ Woodland - Tracts of upland forest or woodland that would be removed for the construction row or extra work or staging areas;
5. Open Land - Non-forested lands and maintained utility ROW;
6. Open Water – Water crossings greater than 100 feet.
7. Residential Land - Residential yards, residential subdivisions, and planned new residential developments;
8. Permanent impacts to forest/woodland were calculated for the entire 50-foot permanent pipeline ROW, however, only the management of the 30-foot wide cleared permanent ROW will require the permanent removal of trees in these forested areas.
9. Temp. ROW – Temporary ROW for construction of the project; includes temporary ROW and additional temporary workspace (ATWS). All units in acres and rounded to the nearest 0.1.
10. Perm. ROW – New permanent ROW; all units in acres and rounded to the nearest 0.1. Values of 0.0 represent impacts less than 0.05 acre and are included in the total project impacts.
11. The totals shown on this table may not equal the sum of addends due to rounding.