

FY 2010 - 2019 STATEWIDE TRANSPORTATION IMPROVEMENT PROGRAM
New Jersey Department of Transportation

Route 50, Tuckahoe River Bridge (2E 3B)

DB # 242 UPC 960429

MILEPOST(S) 6.30 - 7.50

COUNTY: Cape May Atlantic

MUNICIPALITY: Upper Twp. Corbin City

The existing bascule bridge carries two 10-foot travel lanes and a 10-foot shoulder. The replacement will be a fixed structure with a nine-foot, six-inch vertical clearance from Mean High Water Level on the same alignment. The new structure will have two 12-foot travel lanes and 6-foot shoulders, as well as a six-foot sidewalk on the northbound side of the bridge. A temporary structure will be constructed next to the existing structure to maintain traffic during construction. Additional roadway improvements will include signaling the Route 50 and Route 49 intersection as well as providing a 15-foot through lane and 12-foot left-turn lane northbound and a 12-foot through lane and 15-foot right-turn lane southbound. The intersection of Route 50 and Tuckahoe-Mount Pleasant Road will be reconfigured to allow for one-way operation of Tuckahoe-Mount Pleasant Road only. Traffic wishing to access Route 50 will be able to gain safer access to the highway through the reconstructed Marshall Avenue and Kendall Lane intersections. This project will be designed to be bicycle/pedestrian compatible.

The following Federal appropriations were allocated to this project. FY06 SAFETEA-LU/HPP \$3,200,000 (ID# NJ 185),(available 20% per year).

ASSET MANAGEMENT CATEGORY: Bridge Assets-Bridge Rehab and Replacement

LEGISLATIVE DISTRICT: 1 2

SPONSOR: NJDOT

STRUCTURE NO.: 0510152

MPO	Phase	Fund	Amounts in Millions of Dollars										
			FY 2010	FY 2011	FY 2012	FY 2013	FY 2014	FY 2015	FY 2016	FY 2017	FY 2018	FY 2019	
SJTPO	CON	BRIDGE		\$7.800									
SJTPO	CON	HPP20		\$2.920									
SJTPO	CON	STP		\$7.881									