


*New Jersey Department of Transportation*  
1035 Parkway Avenue, PO Box 600, Trenton, New Jersey 08625-0600



## *Baseline Document Change Announcement*

**ANNOUNCEMENT: BDC12S-14**

**DATE: November 21, 2012**

**SUBJECT: Shear Connectors**  
- Revision to Subparts/Subsection 506.03.03, 506.04 and 507.03.06 of the 2007 Standard Specifications for Road and Bridge Construction

Subparts/Subsection 506.03.03, 506.04 and 507.03.06 of the 2007 Standard Specifications for Road and Bridge Construction have been revised to remove the Shear Connector, Galvanized as an Item along with some editorial revisions to 507.03.06.

**The following revisions have been incorporated into the Standard Input SI2007 as of November 20, 2012.**

**506.03.03 Shear Connectors**

THE FIRST PARAGRAPH IS CHANGED TO:

Ensure that shear connectors conform to Section 7 of the ANSI/AWS D1.5 Bridge Welding Code.

**506.04 MEASUREMENT AND PAYMENT**

THE FOLLOWING ITEM IS DELETED:

<i>Item</i>	<i>Pay Unit</i>
SHEAR CONNECTOR, GALVANIZED	UNIT

**507.03.06 4-Bar Open Steel Parapet**

THE ENTIRE TEXT AS IT APPEARS IN THE SI IS CHANGED TO:

Ensure that the deck has cured for at least 14 days before placing concrete for 4-bar open steel parapet. Place concrete for 4-bar open steel parapet as specified in 504.03.02.D. Install as shown on the Plans.

**Implementation Code R (ROUTINE)**

Changes must be implemented in all applicable Department projects scheduled for Final Design Submission at least one month after the date of the BDC announcement. This will allow designers to make necessary plan, specifications, and estimate/proposal changes without requiring the need for an addenda or postponement of advertisement or receipt of bids.

**Recommended By:**

ORIGINAL SIGNED

---

Richard Jaffe  
Acting Director,  
Capital Program Support

RJ: KS: HP  
BDC12S-14.doc

**Approved By:**

ORIGINAL SIGNED

---

Richard T. Hammer  
Assistant Commissioner,  
Capital Program Management