

**New Jersey Department of Transportation**

1035 Parkway Avenue, PO Box 600, Trenton, New Jersey 08625-0600



**Baseline Document Change Announcement**

**ANNOUNCEMENT: BDC21S-15**

**DATE: January 21, 2022**

**SUBJECT: Rumble Strips**  
**- Revision to the 2019 Standard Specifications for Road and Bridge Construction, Subpart 610.03.07**

Subpart 610.03.07 of the 2019 Standard Specifications for Road and Bridge Construction has been revised in order to remove the application of fog seal during the construction of rumble strips.

**The following revisions have been incorporated into the 2019 Standard Specifications via 2019 Standard Inputs, SI2019:**

**610.03.07 Rumble Strip**

THE FOURTH PARAGRAPH IS CHANGED TO:

Ensure that after cutting centerline rumble strips, the centerline rumble strips are cleaned, all debris is collected and the surface is prepared as specified in 610.03.01.B before placing traffic stripes.

**Implementation Code R (ROUTINE)**

Changes must be implemented in all applicable Department projects scheduled for Final Design Submission at least one month after the date of the BDC announcement. This will allow designers to make necessary plan, specifications, and estimate/proposal changes without requiring the need for addenda or postponement of advertisement or receipt of bids.

**Recommended By:**

Handwritten signature of Paul F. Schneider in blue ink.

Paul F. Schneider  
Director  
Capital Program Support

**Approved By:**

Handwritten signature of Snehal Patel in blue ink.

Snehal Patel, P.E., PMP  
Assistant Commissioner  
Capital Program Management  
and State Transportation Engineer