SCOPE OF WORK

Wolverton Generator Installation

Vineland Developmental Center Vineland, Cumberland County, NJ

Project No. M1608-00

STATE OF NEW JERSEY

Honorable Philip D. Murphy, Governor Honorable Tahesha L. Way, Lt. Governor

DEPARTMENT OF THE TREASURY

Elizabeth Maher Muoio, Treasurer



DIVISION OF PROPERTY MANAGEMENT AND CONSTRUCTION

Thomas A. Edenbaum, Director

Date: May 01, 2025

PROJECT NO: M1608-00 DATE: May 01, 2025

TABLE OF CONTENTS

SEC'	TION	PAGE
I.	OBJECTIVE	4
II.	CONSULTANT QUALIFICATIONS	4
A.	CONSULTANT & SUB-CONSULTANT PRE-QUALIFICATIONS	4
III.	PROJECT BUDGET	4
A. B. C.	CONSTRUCTION COST ESTIMATE (CCE) CURRENT WORKING ESTIMATE (CWE) CONSULTANT'S FEES.	4
IV.	PROJECT SCHEDULE	5
A. B.	SCOPE OF WORK DESIGN & CONSTRUCTION SCHEDULECONSULTANT'S PROPOSED DESIGN & CONSTRUCTION SCHEDULE	5 6
V.	PROJECT SITE LOCATION & TEAM MEMBERS	6
	PROJECT SITE ADDRESS PROJECT TEAM MEMBER DIRECTORY 1. DPMC Representative:	7
VI.	PROJECT DEFINITION	7
A. B.	BACKGROUNDFUNCTIONAL DESCRIPTION	
VII.	CONSULTANT DESIGN RESPONSIBILITIES	8
_	INVESTIGATION PHASE GENERATOR INSTALLATION FUNCTIONAL DESIGN CRITERIA General:	9
C. D. C.	2. Location: ADDITIONAL REQUIREMENTS: DESIGN MEETINGS & PRESENTATIONS. EXISTING DOCUMENTATION	12 13
VIII	I. PERMITS & APPROVALS	14
A. B.	NJ UNIFORM CONSTRUCTION CODE PLAN REVIEW AND PERMITOTHER REGULATORY AGENCY PERMITS, CERTIFICATES AND APPROVAL	
IX.	ENERGY REBATE AND INCENTIVE PROGRAMS	18

PROJECT NO: M1608-00 DATE: May 01, 2025

Χ.	ALLOWANCES	18
A.	PLAN REVIEW AND PERMIT FEE ALLOWANCE	
1.	Permits:	
2.	Permit Costs:	
3.	Applications:	
4.	Consultant Fee:	19
XI.	SOW SIGNATURE APPROVAL SHEET	20
XII.	CONTRACT DELIVERABLES	21
XIII.	EXHIBITS	21
	A. SAMPLE PROJECT SCHEDULE FORMAT	
	B. PROJECT SITE LOCATION MAP	
	C. PHOTOS	
	D. VINELAND DEVELOPMENTAL CENTER REGULATION	ΓΙΟΝS

PROJECT NO: M1608-00 DATE: May 01, 2025

I. OBJECTIVE

The objective of this project is to install a new generator and associated automated transfer switch and a minimum of 72 hours diesel fuel supply for the Wolverton building at Vineland Developmental Center. Upgrade the electrical bus as needed to accommodate the new generator. See **Exhibit 'B'** for site location map.

II. CONSULTANT QUALIFICATIONS

A. CONSULTANT & SUB-CONSULTANT PRE-QUALIFICATIONS

The Consultant shall be a firm pre-qualified with the Division of Property Management & Construction (DPMC) in the following discipline(s):

• P002 Electrical Engineering

The Consultant shall also have in-house capabilities or Sub-Consultants pre-qualified with DPMC in:

• P007 Structural Engineering

As well as, <u>any and all</u> other Architectural, Engineering and Specialty Disciplines necessary to complete the project as described in this Scope of Work (SOW).

III. PROJECT BUDGET

A. CONSTRUCTION COST ESTIMATE (CCE)

The initial Construction Cost Estimate (CCE) for this project is \$331,763.96

The Consultant shall review this Scope of Work and provide a narrative evaluation and analysis of the accuracy of the proposed project CCE in its technical proposal based on its professional experience and opinion.

B. CURRENT WORKING ESTIMATE (CWE)

The Current Working Estimate (CWE) for this project is \$524,187

The CWE includes the construction cost estimate and all consulting, permitting and administrative fees.

PROJECT NO: M1608-00 DATE: May 01, 2025

The CWE is the client agency's financial budget based on this project Scope of Work and shall not be exceeded during the design and construction phases of the project unless DPMC approves the change in Scope of Work through a Contract amendment.

C. CONSULTANT'S FEES

The construction cost estimate for this project *shall not* be used as a basis for the Consultant's design and construction administration fees. The Consultant's fees shall be based on the information contained in this Scope of Work document and the observations made and/or the additional information received during the pre-proposal meeting.

IV. PROJECT SCHEDULE

A. SCOPE OF WORK DESIGN & CONSTRUCTION SCHEDULE

The following schedule identifies the estimated design and construction phases for this project and the estimated durations.

ESTIMATED DURATION (Calendar Days) PROJECT PHASE 1. Site Access Approvals & Schedule Design Kick-off Meeting 14 2. Investigation Phase 28 14 Project Team & DPMC Plan/Code Unit Review & Comment 42 3. Design Development Phase 14 Project Team & DPMC Plan/Code Unit Review & Comment 42 4. Final Design Phase 14 Project Team & DPMC Plan/Code Unit Review & Approval 7 5. Final Design Re-Submission to Address Comments Project Team & DPMC Plan/Code Unit Review & Approval 14 6. DCA Submission Plan Review **30** 7. Permit Application Phase 7 Issue Plan Release 8. Bid Phase 42 9. Award Phase 28

PROJECT NO: M1608-00 DATE: May 01, 2025

10. Construction Phase

180*

11. Project Close Out Phase

30

B. CONSULTANT'S PROPOSED DESIGN & CONSTRUCTION SCHEDULE

*Construction Phase duration to be adjusted for long lead items as necessary. The Consultant shall submit a project design and construction schedule with its technical proposal that is similar in format and detail to the schedule depicted in **Exhibit 'A'**. The schedule developed by the Consultant shall reflect its recommended project phases, phase activities, activity durations.

A written narrative shall also be included with the technical proposal explaining the schedule submitted and the reasons why and how it can be completed in the time frame proposed by the Consultant.

This schedule and narrative will be reviewed by the Consultant Selection Committee as part of the evaluation process and will be assigned a score commensurate with clarity and comprehensiveness of the submission.

V. PROJECT SITE LOCATION & TEAM MEMBERS

A. PROJECT SITE ADDRESS

The location of the project site is:

Vineland Developmental Center (Wolverton) 1676 East Landis Avenue Vineland, Cumberland County, New Jersey 08362

See Exhibit 'B' for the project site location map.

PROJECT NO: M1608-00 DATE: May 01, 2025

B. PROJECT TEAM MEMBER DIRECTORY

The following are the names, addresses, and phone numbers of the Project Team members.

1. DPMC Representative:

Name: Darren Comegys, Project Design Manager

Address: Division of Property Management & Construction

20 West State Street, 3rd Floor

Trenton, NJ 08608-1206

Phone No: (609)690-3298

E-Mail: Darren.Comegys@treas.nj.gov

2. Department of Human Services Representative:

Name: Christian Casteel, Senior Executive Service

Address: Department of Human Services

222 South Warren Street

Trenton, NJ 08625

Phone No: (609) 472-5622

E-Mail: Christian.Casteel@dhs.nj.gov

Name: Patrick Littleford, Project Manager Address: Department of Human Services

222 South Warren Street

Trenton, NJ 08625

Phone No: (609) 940-9964

E-Mail: Patrick.Littleford@dhs.nj.gov

VI. PROJECT DEFINITION

A. BACKGROUND

The Vineland Developmental Center was founded in 1888, and provides a comprehensive array of residential, habilitation, behavioral and health care services for women and men with intellectual and developmental disabilities. Vineland Developmental Center is a 205 Bed Intermediate Care Facility with service to the surrounding community.

PROJECT NO: M1608-00 DATE: May 01, 2025

B. FUNCTIONAL DESCRIPTION

Wolverton Cottage is a one-story block steel frame building. The Department of Human Services (DHS) is seeking to install a generator and associated automated transfer switch and a minimum of 72 hours supply of diesel fuel for the Wolverton building at the Vineland Developmental Center.

As a priority, the generator shall back up the oxygen systems within the building. It will be the Consultant's responsibility to determine what building loads fall under what classification and how the systems are classed, designed and installed under the (3) NEC code classifications.

The project shall include a coordination study to ensure that the generator does not operate simultaneously with the campus generators.

VII. CONSULTANT DESIGN RESPONSIBILITIES

A. INVESTIGATION PHASE

1. Generator Size & Capacity Investigation:

The Consultant shall meet and coordinate with NJDHS Staff and VDC Staff to outline all functional requirements necessary for the design to install the generator system and ATS. The Consultant shall document interviews with the Client Agency Staff and with the VDC Staff to identify their requirements and needs.

The Consultant shall investigate the existing conditions of the site and confirm the generator classification, size, condition, ratings, generator exhaust breaching and arrangement of the existing electrical equipment and power distribution system.

Evaluate the existing emergency electrical distribution system and normal power interface. Check the adequacy of the existing equipment with proposed new equipment, as required by the facility and by the client agency. Make the necessary design changes to the electrical system to achieve the required connections for the capacity of the new generator.

A coordination study shall be performed to ensure the new generator does not operate simultaneously with existing campus generators.

Items to investigate shall include, but not be limited to, the electrical supply system, electrical system devices and operation, controls, wiring, building penetrations, and generator exhaust breaching and cost estimates.

PROJECT NO: M1608-00 DATE: May 01, 2025

This information shall also be used to identify the areas of the building that will be impacted by the new construction.

2. Electrical Bus Upgrade Investigation:

The Consultant shall conduct a survey of the existing electrical bus and upgrade it to be compatible with the new generator system. Analyze the electrical bus configuration, battery storage system and charging infrastructure, and capacity. Document the location of the electrical panels, zone detectors, sensors, wiring & raceways, and all equipment and systems.

3. Title V Air Permit:

The Consultant shall investigate the requirements for DEP permit modification and present this information, along with any required DEP prior approvals or pre-construction permits, as part of their Investigation Phase report. The Consultant may require coordination with the DOH air permitting Consultant.

4. Investigation Report and Presentation:

Provide three (3) bound copies of the Generator Size/Capacity, Electrical Bus Upgrade and ATS Capacity Investigation Report to the Project Manager. The document shall be presented in an 8 ½" x 11" bound booklet that contains a Table of Contents describing all of the information contained in the document and an Executive Summary with a list of recommendations.

An oral presentation shall be made to the Project Team describing the findings of the investigation conducted and the recommendations for upgrade or replacement. The Consultant may not proceed with the design phase of the project until the Project Team has reviewed the report and approved the recommendations made for this project.

All supporting documentation such as calculations, photographs, drawings, catalog cuts, correspondence, meeting minutes, and any other data obtained shall be included in the report appendix for reference.

All cost data shall be in sufficient detail for each related division of the latest CSI format and shall be summarized on the DPMC 38 Cost Analysis form(s).

B. GENERATOR INSTALLATION FUNCTIONAL DESIGN CRITERIA

1. General:

Guided by the results of the Investigation Phase, the Consultant shall provide Design; Construction Administration, Permitting and Bid/Award services to install the new generator and ATS system to back up the Wolverton building at Vineland Developmental Center. The

PROJECT NO: M1608-00 DATE: May 01, 2025

Consultant is to ensure the location and installation are following all applicable codes, regulations and requirements.

The design requirements of this project shall include but not be limited to the following items identified below. These items are meant to be used as a design guide; however, it shall be the responsibility of the Consultant to determine the final design criteria to make a complete working installation based on their experience with projects similar in size and scope to this one, and the equipment manufacturer's requirements.

2. Location:

The Consultant shall investigate locations, provide recommendations, and identify requirements. The Consultant shall coordinate the generator location with the DHS and VDC.

3. New Generator:

The Consultant shall determine the new generator classifications, power, capacity and size according to the full load requirements to back up the building, with oxygen systems as a priority. DHS requests the new generator design to be under full load to back up the building in case of loss of electricity and power outage.

Investigate industry-recognized manufacturers of the installation components to be specified in the design documents. Items to consider shall include, but not be limited to product reliability and performance, manufacturer's years of service, equipment costs, warranties, guarantees, delivery schedule, compatibility with the existing equipment and related components, physical size, etc. Note that the names of three "equal" manufacturers shall be identified and included in the design documents for reference.

The consultant shall evaluate the generator design criteria based on a thorough evaluation of requirements of NEC Articles 700, 701, and 702, as well as the Center for Medicaid and Medicare Services (CMS), NFPA 99 2012, including class and type, paying close attention to the 10 second switching requirement.

4. Drawings:

Provide a Single- Line Diagram to show new generator tie-in details that identifies the name, location, and rating of all switchgears, transformers and generator control panel components. Include all demand factors, switch and panel schedules, wiring identification codes, drawing legends, etc. on the documents.

Provide short circuit study and selective coordination study of over-current protection devices. Provide details on the drawings of any special assembly, electrical tie in requirements, or any other governing or limiting factor of the manufacturer's system component. The drawings shall

PROJECT NO: M1608-00 DATE: May 01, 2025

be prepared with sufficient flexibility to accommodate variations among the equipment manufacturers approved by the Project Team.

5. Generator Pad:

The Consultant shall provide the design and specifications to construct a new concrete pad for the new generator and the new day tank. Provide signed and sealed structural calculations, verifying that they will support the new equipment.

6. Control Equipment:

Provide the design and specification for a master control system, new installation circuit breaker switchgear, and all further details regarding the sequence of operations.

7. Generator Annunciator Panel:

The Consultant shall include in their design local annunciator panels and wireless annunciator panels at approved occupied workstations within the VDC facility.

8. Equipment Installation Schedule:

Develop a proposed sequenced phased construction schedule that identifies how the new generator, components and other related items are to be installed. Minimize the required downtime and switchover periods. Temporary emergency backup power shall be provided if required. The final approved schedule shall be included in Division 1 of the specification for Contractor reference during bidding.

Determine all construction schedule coordination requirements with the local Electrical Utility Company and representatives of the VDC.

9. Equipment Tests:

The design documents shall include detailed test requirements of the new equipment and systems. The Contractor and a certified testing lab shall perform operational tests of the completed installation to certify their proper operation. All test results shall be bound in a booklet and three (3) copies presented to the Project Manager for record.

10. Spare Parts:

A critical spare parts list shall be prepared for all appropriate items and purchased as part of this project. The Consultant shall include provisions for the manufacture/vendor of the equipment to provide critical spare and maintenance parts as part of this project. All of the critical parts shall be reviewed and approved by the Client Agency.

PROJECT NO: M1608-00 DATE: May 01, 2025

C. ADDITIONAL REQUIREMENTS:

The following miscellaneous general requirements shall apply to this project.

1. Contractor's Use of the Premises:

The Consultant shall review the various VDC policies and procedures as indicated in **Exhibit** '**D**' attached at the end of this scope. Any additional use requirements shall be reviewed and approved by the Using Agency.

2. Fire Protection:

Address the fire protection requirements during any demolition and installation of equipment and systems. Language shall be included in the design documents that states any acetylene, welding, brazing, and soldering equipment, or other potential source of fire ignition cannot be used on the construction site until a fire watch program has been submitted by the Contractor and approved by the Consultant and Project Team members. The Contractor shall coordinate fire watch activities with the client agency. Language shall be included in the design documents to require that contractors obtain hot work permits. There are two – a one-time hot work permit issued by DCA and a daily hot work permit issued by the facility based on the contractor's scheduled hot work activities.

3. Working Hours:

Working hours shall be as determined by the facility staff. Consultant and Contractors are advised that due to the nature of this Facility, shift work and/or phased construction may be required. All costs related to site meetings, project inspections, regularly scheduled job meetings, etc., shall be included in the Consultant's base bid.

4. Equipment Spare Parts List:

A spare parts list shall be prepared and items purchased, including a storage cabinet with keyed lock, as part of this project for all critical items necessary for the successful operation of the generator system.

5. Equipment Training:

The authorized service representative(s) shall train the facility personnel in the operation and maintenance of the new equipment and systems installed, including step-by-step troubleshooting with required test equipment. The representative shall be familiar with the installed items and have a minimum of 3 years of training experience.

PROJECT NO: M1608-00 DATE: May 01, 2025

Three (3) copies of the operation and maintenance manuals shall be prepared and presented to the Project Manager for reference.

6. Construction Work Area Requirements:

Indicate the location and dimensioned details for any temporary construction barriers for security and/or safety, plastic barriers for dust and dirt containment, and special covers for equipment protection during the removal and installation of the new equipment and system components. The design documents shall describe all salvage items that are to be retained by Client Agencies.

D. DESIGN MEETINGS & PRESENTATIONS

1. Design Meetings:

Conduct the appropriate number of review meetings with the Project Team members during each design phase of the project so they may determine if the project meets their requirements, question any aspect of the contract deliverables, and make changes where appropriate. The Consultant shall describe the philosophy and process used in the development of the design criteria and the various alternatives considered to meet the project objectives. Selected studies, sketches, cost estimates, schedules, and other relevant information shall be presented to support the design solutions proposed. Special considerations shall also be addressed such as: Contractor site access limitations, utility shutdowns and switchover coordination, phased construction and schedule requirements, security restrictions, available swing space, material and equipment delivery dates, etc.

It shall also be the responsibility of the Consultant to arrange and require all critical Sub-Consultants to be in attendance at the design review meetings.

Record the minutes of each design meeting and distribute within three (3) calendar days to all attendees and those persons specified to be on the distribution list by the Project Manager.

2. Design Presentations:

The minimum number of design presentations required for each phase of this project is identified below for reference:

Investigation Phase: One (1) oral presentation at phase completion.

One (1) working meeting halfway through phase.

One (1) oral presentation at phase completion.

Design Development Phase: One (1) oral presentation at phase completion.

PROJECT NO: M1608-00 DATE: May 01, 2025

One (1) working meeting halfway through phase.

One (1) oral presentation at phase completion.

Final Design Phase: One (1) oral presentation at phase completion.

One (1) working meeting halfway through phase.

One (1) oral presentation at phase completion.

C. EXISTING DOCUMENTATION

Copies of the following documents will be provided to each Consulting firm at the pre-proposal meeting to assist in the bidding process.

- (M080: Long Term Care Facility Vineland State School, 11-1979, and by Architects II)
- (M0715-02: Electrical System Distribution VDC East Campus, 05-19-1988, and by Stone & Webster Engineering Corporation)
- (M1343-00: Central Fire Notification System Improvements VDC East Campus, 10-01-2003, and by COLM Engineering)
- (Proposed Extension of O2 System, 03-19-2014, and by PMH Associates, INC.)
- (New Oxygen and Vacuum Outlets, 04-02-2020, and by Lammey & Gorgio)

Review these documents and any additional information that may be provided at a later date such as reports, studies, surveys, equipment manuals, as-built drawings, etc. The State does not attest to the accuracy of the information provided and accepts no responsibility for the consequences of errors by the use of any information and material contained in the documentation provided. It shall be the responsibility of the Consultant to verify the contents and assume full responsibility for any determination or conclusion drawn from the material used. If the information provided is insufficient, the Consultant shall take the appropriate actions necessary to obtain the additional information required.

All original documentation shall be returned to the provider at the completion of the project.

VIII. PERMITS & APPROVALS

A. NJ UNIFORM CONSTRUCTION CODE PLAN REVIEW AND PERMIT

The project construction documents must comply with the latest adopted edition of the NJ Uniform Construction Code (NJUCC).

PROJECT NO: M1608-00 DATE: May 01, 2025

The latest NJUCC Adopted Codes and Standards can be found at:

http://www.state.nj.us/dca/divisions/codes/codreg/

1. NJ Uniform Construction Code (NJUCC) Plan Review

Consultant shall determine the cost of the NJUCC Plan Review by DCA and provide this information to DHS. DHS will pay the NJUCC Plan Review Fee.

Upon approval of the Final Design Phase Submission by DPMC, the Consultant shall submit the construction documents to the Department of Community Affairs (DCA), Bureau of Construction Project Review to secure a complete plan release.

As of July 25, 2022, the Department of Community Affairs (DCA) is only accepting digital signatures and seals issued from a third party certificate authority.

Procedures for submission to the DCA Plan Review Unit can be found at:

https://www.state.nj.us/dca/divisions/codes/forms/pdf_bcpr/pr_app_guide.pdf

Consultant shall complete the "Project Review Application" and include the following on Block 5 as the "Owner's Designated Agent Name":

Trevor M. Dittmar, DPMC PO Box 235 Trenton, NJ 08625-0235 Trevor.Dittmar@treas.nj.gov 609-984-5529

The Consultant shall complete the NJUCC "Plan Review Fee Schedule", determine the fee due and pay the NJUCC Plan Review fees, refer to Paragraph X.A. The NJUCC "Plan Review Fee Schedule" can be found at:

http://www.state.nj.us/dca/divisions/codes/forms/pdf_bcpr/pr_fees.pdf

2. NJ Uniform Construction Code Permit

Upon receipt of a complete plan release from the DCA Bureau of Construction Project Review, the Consultant shall complete the NJUCC permit application and all applicable technical subcode sections. The "Agent Section" of the application and certification section of the building sub-code section shall be signed. These documents, with six (6) sets of DCA approved, signed and sealed construction documents shall be forwarded to the DPMC Project Manager.

PROJECT NO: M1608-00 DATE: May 01, 2025

The Consultant may obtain copies of all NJUCC permit applications at the following website:

https://www.nj.gov/dca/divisions/codes/resources/constructionpermitforms.html

All other required project permits shall be obtained and paid for by the Consultant in accordance with the procedures described in Paragraph VIII.B.

3. Prior Approval Certification Letters:

The issuance of a construction permit for this project may be contingent upon acquiring various "prior approvals" as defined by N.J.A.C. 5:23-1.4. It is the Consultant's responsibility to determine which prior approvals, if any, are required. The Consultant shall submit a general certification letter to the DPMC Plan & Code Review Unit Manager during the Permit Phase of this project that certifies all required prior approvals have been obtained.

In addition to the general certification letter discussed above, the following specific prior approval certification letters, where applicable, shall be submitted by the Consultant to the DPMC Plan & Code Review Unit Manager: Soil Erosion & Sediment Control, Water & Sewer Treatment Works Approval, Coastal Areas Facilities Review, Compliance of Underground Storage Tank Systems with N.J.A.C. 7:14B, Pinelands Commission, Highlands Council, Well Construction and Maintenance; Sealing of Abandoned Wells with N.J.A.C. 7:9D, Certification that all utilities have been disconnected from structures to be demolished, Board of Health Approval for Potable Water Wells, Health Department Approval for Septic Systems. It shall be noted that in accordance with N.J.A.C. 5:23-2.15(a)5, a permit cannot be issued until the letter(s) of certification is received.

4. Multi-building or Multi-site Permits:

A project that involves many buildings and/or sites requires that a separate permit shall be issued for each building or site. The Consultant must determine the construction cost estimate for *each* building and/or site location and submit that amount where indicated on the permit application.

5. Special Inspections:

In accordance with the requirements of the New Jersey Uniform Construction Code N.J.A.C. 5:23-2.20(b), Bulletin 03-5 and Chapter 17 of the International Building Code, the Consultant shall be responsible for the coordination of all special inspections during the construction phase of the project.

Bulletin 03-5 can be found at:

https://www.nj.gov/dca/codes/publications/pdf_bulletins/b_03_5.pdf

PROJECT NO: M1608-00 DATE: May 01, 2025

a. Definition:

Special inspections are defined as an independent verification by a certified special inspector for **Class I buildings and smoke control systems in any class building**. The special inspector is to be independent from the Contractor and responsible to the Consultant so that there is no possible conflict of interest.

Special inspectors shall be certified in accordance with the requirements in the New Jersey Uniform Construction Code.

b. Responsibilities:

The Consultant shall submit with the permit application, a list of special inspections and the agencies or special inspectors that will be responsible to carry out the inspections required for the project. The list shall be a separate document, on letter head, signed and sealed.

B. OTHER REGULATORY AGENCY PERMITS, CERTIFICATES AND APPROVALS

The Consultant shall identify and obtain all other State Regulatory Agency permits, certificates, and approvals that will govern and affect the work described in this Scope of Work. An itemized list of these permits, certificates, and approvals shall be included with the Consultant's Technical Proposal and the total amount of the application fees should be entered in the Fee Proposal line item entitled, "Plan Review and Permit Fee Allowance."

The Consultant may refer to the Division of Property Management and Construction "Procedures for Architects and Engineers Manual", Paragraph "9. REGULATORY AGENCY APPROVALS" which presents a compendium of State permits, certificates, and approvals that may be required for this project.

The Consultant shall determine the appropriate phase of the project to submit the permit application(s) in order to meet the approved project milestone dates.

Where reference to an established industry standard is made, it shall be understood to mean the most recent edition of the standard unless otherwise noted. If an industry standard is found to be revoked, or should the standard have undergone substantial change or revision from the time that the Scope of Work was developed, the Consultant shall comply with the most recent edition of the standard.

PROJECT NO: M1608-00 DATE: May 01, 2025

IX. ENERGY REBATE AND INCENTIVE PROGRAMS

The Consultant shall review any and all programs on the State and Federal level to determine if any proposed upgrades to the mechanical and/or electrical equipment and systems for this project qualify for approved rebates and incentives.

The Consultant shall review the programs available on the "New Jersey's Clean Energy Program" website at: http://www.njcleanenergy.com as well as federal websites and New Jersey electric and gas utility websites to determine if and how they can be applied to this project.

The Consultant shall identify all applicable rebates and incentives in their technical proposal and throughout the design phase.

The Consultant shall be responsible to complete the appropriate registration forms and applications, provide any applicable worksheets, manufacturer's specification sheets, calculations, attend meetings, and participate in all activities with designated representatives of the programs and utility companies to obtain the entitled financial incentives and rebates for this project.

All costs associated with this work shall be estimated by the Consultant and the amount included in the base bid of its fee proposal.

X. ALLOWANCES

A. PLAN REVIEW AND PERMIT FEE ALLOWANCE

The Consultant shall obtain and pay for all of the project permits in accordance with the guidelines identified below. This allowance is only for plan review or permits that the consultants foresee in addition to or beyond UCC/DCA plan review and permitting.

1. Permits:

The Consultant shall determine the various permits, certificates, and approvals required to complete this project.

2. Permit Costs:

The Consultant shall estimate the application fee costs for all of the required project permits, certificates, and approvals (excluding the NJ Uniform Construction Code permit and DCA plan review fee) and include that amount in its fee proposal line item entitled "Plan Review and

PROJECT NO: M1608-00 DATE: May 01, 2025

Permit Fee Allowance". A breakdown of each permit and application fee shall be attached to the fee proposal for reference.

NOTE: The NJ Uniform Construction Code permit and DCA Plan Review are excluded since they will be paid for by the State.

3. Applications:

The Consultant shall complete and submit all permit applications to the appropriate permitting authorities and the costs shall be paid from the Consultant's permit fee allowance. A copy of the application(s) and the original permit(s) obtained by the Consultant shall be given to the DPMC Project Manager for distribution during construction.

4. Consultant Fee:

The Consultant shall determine what is required to complete and submit the permit applications, obtain supporting documentation, attend meetings, etc., and include the total cost in the base bid of its fee proposal under the "Permit Phase" column.

Any funds remaining in the permit allowance will be returned to the State at the close of the project.

PROJECT NO: M1608-00 DATE: May 01, 2025

XI. SOW SIGNATURE APPROVAL SHEET

This Scope of Work shall not be considered a valid document unless all signatures appear in each designated area below.

The client agency approval signature on this page indicates that they have reviewed the design criteria and construction schedule described in this project Scope of Work (including the subsequent contract deliverables and exhibits) and verifies that the work will not conflict with the existing or future construction activities of other projects at the site.

SOW PREPARED BY	Cecile Guirguis	05-01-2025
	CECILE GUIRGUIS, PROJECT MANAGER DPMC PROJECT PLANNING & INITIATION	DATE
SOW APPROVED BY	JAMES WRIGHT, MANAGER DPMC PROJECT PLANNING & INITIATION	5/1/2025 DATE
SOW APPROVED BY	CHRISTIAN CASTEEL, DIRECTOR CLIENT AGENCY REPRESENTATIVE	5/1/25 DATE
SOW APPROVED BY	Darren Comegys DARREN COMEGYS, PROJECT MANAGER DPMC PROJECT MANAGEMENT GROUP	5/1/25 DATE
SOW APPROVED BY	: Cantle M. Barrard JANETTE M. BARNARD, DEPUTY DIRECTOR DIV PROPERTY MGT & CONSTRUCTION	5.29.25 DATE

PROJECT NO: M1608-00 DATE: May 01, 2025

XII. CONTRACT DELIVERABLES

The following are checklists listing the Contract Deliverables that are required at the completion of each phase of this project. The Consultant shall refer to the DPMC publication entitled "Procedures for Architects and Engineers," 3.0 Edition, dated September 2022 available at https://www.nj.gov/treasury/dpmc/Assets/Files/ProceduresforArchitectsandEngineers.pdf for a detailed description of the deliverables required for each submission item listed. References to the applicable paragraphs of the "Procedures for Architects and Engineers" are provided.

Note that the Deliverables Checklist may include submission items that are "S.O.W. Specific Requirements". These requirements will be defined in the project specific scope of work and included on the deliverables checklist.

This project includes the following phases with the deliverables noted as "Required by S.O.W" on the Deliverables Checklist:

- INVESTIGATION PHASE
- DESIGN DEVELOPMENT PHASE
- FINAL DESIGN PHASE
- PERMIT APPLICATION PHASE
- BIDDING AND CONTRACT AWARD
- CONSTRUCTION PHASE
- PROJECT CLOSE-OUT PHASE

XIII. EXHIBITS

- A. SAMPLE PROJECT SCHEDULE FORMAT
- B. PROJECT SITE LOCATION MAP
- C. PHOTOS
- D. VINELAND DEVELOPMENTAL CENTER REGULATIONS

END OF SCOPE OF WORK

Deliverables Checklist Investigation Phase

A/E Name:		
-----------	--	--

A/E Manual		Required by S.O.W.		Previously Submitted		Included	
Reference	Submission Item	Yes	No	Yes	No	Yes	No
11.5.1.	A/E Statement of Site Visit						
11.5.2	Narrative Description of Project						
11.5.3.	Space Analysis						
11.5.4.	Special Features						
11.5.5.	Site Evaluation						
11.5.6.	Subsurface Investigation						
11.5.7.	Surveys						
11.5.8.	Arts Inclusion						
11.5.9.	Design Rendering						
11.5.10.	Regulatory Approvals						
11.5.11.	Utility Availability						
11.5.12.	Diagrammatic Sketches/Drawings (6 Sets)						
11.5.13.	Specifications (6 Sets)						
11.5.14.	Current Working Estimate/Cost Analysis						
11.5.15.	Project Schedule						
11.5.16.	Formal Presentation						
11.5.17.	Scope of Work Compliance Statement						
11.5.18.	Advisability Study Deliverables Checklist						
S.O.W. Reference	S.O.W. Specific Requirements				T	ī	

hall be completed by the Design Consultant and in the DPMC the status of all the deliverables require				sion to
Consultant Signature	 	 Date	 	

Deliverables Checklist Design Development Phase

A/E Name:

A/E Manual		Required by S.O.W.		Previously Submitted		Enclosed	
Reference	Submission Item	Yes	No	Yes	No	Yes	No
14.4.1.	A/E Statement of Site Visit						
14.4.2.	Narrative Description of Project						
14.4.3.	Building Code Information Questionnaire						
14.4.4.	Space Analysis						
14.4.5.	Special Features						
14.4.6.	Catalog Cuts						
14.4.7.	Site Evaluation						
14.4.8.	Subsurface Investigation						
14.4.9.	Surveys						
14.4.10.	Arts Inclusion						
14.4.11.	Design Rendering						
14.4.12.	Regulatory Approvals						
14.4.13.	Utility Availability						
14.4.14.	Drawings (6 Sets)						
14.4.15.	Specifications (6 Sets)						
14.4.16.	Current Working Estimate/Cost Analysis						
14.4.17.	Project Schedule						
14.4.18.	Formal Presentation						
14.4.19.	Plan Review/Scope of Work Compliance Statement						
14.4.20.	Design development Phase Deliverables Checklist						
S.O.W. Reference	S.O.W. Specific Requirements						

his checklist shall be completed by the Design Consultant and included as the cover sheet of this submission to
ocument to the DPMC the status of all the deliverables required by the project specific Scope of Work.

Date

Consultant Signature

Deliverables Checklist Final Design Phase

A/E Name:

A/E Manual		Required by S.O.W.		Previously Submitted		Enclosed	
Reference	Submission Item	Yes	No	Yes	No	Yes	No
15.4.1.	A/E Statement of Site Visit						
15.4.2.	Narrative Description of Project						
15.4.3.	Building Code Information Questionnaire						
15.4.4.	Space Analysis						
15.4.5.	Special Features						
15.4.6.	Catalog Cuts						
15.4.7.	Site Evaluation						
15.4.8.	Subsurface Investigation						
15.4.9.	Surveys						
15.4.10.	Arts Inclusion						
15.4.11.	Design Rendering						
15.4.12.	Regulatory Approvals						
15.4.13.	Utility Availability						
15.4.14.	Drawings (6 Sets)						
15.4.15.	Specifications (6 Sets)						
15.4.16.	Current Working Estimate/Cost Analysis						
15.4.17.	Project Schedule						
15.4.18.	Formal Presentation						
15.4.19.	Plan Review/Scope of Work Compliance Statement						
15.4.20.	Final Design Phase Deliverables Checklist						
S.O.W. Reference	S.O.W. Specific Requirements						

This checklist shall be completed by the Design Consultant and included as the cover sheet of this submission to
document to the DPMC the status of all the deliverables required by the project specific Scope of Work.

Date

Consultant Signature

Deliverables Checklist Permit Application Phase

A/E Manual		-	red by .W.	Previ Subm	-	Enclo	osed
Reference	Submission Item	Yes	No	Yes	No	Yes	No
16.1.	N.J. UCC Permit Application						
16.4.	Drawings, Signed and Sealed (6 Sets)						
16.5.	Specifications, Signed and Sealed (6 Sets)						
16.6.	Current Working Estimate/Cost Analysis						
16.7.	Project Schedule						
16.8.	Plan Review/Scope of Work Compliance Statement						
16.9.	Permit Application Phase Deliverables Checklist						
S.O.W. Reference	S.O.W. Specific Requirements	-					

Deliverables Checklist Bidding and Contract Award Phase

A/E Manual		Requir S.O	-	Previ Subm	-	Enclo	osed
Reference	Submission Item	Yes	No	Yes	No	Yes	No
17.1.1.	Notice of Advertising						
17.1.2.	Bid Proposal Form						
17.1.3.	Bid Clearance Form						
17.1.4.	Drawings (6 Sets)						
17.1.5.	Specifications (6 Sets)						
17.1.6.	Construction Schedule						
17.3	Pre-Bid Conference/Mandatory Site Visit						
17.3.1.	Meeting Minutes						
17.4	Bulletins						
17.5	Post Bid Meeting						
17.6.	Contract Award "Letter of Recommendation"						
17.8.	Bid Protests - Hearings						
17.9.	Bidding and Contract Award Phase						
	Deliverables Checklist						
S.O.W. Reference	S.O.W. Specific Requirements						

Date

Consultant Signature

Deliverables Checklist Construction Phase

A/E Name:				
	Domition	بيط امي	Duardanala	

A/E Manual		-	red by		ously	Encl	osed
Reference	Submission Item	Yes	No	Yes	No	Yes	No
18.2.	Pre-Construction Meeting						
18.3.	Submittal Log						
18.4.	Construction Schedule						
18.5.	Project Progress Meetings						
18.7.	Contractor's Invoicing and Payment Process						
18.8.	Contractor Submittals						
18.10.	Testing						
18.11.	Shop Drawings (6 Sets)						
18.12.	As-Built & Record Set Drawings (6 Sets)						
18.13.	Change Orders						
18.14.	Construction Photographs						
18.15.	Field Observations						
18.17.	Construction Phase Deliverables Checklist						
S.O.W. Reference	S.O.W. Specific Requirements						

his checklist shall be completed by the Design Consultant and included as the cover sheet of this submission to
ocument to the DPMC the status of all the deliverables required by the project specific Scope of Work.

Consultant Signature	Date	

Deliverables Checklist Project Close-Out Phase

A/E Name:			
	Required by	Previously	
A / E N/10 minut	50.14	Submitted	Englosed

A/E Manual			red by		ously	Encl	osed
Reference	Submission Item	Yes	No	Yes	No	Yes	No
19.3.	Development of Punch List and Inspection Reports						
19.5.	Determination of Substantial Completion						
19.6.	Correction/Completion of Punch List						
19.7.	Submission of Close-Out Documentation						
19.7.1.	As-Built and Record Sets of Drawing (6 Sets)						
19.8.	Final Payment						
19.9.1.	Contractors Final Payment						
19.9.2.	A/E's Final Payment						
19.10.	Project Close-Out Phase Deliverables Checklist						
S.O.W. Reference	S.O.W. Specific Requirements						

shall be completed by the Design Consultant and i he DPMC the status of all the deliverables require				sion to
Consultant Signature		Date	 	

February 7, 1997 **Rev.**: January 29, 2002

Responsible Group Code Table

The codes below are used in the schedule field "GRP" that identifies the group responsible for the activity. The table consists of groups in the Division of Property Management & Construction (DPMC), as well as groups outside of the DPMC that have responsibility for specific activities on a project that could delay the project if not completed in the time specified. For reporting purposes, the groups within the DPMC have been defined to the supervisory level of management (i.e., third level of management, the level below the Associate Director) to identify the "functional group" responsible for the activity.

CODE	DESCRIPTION	REPORTS TO ASSOCIATE DIRECTOR OF:
CM	Contract Management Group	Contract Management
CA	Client Agency	N/A
CSP	Consultant Selection and Prequalification Group	Technical Services
A/E	Architect/Engineer	N/A
PR	Plan Review Group	Technical Services
CP	Construction Procurement	Planning & Administration
CON	Construction Contractor	N/A
FM	Financial Management Group	Planning & Administration
OEU	Office of Energy and Utility Management	N/A
PD	Project Development Group	Planning & Administration

	Description	Rspn Weeks	
<pr< td=""><td><proj></proj></td><td></td><td></td></pr<>	<proj></proj>		
Design	u		
CV3001	Schedule/Conduct Predesign/Project Kick-Off Mtg.		
CV3020	Prepare Program Phase Submittal	# W	
CV3021	Distribute Program Submittal for Review		
CV3027	Prepare & Submit Project Cost Analysis (DPMC-38)		
CV3022	Review & Approve Program Submittal	5	
CV3023	Review & Approve Program Submittal		
CV3024	Review & Approve Program Submittal		
CV3025	Consolidate & Return Program Submittal Comments		
CV3030	Prepare Schematic Phase Submittal	## W	
CV3031	Distribute Schematic Submittal for Review		
CV3037	Prepare & Submit Project Cost Analysis (DPMC-38)		
CV3032	Review & Approve Schematic Submittal		
CV3033	Review & Approve Schematic Submittal		
CV3034	Review & Approve Schematic Submittal	8	
CV3035	Consolidate & Return Schematic Submittal Comment		
CV3040	Prepare Design Development Phase Submittal	¥	
CV3041	Distribute D. D. Submittal for Review		
CV3047	Prepare & Submit Project Cost Analysis (DPMC-38)		
CV3042	Review & Approve Design Development Submittal		
CV3043	Review & Approve Design Development Submittal		
CV3044	Review & Approve Design Development Submittal		
CV3045	Consolidate & Return D.D. Submittal Comments		
CV3050	Prepare Final Design Phase Submittal	YB	
CV3051	Distribute Final Design Submittal for Review		
CV3052	Review & Approve Final Design Submittal	8	
CV3053	Review & Approve Final Design Submittal	æ	
CV3054	Review Final Design Submitl for Constructability	830	
NOTE:		DBCA - TEST Sheet 1 of 3	
Ref. Sco	Refer to section "IV Project Schedule" of the Scope of Work for contract phase durations.	Bureau of Design & Construction Services	IT 'A'
			T7 T7

The Content of the	Activity	\															ſ
A contract of the Design Submitted	A		Rspn						Weeks								
Submit Permit Application Documents CM	CV3055	Review & Approve Final Design Submittal	₹												THE PERSON NAMED IN		THE REAL PROPERTY.
Subtrait Permit Application Documents AB Subtrait Permit Application Documents & Subtrait Permit Acquisition CM Subtrait Bidding Cost Analysis (DPMC-38) CM Subtrait Bidding Cost Cost Cost Cost Cost Cost Cost Cost	CV3056	Consolidate & Return Final Design Comments	₹		N 10 10								0 00 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0		500 5 50 5 50 5 50		
Contact Cont	CV3060	Prepare & Submit Permit Application Documents	ΑE		the second										2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2	v v	
Construction Contracts Construction Contra	CV3068	Prepare & Submit Bidding Cost Analysis (DPMC-38)	CM														1 0
Avarage Construction Contracts CA	Plan R	Review-Permit Acquisition											100				
A ward	CV4001	Review Constr. Documents & Secure UCC Permit	R.				20 Mg	Color	Email							· · · · ·	en e i
Id Clearance	CV4010	Provide Funding for Construction Contracts	CA		25 Mo 100 26 400 Mo 27 27 Mo 27 27 Mo 27 27 Mo 27 27 Mo 27 27 Mo 27 Mo 2		10 10 10 10 10 10 10 10 10 10 10		* 00 0							2	- 100 FB
Start Contracts CP Start	CV4020	Secure Bid Clearance	Æ					7 to 100 to 1									
Bids & Prep. Recommendation for Award CP Bids & Prep. Recommendation CP Bids & Prep. Recom	Advert	ise-Bid-Award															
Bids & Prep. Recommendation for Award CM Bids & Prep. Recommendation for Award CM Bids & Prep. Recommendation for Award CM onstruction Contracts/Issue NTP CM Start/Contract Work (25%) Complete COM Sconstruction Submittals COM Each Procurement Item Ordered COM Sconstruction Submittals COM Sconstruction Sub	CV5001	Advertise Project & Bid Construction Contracts	B								2 0				A SECURE	· · ·	
Bids & Prep. Recommendation for Award AE	CV5010	Open Construction Bids	ප		100 m											5	COCCES TO ACT AND AND MACHINE AND ACT AND AND AND
Bids & Prep. Recommendation for Award AE onstruction Contracts/Issue NTP CP onstruction Star/Ussue NTP CM Star/Contract Work (25%) Complete CON construction Submittals CON construction Submittals CON c Submit Shop Drawings CON Work (50%+) Complete CON Porture of the same durations. Bureau of Design & Construction Services	CV5011	Evaluate Bids & Prep. Recommendation for Award	₹						155			A			20 TO 10 TO	10 Me	
Start Contract Start	CV5012	Evaluate Bids & Prep. Recommendation for Award	AE		0.00								E E E E E E E E E E E E E E E E E E E			1	27 A 63
CP CP	CV5014	Complete Recommendation for Award	ප									**************************************		10 10 mm		202	A 18
Start/Contract Work (25%) Complete	CV5020	Award Construction Contracts/Issue NTP	පි														
Start/Contract Work (25%) Complete	Constr	uction			2 m												
Preconstruction Meeting Begin Preconstruction Meeting Begin Preconstruction Meeting Begin Preconstruction Submittals CON Freque & Submit Shop Drawings Complete Construction Submittals CON Contract Work (50%+) Complete Contract Work (75%) Complete Contract Work (75%) Complete Contract Work (75%) Complete Contract Work (50%+) Complete Contract Work (75%) Complete Contract Work (75%) Complete Contract Work (75%) Complete Contract Work (15%) Complete CON	CV6000	Project Construction Start/Issue NTP	S											**************************************		100 to	10 mm
Preconstruction Meeting Begin Preconstruction Submittals Longest Lead Procurement Item Ordered CON Complete Construction Submittals Contract Work (30%+) Complete Contract Work (30%+) Complete Contract Work (75%) Complete Contract Work for contract phase durations. © Primavera Systems, Inc. Bureau of Design & Construction Services	CV6001	Contract Start/Contract Work (25%) Complete	CON													6	
Begin Preconstruction Submittals Longest Lead Procurement Item Ordered Lad Time for Longest Lead Procurement Item Ordered Con Prepare & Submit Shop Drawings Complete Construction Submittals Contract Work (50%+) Complete Contract Work (50%+) Complete Contract Work (50%+) Complete Contract Work (50%) Complete Contract Work (75%) Complete Contract Work for contract phase durations. © Primavera Systems, Inc. Bureau of Design & Construction Services	CV6002	Preconstruction Meeting	CM	1 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2		4 A P	** ** ** ** ** ** ** ** ** ** ** **						M. Burn	FN 0	A SA IN		or to the
Longest Lead Procurement Item Ordered CON Lead Time for Longest Lead Procurement Item CON Prepare & Submit Shop Drawings Complete Construction Submittals Complete Construction Submittals Complete Construction Submittals Contract Work (50%+) Complete Contract Work (50%+) Complete Contract Work (75%) Complete Contract Work (75%) Complete Contract Work (75%) Complete Contract Work for contract phase durations. © Primavera Systems, Inc. Bureau of Design & Construction Services	CV6003	Begin Preconstruction Submittals	CON								TATION NO. 1	- 1- 1- 1- 1- 1- 1- 1- 1- 1- 1- 1- 1- 1-	TO BE SENTEN		n contra		
Lead Time for Longest Lead Procurement Item CON Prepare & Submit Shop Drawings Complete Construction Submittals Configuration Submit Shop Drawings Contract Work (50%+) Complete Contract Work (50%+) Complete Contract Work (75%) Complete Contract Work (75%) Complete Contract Work (75%) Complete Contract Work (75%) Complete Contract Work for confract phase durations. © Primavera Systems, Inc. Bureau of Design & Construction Services	CV6004	Longest Lead Procurement Item Ordered	CON								- 1000 0						
Prepare & Submit Shop Drawings Complete Construction Submittals Roughing Work Start Roughing Work Start Perform Roughing Work Contract Work (50%+) Complete Contract Work (50%+) Complete Contract Work (75%) Complete Contract Work (75%) Complete Contract Work (75%) Complete Contract Work (75%) Complete Contract Work for contract phase durations. © Primavera Systems, Inc. Bureau of Design & Construction Services	CV6005	Lead Time for Longest Lead Procurement Item	CON														
Complete Construction Submittals Roughing Work Start Contract Work (50%+) Complete Contract Work (50%+) Complete Contract Work (75%) Complete Contract Work (75%) Complete Contract Work (75%) Complete Contract Work (75%) Complete CON Contract Work for contract phase durations. © Primavera Systems, Inc. Bureau of Design & Construction Services	CV6006	Prepare & Submit Shop Drawings	N OS		(C)	PROFILE				Market	1 04 DE				1001 1001 1001 1001 1001 1001 1001 100	200 00	179 KJ
Roughing Work Start CON Perform Roughing Work CON Contract Work (30%+) Complete CON Contract Work (75%) Complete CON Contract Work (75%) Complete CON It to section "IV Project Schedule" of the e of Work for contract phase durations. Bureau of Design & Construction Services © Primavera Systems, Inc. Bureau of Design & Construction Services	CV6007	Complete Construction Submittals	NOS			3 0078	5 % % • • • • • • • • • • • • • • • • • • •		* 1 m 1 m		0 0 0 0 0 0 0 0						i de la constantina della cons
Perform Roughing Work Contract Work (30%+) Complete Contract Work (75%) Complete Contract Work (75%) Complete Contract Work (75%) Complete Contract Work (75%) Complete CON DBCA-TEST Bureau of Design & Construction Services © Primavera Systems, Inc.	CV6011	Roughing Work Start	NOS		20 100 100 100 100 100 100 100 100 100 1									A PERSONAL PROPERTY OF THE PERSONAL PROPERTY O	2 0 100 0000000 2 (40 440 2 000 0		
Contract Work (50%+) Complete Contract Work (75%) Complete Contract Work (75%) Complete Contract Work (75%) Complete CON Contract Work (75%) Complete CON Bureau of Design & Construction Services PBUFFAULTION PBCA-TEST Bureau of Design & Construction Services	CV6012	Perform Roughing Work	NO NO						274-96-27-4-4-						2 50 2 500 4 500 2 100 1 100 100 1 100 100	THE REP. TO.	N N
Contract Work (75%) Complete CONTRACT DBCA - TEST Bureau of Design & Construction Services © Primavera Systems, Inc.	CV6010	Contract Work (50%+) Complete	CON								- 10-						
Contract Work (75%) Complete r to section "IV Project Schedule" of the e of Work for contract phase durations. © Primavera Systems, Inc.	CV6013	Longest Lead Procurement Item Delivered	CON														0 10 015 H3 VI 100 000
r to section "IV Project Schedule" of the e of Work for contract phase durations. © Primavera Systems, Inc.	CV6020	Contract Work (75%) Complete	CON			40 A					to enter the second of the sec						\$ 145 6 1861 Ad
r to section "IV Project Schedule" of the e of Work for contract phase durations. © Primavera Systems, Inc.	NOTE		DBCA - TEST						Sheet 2 of								
© Primavera Systems, Inc.	Ref	er to section "IV Project Schedule" of the pe of Work for contract phase durations.		ureau of Desig	in & Co	nstructi	on Ser	vices			X		2		-		
		© Primavera Systems, Inc.								4	7				4	4	

Description Style	Activity													VIV											32 33 34	
Interior Finishes Surface CON Substantial Completion CON Substantial Completion Declared CON Substantial Completion Declared Completion Declared Completion Declared Completion Declared Completion Declared Completion Contract Complete Deferred Contraction Complete Completion Declared Contraction Complete Contract Contraction Contract Contraction Contract Contraction Contract Contraction Contract Completion Declared Completion Completion Declared Completion Declared Completion Declared Completion Completion Declared Declared Declared Declared Declared Declared Declared Declared Dec	1	Description Description	Rspn	THE REAL PROPERTY.		Transian.	HIMMIN		THE REAL PROPERTY.	THE REAL PROPERTY.		THE REAL PROPERTY.	THE REAL PROPERTY.					MANAGER			THE STATE OF THE S					
Interior Finishes Start	10010	Rougning work Complete	CON	9 19		A 17		N 4 80		7 19 2 19 2 19				- 1/ 1						4 - 6000 0 00 0 00			200 200 200 200 200 200	0 -0 2 -05 		7 1 2 1
Install merior Finishes COM Comman Work to Exbandial Completion Comman Work for Construction Complete Complete Deferred Pennel List/Seasonal Activities Complete Completion Contracts Complete Complete Completion Declared Complete Completion Declared Complete Completion Declared Complete Complete Complete Complete Complete Complete Complete Complete Complete Complete Comple	CV6021	Interior Finishes Start	CON		especial	7 (1) (1) (2) (2) (2)	note of the second seco			to the com-			6 / 26 6 (100) 100 6 (100) 100 6 (100) 100				n si os	100 MIT 100		a 4 5	** ** **		20 86 2 6 62 6 63 6 7 8	or a	10 (5) 8 00 (6) 00 (6)	
Subtantial Completion Subtantial Completion Subtantial Completion Subtantial Completion Subtantial Completion Complete Deferred Panel List/Seasonal Activities Toyler Construction Complete Close Out Construction Complete Close Out AE Contract Completion Declared Completion	CV6022	Install Interior Finishes	CON					Commence			-						-	1		1 1 1 1				8 8		
Substantial Completion Declared Complete Deferred Punch List/Seasonal Activities Complete Deferred Punch List/Seasonal Activities Project Construction Complete Close Out Activities Close Out Activit	CV6030	Contract Work to Substantial Completion	CON	i de de Es des										encentra E Sa		· · · · ·								3 00 0 2 2	entra di la la constanti la con	
Complete Deferred Purch List/Seasonal Activities CON Project Construction Complete CM Close Out Construction Complete CM Close Out A/B Contract Complete CM Construction Contract Complete CM Construction Contract CM Construction Contract CM Construction Contract CM Construction Construction Conference CM CM Construction Conference CM CM CM CM CM CM CM C	CV6031	Substantial Completion Declared	CM	a a s Su		~ ~ .	2 10 1 2 10 1 2 10 1 2 1 ₀ 1	10 00 0 10 00 0			0.00 M 0	- w	en en	20 R 20 K		4 4	e E ad tota so tota so			*				U N 1		
Project Construction Complete Close Out CAR Contracts Construction Complete Construction Contracts Construction Contract Project Completion Declared Construction Contract Project Completion Declared Construction Contract Construction Contract Construction Contract plase durations.	CV6075	Complete Deferred Punch List/Seasonal Activities	CON	er gegen eran ak Ela ad			* 1, 19 * 3, 19 * 3, 19	× 2000						0 00 00 0 00 00 0 0 00				and and an					**************************************		1 00 00 1 1 0 10 1 0 10 1 0 10	
Close Out Construction Contracts CM CM Project Completion Declared CM Project Contract Completion Declared CM CM CM CM CM CM CM	CV6079	Project Construction Complete	CM				entities of			ANTENE O	20 au 5		1000 1 1000 100 1					- 100 A.A. - 401 A.A.A.					A S		0 (M) (0 M (0 10 M (0 10	
Construction Contracts Complete	CV6080	Close Out Construction Contracts	₹					1.							#			#		1					1	\Box
Cooper Completion Declared CM CM CM CM CM CM CM C	CV6089	Construction Contracts Complete	5								en in er						200 100 000 200 400 40 30 40 40	F 90 90					Commission of	B 8 :		
E: Bureau of Design & Construction Services Bureau of Design & Construction Services	CV6090	Close Out A/E Contract	Č			100 II I	POSTON P. B. S. POSTON P. POSTON P. POSTON P.		en en e	an more	74. 04 4 24. 44. 4	100 mm 1	The second	ne of a	10. 100 ·		5 (50000) (100000) (100000)				2 12	er order total	n an nac (a) (a)	1 10 1 100 1 100		
r to section "IV Project Schedule" of the e of Work for contract phase durations. Bureau of Design & Construction Services	CV6092	Project Completion Declared	₹			******											**************************************				***					
r to section "IV Project Schedule" of the e of Work for contract phase durations.					*											4										
*******	NOTE Refe	: er to section "IV Project Schedule" of the ne of Work for contract nhace durations	DBCA - TE		reau	l Jo	 esign	3 u	Cons	truct	ion) Servi	ces	Sheet	30f3			5				[_	-	
© Primavera Systems, Inc.		© Primavera Systems, Inc.														7	3		=			┥.		Y		








EXHIBIT 'B'






OXYGEN INLET LOCATION









AIR HANDLER UNIT



COMPRESSOR MOTOR



MAIN DISTREBUTION PANEL

Vineland Developmental Center

Regulations Governing Contractors and Their Employees

The Administration is charged with the responsibility of custody welfare of our consumers. All non-State employees are responsible and must comply with the following rules for their own protection as well as the safety of our clients.

- No workman is to fraternize with our clients. Any difficulties encountered are to be reported directly to the Facility Engineer.
- 2. Do not give or take any item to or from the clients.
- 3. Lock all cars and trucks and demobilize all equipment when left unattended.
- 4. Issuance of keys to contractors and their employees, carries with it the responsibility for exercising the utmost care in their security.
- 5. No photographs are to be taken without the express permission of the Facility Engineer.
- All tools and equipment must be secured before leaving at the end of the day.
 Should equipment such as scaffolding and ladders be required to remain up overnight, the contractor will obtain prior permission of the facility engineer.
- 7. Warning lights must be displayed at all dangerous area overnight.
- 8. No firearms, hunting knives, ammunition or other articles of this kind are to be brought on facility grounds.
- 9. No alcoholic beverages are permitted on facility grounds.
- 10. Institutional fire regulations shall be strictly adhered to. Questions are to be directed to the Facility Engineer.
- 11. The 15 M.P.H. speed limit will be strictly adhered to.
- 12. Personal items and supplies must be stored or kept in a central location designated for your use.
- 13. All excavation will be protected as directed by the Facility Engineer and those across roads must be covered with plates.
- 14. It is the responsibility of the contractor to secure all tools and equipment.
- 15. All contractors must report to the Engineer's Office when arriving on grounds during normal business hours.

- 16. No littering is permitted. Please help to keep the institution clean. Our clients are curious and may ingest what you discard.
- 17. There will be no materials, supplies or equipment shipped to the site without the express permission of the Facility Engineer. It is the sole responsibility of the contractor to have someone on site to receive any item shipped for work to be performed. The facility cannot be held liable for loss of material or receipt of items.
- 18. The use of telephones is strictly prohibited. The contractor must supply their own means of communication, or use available payphones.

The administration will regretfully take action against anyone violating these regulations. Thank you for your cooperation to keep our residents safe.

Contractor	Date	Bruce D. Mondgock, Engineer In Charge of Maintenance